

**RECORD OF DECISION**

SDMS Document



95449

**Operable Unit Three**

**Rockaway Borough Wellfield Superfund Site**

**Rockaway, Morris County, New Jersey**

**United States Environmental Protection  
Agency**

**Region II**

**September 2006**

500001

## DECLARATION STATEMENT

### RECORD OF DECISION

#### SITE NAME AND LOCATION

Rockaway Borough Wellfield Superfund Site (EPA ID# NJD980654115) Rockaway Borough, Morris County, New Jersey, Operable Unit 3.

#### STATEMENT OF BASIS AND PURPOSE

This decision document presents the Selected Remedy to address the contamination source for the Wall Street/East Main Street (WS/EM Source Area), which is Operable Unit (OU3) of the Rockaway Borough Wellfield Site in Rockaway Borough, Morris County, New Jersey. This Selected Remedy was chosen in accordance with the requirements of the Comprehensive Environmental Response, Compensation, and Liability Act, as amended (CERCLA), and to the extent practicable, the National Oil and Hazardous Substances Pollution Contingency Plan (NCP). This decision is based on the Administrative Record file for the Site.

The State of New Jersey concurs with the Selected Remedy.

#### ASSESSMENT OF THE SITE

The remedial action selected in this Record of Decision (ROD) is necessary to protect public health, welfare, or the environment from actual or threatened releases of hazardous substances from the Site into the environment.

#### DESCRIPTION OF THE SELECTED REMEDY

The Selected Remedy described in this document involves the active remediation of the contaminated groundwater WS/EM Source Source Area at the Site. A previous ROD, signed on September 30, 1991, selected a remedy for contaminated groundwater associated with this source area, as operable unit 2 (OU2). This decision document addresses the source of the WS/EM groundwater contamination (OU3). A fourth operable unit (OU4) will address the contamination source related to the Klockner and Klockner contaminated groundwater (K&K Source Area). The Klockner and Klockner (K&K) contaminated groundwater is being remediated by a Potentially Responsible Party, also as part of OU2.

The major components of the Selected Remedy include:

- Excavation of an estimated 40 cubic yards of soil contaminated with volatile organic compounds;
- Off-site treatment and/or disposal; and
- Soil Vapor Extraction (SVE), if necessary to augment the soil excavation.

#### DECLARATION OF STATUTORY DETERMINATIONS

##### Part 1: Statutory Requirements

The selected remedial action is protective of human health and the environment, complies with federal and state requirements that are legally applicable or relevant and appropriate to the remedial action, and is cost-effective. The Selected Remedy utilizes permanent solutions and alternative treatment (or resource recovery) technologies to the maximum extent practicable.

##### Part 2: Statutory Preference for Treatment

Excavation with off-site treatment and/or disposal, with SVE of the source area as necessary, satisfies the statutory preference for treatment as a principal element of the remedy (i.e., reduces the toxicity, mobility, or volume of hazardous substances, pollutants, or contaminants as a principal element through treatment).

##### Part 3: Five-Year Review Requirements

Because this remedial action will not result in hazardous substances, pollutants, or contaminants remaining on the Site above levels that allow for unrestricted and unlimited exposure, the five-year review will not apply to this action related to the WS/EM Source Area.

## ROD DATA CERTIFICATION CHECKLIST

The following information is included in the Decision Summary section of this ROD. Additional information can be found in the Administrative Record for this site.

- Chemicals of concern and their respective concentrations may be found in the "Site Characteristics" section.
- Current and reasonably-anticipated future land and groundwater use assumptions are discussed in the "Current and Potential Future Site and Resources Uses" section.
- Baseline risk represented by the chemicals of concern may be found in the "Summary of Site Risks" section.
- A discussion of the goals of the cleanup and of cleanup levels for chemicals of concern may be found in the "Remedial Action Objectives" section.
- A description of the cleanup alternatives evaluated and estimated capital, annual operation and maintenance (O&M), and total present worth costs are discussed in the "Description of Alternatives" section.
- Key factors that led to selecting the remedy (i.e., how the Selected Remedy provides the best balance of tradeoffs with respect to the balancing and modifying criteria, highlighting criteria key to the decisions) may be found in the "Comparative Analysis of Alternatives" and "Statutory Determinations" sections.
- A discussion of source area materials constituting principal threats may be found in the "Principal Threat Waste" section.

  
\_\_\_\_\_  
George Pavlou, Director  
Emergency and Remedial Response Division

  
\_\_\_\_\_  
Date

Record of Decision  
Decision Summary

Operable Unit Three

Rockaway Borough Wellfield Site  
Rockaway Borough, Morris County  
New Jersey

United States Environmental Protection Agency

Region II

September 2006

## TABLE OF CONTENTS

Site Name, Location, and Description	1
Site History and Enforcement Activities	2
Highlights of Community Participation	4
Scope and Role of Response Action	4
Summary of Site Characteristics	5
Current and Potential Future Site And Resource Uses	12
Summary of Site Risks	12
Remedial Action Objectives	17
Description of Remedial Alternatives	18
Comparative Analysis of Alternatives	21
Principal Threat Waste	26
Selected Remedy	27
Statutory Determinations	27
Documentation of Significant Changes	29

### Appendices

Appendix I - Figures

Appendix II - Tables

Appendix III - Responsiveness Summary

Appendix IV - Administrative Record Index

Appendix V - NJDEP's Letter of Concurrence

## SITE NAME, LOCATION, AND DESCRIPTION

The Rockaway Borough Wellfield Site is located in Rockaway Borough in Morris County, New Jersey (Figure 1). Rockaway Borough is situated in the center of Morris County, approximately 10 miles north of Morristown and 20 miles northwest of Newark in the north-central portion of the state.

The Wall Street/East Main Street (WS/EM) Source Area (Figure 2) is a portion of the larger Rockaway Borough Wellfield Superfund Site. The Rockaway Borough Wellfield Superfund Site includes three municipal water supply wells (Nos. 1, 5, and 6), which are located off Union Street in the eastern section of the Borough. The groundwater at the municipal water supply wells is contaminated primarily with tetrachloroethene (PCE) and trichloroethene (TCE). Based on prior investigations, the suspected sources of the TCE and PCE contamination included industrial operations within the Borough, including the Klockner and Klockner (K&K) facility, and a dry cleaning operation (Lusardi's Cleaners, Inc.).

Low concentrations of metals including chromium, lead and nickel are also present in WS/EM Source Area soil. A former foundry, the M. Hoagland Union Foundry, operated in the WS/EM Source Area and is a potential source of the metals detected in soils. Metals, however, are not associated with the groundwater contamination at the site. Additionally, the human health risk assessment for the WS/EM Source Area did not find unacceptable risks or hazards associated with exposure to metals in soil.

The WS/EM Source Area is primarily comprised of a commercial area in the heart of downtown Rockaway Borough, Morris County, New Jersey. The remedial investigation and feasibility study (RI/FS) study area for OU3 encompassed businesses located in this area including dry cleaning, auto body repair, auto service and repair, banking, hardware, hair dressing, convenience stores, and food establishments. Borough Police and Fire Departments, Memorial Park, and municipal parking lots are also located within the area studied for the OU3 RI/FS.

The developed portions of the WS/EM Source Area are covered by impervious surfaces including asphalt roadways and

driveways, concrete building slabs and sidewalks, and asphalt parking areas. A limited number of small, fragmented areas of exposed soils comprising suburban parkland, mowed lawns, ballfields and playgrounds, and fragmented areas of forested habitats, occur in the developed area of the WS/EM Source Area.

## **SITE HISTORY AND ENFORCEMENT ACTIVITIES**

Investigations, conducted by the New Jersey Department of Environmental Protection (NJDEP) at the Rockaway Borough Wellfield site since 1980, indicated the presence of volatile organic compounds (VOCs), primarily trichloroethylene (TCE) and tetrachloroethylene (PCE) in the groundwater. Several inorganic compounds including chromium, lead, and nickel were also identified. This contamination, which has affected the wellfield, emanates from multiple source areas within Rockaway Borough.

The presence of VOC contamination caused the Borough of Rockaway to construct a three-bed granular activated carbon adsorption treatment system to treat the municipal water supply. The system began operating in July 1981, treating approximately 900,000 gallons per day of raw water pumped from the Borough's wells. Overall, the system has reduced the VOC contaminant concentrations in the municipal water supply to levels meeting the state and federal drinking water standards.

In December 1982, the site was placed on the United States Environmental Protection Agency (EPA) National Priorities List of Superfund Sites. Under a cooperative agreement with EPA, NJDEP initiated an RI/FS to determine the nature and extent of contamination. The RI/FS utilized a soil gas survey that identified three potential source areas within the Borough, although the horizontal and vertical extent of groundwater and soil contamination was not defined. As part of the study, remedial alternatives were developed and evaluated to address the known contamination.

On September 29, 1986, at the conclusion of the NJDEP RI/FS, EPA signed a ROD for the first operable unit. The ROD called for the continued use of the existing carbon treatment system operated by Rockaway Borough, and directed the commencement of a supplemental RI/FS in order to

identify the contaminant source(s), further delineate the full extent of the contamination, and evaluate additional remedial action alternatives to address those sources.

Based on these findings, EPA initiated a Phase II RI/FS to identify the contaminant sources, further delineate the full extent of contamination and evaluate remedial action alternatives to address the sources of contamination.

Some of the major findings and conclusions of the Phase II RI/FS were as follows:

- PCE groundwater contamination emanating from the WS/EM Source Area was impacting municipal wells No. 1 and 5;
- TCE groundwater contamination emanating from the K&K property was impacting municipal well No. 6;
- Groundwater contamination from VOCs was present in the Roned Realty Industrial Area (an industrial park in Rockaway Borough).

On September 30, 1991, EPA issued a ROD selecting a remedy for OU2, the VOC plumes in groundwater that are migrating to the Borough Wellfield. The selected remedy called for the remediation of the K&K and WS/EM groundwater plumes, and no further action in relation to the Roned Realty Industrial Area. The selected remedy included groundwater extraction and treatment by air stripping and chemical precipitation; reinjection of the treated groundwater to the aquifer; and appropriate environmental monitoring to ensure the effectiveness of the remedy.

The OU2 ROD also directed further investigation to identify the source areas for the groundwater, and further delineate the full extent of contamination. In 2003, EPA began an RI/FS with respect to the WS/EM Source Area. An RI/FS for the K&K Source Area, which will be addressed as OU4, is also underway.

Two Remedial Designs (RDs) have been completed to address the groundwater contamination (OU2). In 1994, EPA entered into a Consent Decree with Alliant Techsystems (ATK), a Potentially Responsible Party (PRP) for the K&K groundwater plume, requiring ATK to undertake the RD for both contaminated groundwater plumes that comprise OU2 of the Rockaway Borough Wellfield site, and to perform the

Remedial Action (RA) for the K&K contaminated groundwater plume. ATK has completed the RA for the K&K plume and the groundwater treatment system is currently operational.

EPA is presently conducting RA activities for the WS/EM contaminated groundwater plume.

#### **HIGHLIGHTS OF COMMUNITY PARTICIPATION**

The RI/FS Report and the Proposed Plan for OU3 of the Rockaway Borough Wellfield Site were released to the public for comment on August 11, 2006. These two documents were made available to the public as part of the administrative record maintained at EPA's Records Center, a copy of which is located at the Rockaway Borough Free Public Library. The notice of availability for these two documents was published in the Morris County Daily Record on August 11, 2006. A public comment period on the documents was held from August 11, 2006 to September 11, 2006. In addition, a public meeting was held on August 23, 2006. At this meeting, representatives from NJDEP and EPA were available to answer questions about the contamination at the WS/EM Source Area and the remedial alternatives that were evaluated. EPA's response to the comments and questions received during this period is included in the Responsiveness Summary, which is part of this ROD.

#### **SCOPE AND ROLE OF RESPONSE ACTION**

As with many Superfund sites, the problems at the Rockaway Borough Wellfield Site are complex. As a result, EPA has organized the remedial work into four operable units. This ROD addresses the third of four operable units for this Site.

- OUI was developed to protect public health by providing a reliable supply of safe, potable water to those consumers currently dependent on the Rockaway Borough Wellfield. A ROD for OUI was signed in 1986 requiring the continuation of their activated carbon treatment system and to continue to attempt to identify the contaminant source(s), further delineate the full extent of contamination, and evaluate additional remedial action alternatives to address those sources.

- OU2 addresses the contaminated groundwater that is impacting the Rockaway Borough Wellfield. The OU2 ROD selected a pump and treat system to capture and treat the most contaminated groundwater before it reaches the Wellfield.
- OU3 addresses the remediation of the identified contaminant source in the soil at the WS/EM Source Area that is adversely impacting the groundwater. This action addresses the principal threats posed by the conditions at WS/EM Source Area.
- OU4 will address the remediation of the identified contaminant source in the soil at the K&K Source Area. An RI/FS is currently underway with respect to OU4.

#### **SUMMARY OF SITE CHARACTERISTICS**

The RI for the WS/EM Source Area portion of the Rockaway Borough Wellfield Site was initiated in June 2003 to identify the source and extent of soil contamination. The RI Report, finalized in May 2005, concluded that data collected during the RI field investigation indicate that the WS/EM Source Area soils are contaminated at levels that warranted further evaluation in an FS.

The nature and extent of contamination was assessed as part of the Site evaluation. Due to historic operations, such as dry cleaning, EPA determined that areas of the Site had the potential to be contaminated with PCE and other constituents. The RI Site Reconnaissance included the surveying of site areas for buried materials and possible source areas using geophysical survey techniques. In addition, the sampling of soil gas, shallow soils and subsurface soils was performed to delineate the nature and extent of potential contamination in the soils.

#### **Data Collection and Analyses**

An on-site mobile laboratory analyzed soil gas samples from vadose zone soils for select volatile organics. Analyzed compounds included TCE, PCE, 1,1-dichloroethene (DCE), cis-1,2-DCE, 1,1-dichloroethane (DCA), 1,1,1-trichloroethane (TCA), chloroethane, and vinyl chloride. A gas chromatograph, equipped with an electron capture detector

and Flame Ionized Detector, was used during on-site analysis of the vapor samples.

The soil samples were analyzed by off-site laboratories for Target Compound List (TCL) VOCs and select metal constituents (chromium, lead, and nickel), as per the EPA Contract Laboratory Program (CLP) Statements of Work (SOWs) OLM04.3 and ILM04.1, respectively. Soil samples were also analyzed for hexavalent chromium, following SW-846 Method 7196A. In addition, six soil cores from the 4 to 8 feet below ground surface (bgs) interval, one each from locations S-03 through S-08 (see Figure 3), were analyzed for the following geotechnical parameters: total porosity, dry bulk density, volumetric water content, natural water content, specific gravity, grain size, and organic carbon.

### **Previous Sampling Investigation**

EPA performed a site-wide RI from 1990 to 1991. During this investigation, 17 subsurface soil samples were collected from 5 soil borings and 10 monitoring well boring locations. Soil samples were collected using split-spoon samplers. Auger refusal and poor recovery limited the number of samples collected per location. The soil samples were analyzed through the EPA CLP for TCL VOCs, SVOCs, pesticides and PCBs, and inorganics, and the data results were validated by certified personnel.

Of the samples collected during the earlier RI, only one soil sample was obtained from within the OU3 RI/FS study area, from a depth of 6 to 8 feet bgs. No VOCs were detected in the soil sample, and the lead, chromium and nickel detected were at low concentrations.

### **Contaminant Source Investigation**

#### Soil Sampling Information

An evaluation of historical information was performed to determine potential contaminant source areas. Aerial photographs dating from the 1940s to the 1990s were reviewed in order to acquire a representative understanding of property developments. The results of additional historical record searches were included as part of the Stage 1A Cultural Resources Investigation Report and Archeological Monitoring Report.

During the records review, dry cleaning companies (i.e., Lusardi's Cleaners, Rockaway Cleaners) and auto service/repair shops (i.e., R&R Friendly Service, H&L Auto Repair, Mirror Image Auto Body, Mikron Auto Body) were found to be potential past and current users of chlorinated solvents such as PCE and/or TCE. Historical usage by companies other than these was not discovered.

### Geophysical Survey

A geophysical survey was conducted at the WS/EM Source Area in August 2003, to examine subsurface conditions and delineate possible areas of subsurface contamination. In general, the results showed many areas with buried metallic objects, including subsurface pipes or other utilities (e.g., linear anomalies in Municipal Parking Lots #1 & #2).

The survey indicated that different fill materials may have been used in the WS/EM Source Area, as the baseball field in Memorial Park had higher conductivity soils than the playground portion. In the northeastern portion of the survey area (the baseball field and area to the northwest), an area of increasing metallic component in the deeper subsurface was noted. This area is at least 100 feet in length and 70 feet in width and trends approximately northeast-southwest. This feature may continue out of the surveyed area to the northwest and/or northeast, and may be a reinforced concrete pad or a large area of metallic debris.

The former Morris Canal was not apparent in the survey. This is probably due to the large quantity of utilities that are now present within the canal footprint. Any potential conductivity anomaly from the former canal is most likely overshadowed by the presence of utilities and the disparate fill materials used to bring the canal to its current grade.

The results of the geophysical survey did not provide any specific information that would identify potential source areas.

### Soil Gas Survey

The contaminant of concern detected during the soil gas survey at elevated levels was PCE. PCE was generally present throughout the WS/EM Source Area, with detected

concentrations ranging from 0.002 micrograms per liter (ug/L) to 9,700 ug/L. An isoconcentration contour map was developed for PCE in the soil gas samples collected at approximately 5 feet bgs, utilizing the mobile laboratory results, and presents the potential horizontal extent of soil gas contamination. An area of potential concern (i.e., greater than 100 ug/L) is indicated in the vicinity of 2 Wall Street, and this area was enlarged. In-situ soil gas from location SG01B-MP-5 (southern portion of Municipal Parking Lot #2, north of 2 Wall Street) contained the maximum concentration (i.e., 9,700 ug/L) of PCE. Other elevated values in this area include 340 ug/L (SG01-MP, to the north); 670 ug/L (SG03-LB, to the south); and 430 ug/L (SG04-LB, to the southeast). These four locations were also sampled at a deeper depth interval (either 8 or 10 feet bgs). For the two Municipal Parking Lot #2 samples (SG01-MP and SG01B-MP-10), PCE concentrations decreased with depth (i.e., to 230 ug/L and 460 ug/L, respectively).

The concentration of PCE in the two soil gas locations installed in the basement of 2 Wall Street, SG03-LB and SG04-LB, increased to 790 ug/L and 670 ug/L, respectively, in the 8 and 10-foot bgs samples, respectively.

The central area with elevated PCE soil gas concentrations was investigated further during soil boring activities. Based on the lack of significant amounts of PCE in the soil gas samples, further activities were not performed in the areas to southeast (Rockaway Cleaners, Mirror Image Auto Body, H&L Auto Repair, and R&R Friendly Service), or southwest (Mikron Auto Body).

#### **SOIL INVESTIGATION**

To determine potential sources and to obtain an understanding of the extent of the soils contamination at the WS/EM Source Area, sampling of the surface, shallow subsurface and deep subsurface soil occurred during the field investigation.

##### **Surface Soils**

Surface soils (i.e., 0 to 1 foot bgs) were collected from each of the 17 boring locations, along with two duplicate samples (for a total of 19 soil samples). Surface soils showed constituents present in the background soil locations (i.e., S-01, S-10 and D-01) (Figure 3).

## Volatile Organic Compounds

Eleven individual VOCs were detected in the surface soils. A majority of these constituents (i.e., 9 of the 11; or 82 percent) were present at concentrations less than their respective most conservative criteria values evaluated in the Baseline Human Health Risk Assessment for the WS/EM Source Area (BHHRA). However, PCE was present in 10 of the 19 (53 percent) surface soil samples.

Two VOCs, benzene and PCE, occurred above most conservative criteria values evaluated in the BHHRA for the WS/EM Source Area. The only exceedance concentration of benzene (90 micrograms per kilogram (ug/kg)) was detected in boring D-03 (Figure 3). This value is three times greater than benzene's most conservative criteria value, BHHRA for the WS/EM Source Area, of 30 ug/kg. As D-03 is located in Municipal Parking Lot #2, the exceedance of benzene may be related to vehicle fuels (such as gasoline) being released/spilled in this area.

PCE occurred at concentrations exceeding its most conservative criteria value evaluated in the BHHRA for the WS/EM Source Area, (i.e., 60 ug/kg) in surface soil samples from S-05 (950 ug/kg), S-05A (12,000 ug/kg), S-06 (62 ug/kg), and D-04 (14,000 ug/kg). Lower concentrations of PCE were present in five other locations (i.e., detected range: 4 to 49 ug/kg). PCE was not detected in any of the three background locations. The more elevated concentrations of PCE in surface soil are present in the central portion of the WS/EM Source Area, including in the vicinity of the elevated soil gas occurrences. Two areas of elevated concentrations are shown, in the vicinity of S-05, S-05A and S-06, and around D-04. The S-05/S-05A/S-06 area is relatively bounded on the northeast (S-05B), southwest (S-02/S-03) and northwest (S-04) by locations with PCE less than its most conservative criteria value evaluated in the BHHRA for the WS/EM Source Area. The D-04 "hot spot" exceedance is also relatively bounded to the northwest (S-07), north (D-03) and east (S-08). Supplemental sampling in April 2006 further determined the horizontal and vertical extent of contamination for the Municipal Parking Lot #2 as well as the parking lot of 21 Maple Avenue.

## Metals

Low concentrations of metals including chromium, lead and nickel are also present in WS/EM Source Area soil. A former foundry, the M. Hoagland Union Foundry, operated in the WS/EM Source Area and is a potential source of the metals detected in soils. Metals, however, are not associated with the groundwater contamination at the site. Additionally, the human health risk assessment for the WS/EM Source Area did not find unacceptable risks or hazards associated with exposure to metals in soil.

## Subsurface Soils

Shallow subsurface soils (i.e., 1 to about 10 feet bgs) were collected from ten locations (S-01 through S-10; Figure 3), while deeper subsurface soils (i.e., about 8 to 42 feet bgs) were collected from five locations (D-01 through D-05). A total of 46 subsurface soil samples and 2 duplicate samples were analyzed, and summaries of the detected constituents for all subsurface soil depth intervals are provided for background.

## Volatile Organic Compounds

Ten individual VOCs were detected in the subsurface soils. Seven of these constituents (or 70 percent) were present at concentrations less than their respective most conservative criteria values evaluated in the BHHRA for the WS/EM Source Area, although detected concentrations ranged up to 1,100 ug/kg (acetone in the 2 to 4-foot bgs interval of S-05A). Frequencies of detection ranged between 2 percent (i.e., one occurrence; for ethylbenzene, styrene, and xylenes) and 44 percent (i.e., 21 occurrences; for PCE). For the subsurface soils, the three VOC constituents present at concentrations that were greater than their respective most conservative criteria values evaluated in the BHHRA for the WS/EM Source Area were benzene, methylene chloride, and PCE.

Both benzene and methylene chloride were present at exceedance concentrations in location D-03 (at 8 to 10 feet bgs). These two constituents were present at 72 ug/kg and 68 ug/kg, respectively, which are greater than their criteria values evaluated in the BHHRA for the WS/EM Source Area of 30 ug/kg and 20 ug/kg. The surface soil sample from D-03 also contained an exceedance level of benzene,

and the exceedance of benzene in this area may be related to fuel residuals at this boring location (i.e., Municipal Parking Lot #2).

PCE was detected at concentrations greater than its criteria value evaluated in the BHHRA for the WS/EM Source Area in four depth interval samples from three boring locations. PCE exceedances included: 510 ug/kg at 6 to 8 feet bgs in S-03; 730 ug/kg at 8 to 10 feet bgs in S-03; 64 ug/kg at 8 to 10 feet bgs in S-05; and 260 ug/kg at 2 to 4 feet bgs in S-05A. The potential horizontal extent of PCE in the subsurface soils across the entire WS/EM Source Area was contoured based on the maximum concentration detected at a sampling location. Supplemental sampling in April 2006 further determined the horizontal and vertical extent of contamination in Municipal Parking Lot #2 as well as the parking lot of 21 Maple Avenue.

#### **Metals**

Low concentrations of metals including chromium, lead and nickel are also present in WS/EM Source Area soil. A former foundry, the M. Hoagland Union Foundry, operated in the WS/EM Source Area and is a potential source of the metals detected in soils. Metals, however, are not associated with the groundwater contamination at the site. Additionally, the human health risk assessment for the WS/EM Source Area did not find unacceptable risks or hazards associated with exposure to metals in soil.

#### **Summary**

The nature and extent of soil contamination present in the WS/EM Source Area was assessed through sampling of surface, shallow subsurface and deep subsurface soils. In addition, available historical information and the results of the geophysical and soil gas surveys were evaluated to assist in the determination of potential contaminant source areas.

PCE is the primary contaminant at the WS/EM Source Area. It is present at elevated concentrations in the soil (i.e., up to 14,000 ug/kg in the surface and 730 ug/kg in the subsurface) adjacent to the building at 2 Wall Street and the parking lot at 21 Maple Avenue.

Low concentrations of metals including chromium, lead and nickel are also present in WS/EM Source Area soil. A former foundry, the M. Hoagland Union Foundry, operated in the WS/EM Source Area and is a potential source of the metals detected in soils. Metals, however, are not associated with the groundwater contamination at the site. Additionally, the human health risk assessment for the WS/EM Source Area did not find unacceptable risks or hazards associated with exposure to metals in soil.

## **CURRENT AND POTENTIAL FUTURE SITE AND RESOURCE USES**

### **Site Uses**

The area has been developed by commercial businesses and light industries including bookstores, restaurants, hobby stores, print shop, etc. It is unlikely that this development scenario will change in the future.

### **Resource Uses**

The contaminated soil is located below a municipal parking lot adjacent to 2 Wall Street and a commercial parking lot at 21 Maple Avenue. Contamination may also extend beneath the building at 2 Wall Street.

## **SUMMARY OF SITE RISKS**

Based upon the results of the RI, a baseline risk assessment was conducted to estimate the risks associated with current and future site conditions. The baseline risk assessment process, which is explained below, estimates the human health risk that could result from the contamination at the WS/EM Source Area if no remedial action were taken. The risk assessment found that the risks and hazards associated with soil exposure are within or below EPA's acceptable values. However, the soil concentrations of PCE are above the concentrations that are associated with an adverse impact to groundwater; thus, there is a need to address the soil through a remedial action.

## **HUMAN HEALTH RISK ASSESSMENT**

A four-step process is used for assessing site-related human health risks for a reasonable maximum exposure scenario: Hazard Identification - identifies the contaminants of concern at the site based on several factors such as

toxicity, frequency of occurrence, and concentration. Exposure Assessment - estimates the magnitude of actual and/or potential human exposures, the frequency and duration of these exposures, and the pathways (e.g., ingesting contaminated well-water) by which humans are potentially exposed. Toxicity Assessment - determines the types of adverse health effects associated with chemical exposures, and the relationship between magnitude of exposure (dose) and severity of effect (response). Risk Characterization - summarizes and combines outputs of the exposure and toxicity assessments to provide a quantitative assessment of site-related risks.

### Hazard Identification

EPA conducted a baseline risk assessment to evaluate the potential risks to human health and the environment associated with the WS/EM Source Area in its current state. The risk assessment evaluated many contaminants identified in the soils, but only PCE was identified as a contaminant of potential concern, primarily from direct contact with the contaminated soils. This section of the decision summary will focus on the risks associated with this contaminant in the soils. A summary of the concentrations of PCE in the soils is provided in Table 1. Concentrations of other contaminants found in soil, such as chromium, lead, and nickel, either did not exceed conservative risk-based screening values or exposure to them was not associated with unacceptable risks or hazards.

### Exposure Assessment

EPA's baseline risk assessment addressed the potential risks to human health by identifying several potential exposure pathways by which the public may be exposed to contaminant releases at the WS/EM Source Area under current and future land use conditions. The area is currently used for a commercial purposes, and any future use is expected to be the same. Therefore, the baseline risk assessment focused on health effects for populations typically associated with commercial facilities, including drycleaning workers and future construction workers, who could come in contact with contaminated surface and subsurface soils.

In addition, due to the potential for exposure from inhalation of vapors from the VOCs in the soils by drycleaning workers, customers and users of the gym located

above Lusardi's, this pathway was qualitatively evaluated using risk-based screening values derived according to the methodology found in the 2002 EPA Draft Guidance for Evaluation the Vapor Intrusion to Indoor Air Pathway from Groundwater and Soils. Follow-up vapor intrusion sampling is planned for this area.

For all media, the reasonable maximum exposure, which is the greatest exposure that is likely to occur at the WS/EM Area, was evaluated. Table 2 presents all exposure pathways considered in the risk assessment, and the rationale for the inclusion of each pathway. Exposure media, exposure points, and characteristics of receptor populations are also included.

### Toxicity Assessment

Under current EPA guidelines, the likelihood of carcinogenic (cancer-causing) and noncarcinogenic (systemic) effects due to exposure to WS/EM Source Area chemicals are considered separately. Consistent with EPA guidance, it was assumed that the toxic effects of the site-related chemicals would be additive. Thus, carcinogenic and noncarcinogenic risks associated with exposures to individual contaminants of concern were summed to indicate the potential risks associated with mixtures.

Noncarcinogenic risks were assessed using a hazard index (HI) approach, based on a comparison of expected contaminant intake and safe levels of intake (reference doses and inhalation reference doses). Reference doses (RfDs) and inhalation reference doses (RfDis) have been developed by EPA for indicating the potential for adverse health effects. RfDs and RfDis, which are expressed in units of milligrams per kilogram per day (mg/kg-day), are estimates of daily exposure levels for humans thought to be safe over a lifetime (including sensitive individuals). Estimated intakes of chemicals from environmental media (e.g., the amount of a chemical vapor inhaled) are compared with the RfD or RfDi to derive the hazard quotient for the contaminant in the particular medium. The HI is derived by adding the hazard quotients for all compounds within a particular medium that impact a particular receptor population.

An HI greater than 1 indicates that the potential exists for noncarcinogenic health effects to occur because of site-related exposures. The HI provides a useful reference point

for gauging the potential significance of multiple contaminant exposures within a single medium or across media. The toxicity values, including reference dose and inhalation reference dose for PCE, are presented in Table 3.

Potential carcinogenic risks were evaluated using the cancer slope factors developed by EPA for the contaminants of potential concern. Cancer slope factors (SFs) and inhalation cancer slope factors (SFis) have been developed for estimating excess lifetime cancer risks associated with exposure to potentially carcinogenic chemicals. SFs and SFis, which are expressed in units of  $(\text{mg}/\text{kg}\text{-day})^{-1}$ , are multiplied by the estimated intake of a potential carcinogen, in  $\text{mg}/\text{kg}\text{-day}$ , to generate an upper-bound estimate of the excess lifetime cancer risk associated with exposure to the compound at that intake level. The term "upper bound" reflects the conservative estimate of the risks calculated from the SF or SFi. Use of this approach makes the underestimation of the risk highly unlikely. The SF and SFi values used in this risk assessment for PCE are presented in Table 4.

#### Risk Characterization

The quantitative hazard and risk calculations were based on reasonable maximum exposure scenarios. These estimates were developed by taking into account various conservative assumptions about the likelihood of a person being exposed to these media.

The noncarcinogenic HI for PCE is presented in Table 5. It does not exceed EPA's threshold of 1, and therefore non-cancer health effects are unlikely to occur.

For known or suspected carcinogens, risks are generally expressed as the incremental probability of an individual developing cancer over a lifetime as a result of exposure to a carcinogen. These risks are probabilities that usually are expressed in scientific notation (such as  $1 \times 10^{-4}$ ). An excess lifetime cancer risk of  $1 \times 10^{-4}$  indicates that one additional incidence of cancer may occur in a population of 10,000 people who are exposed under the exposure conditions identified in the BHHRA. As stated in the NCP, the acceptable risk range for site-related exposure is  $10^{-4}$  to  $10^{-6}$  (or approximately one in 10,000 to one in one million).

As shown in Table 6, the excess lifetime cancer risk for the current/future drycleaning workers at the WS/EM Source Area is  $7.76 \times 10^{-6}$ , which is within EPA's acceptable range.

Although the risks and hazards associated with the soil exposure via direct contact (ingestion, dermal, and inhalation) are within or below EPA's acceptable values, the soil concentrations of PCE are above the concentrations that are associated with an adverse impact to groundwater. The PCE in soil is a source of groundwater contamination and has contributed to the risks associated with the ingestion of contaminated groundwater. Thus, PCE is a Chemical of Concern (COC) in soil and there is a need to address the soil through a remedial action.

### Uncertainties

The procedures and inputs used to assess risks in this evaluation, as in all such assessments, are subject to a variety of uncertainties. In general, the main sources of uncertainty include:

- environmental chemistry sampling and analysis
- environmental parameter measurement
- fate and transport modeling
- exposure parameter estimation
- toxicological data

Uncertainty in environmental sampling arises in part from the potentially uneven distribution of chemicals in the media sampled. Consequently, there is uncertainty as to the actual levels present. Environmental chemistry analysis error can stem from several sources, including the errors inherent in the analytical methods and characteristics of the matrix being sampled.

Fate and transport modeling is also associated with a certain level of uncertainty. Factors such as the concentrations in the primary medium, rates of transport, ease of transport, and environmental fate all contribute to the inherent uncertainty in fate and transport modeling.

Uncertainties in the exposure assessment are related to estimates of how often an individual would actually come in contact with the chemicals of concern, the period of time over which such exposure would occur, and in the models used

to estimate the concentrations of the chemicals of concern at the point of exposure.

Uncertainties in toxicological data occur in extrapolating both from animals to humans and from high to low doses of exposure, and from the difficulties in assessing the toxicity of a mixture of chemicals. These uncertainties are addressed by making conservative assumptions concerning risk and exposure parameters throughout the assessment. As a result, the risk assessment provides upper-bound estimates of the risks to populations near the WS/EM Source Area, and is highly unlikely to underestimate actual risks related to the WS/EM Source Area.

More specific information concerning public health and environmental risks, including a quantitative evaluation of the degree of risk associated with various exposure pathways, is presented in the risk assessment report.

Actual or threatened releases of hazardous substances from this WS/EM Source Area, if not addressed by implementing the response action selected in the ROD, may present an imminent and substantial endangerment to the public health, welfare, or the environment.

#### Qualitative Ecological Risk Assessment

A Screening Level Ecological Risk Assessment (SLERA) was performed for the WS/EM Source Area. The SLERA determined that based on the majority of the observed concentrations being comparable to background or below screening level benchmark values and the lack of usable terrestrial habitat for ecological receptors at the WS/EM Source Area, risks to ecological receptors are deemed to be low. Therefore, ecologically based screening criteria are not presented and will not be utilized to assist in the interpretation of the nature and extent of soil contamination at the WS/EM Source Area.

#### **REMEDIAL ACTION OBJECTIVES**

Remedial Action Objectives (RAOs) are specific goals to protect human health and the environment. These objectives are based on available information and standards such as applicable or relevant and appropriate requirements (ARARs) and risk-based levels established in the risk assessment.

The overall remediation goal for the site is to protect human health and the environment. An RAO has been identified to mitigate the potential risks associated with the WS/EM Source Area.

#### Soil

The RAO for the contaminated soil at the WS/EM Source Area is:

- Reduce the potential for further migration of PCE from the contaminated soil into groundwater.

The remediation goal for PCE in soil was identified from the New Jersey Impact to Groundwater Soil Criteria and is 1 mg/kg.

#### DESCRIPTION OF REMEDIAL ALTERNATIVES

CERCLA requires that each remedial alternative be protective of human health and the environment, be cost effective, comply with other statutory laws, and utilize permanent solutions and alternative treatment technologies and resource recovery technologies to the maximum extent practicable. In addition, CERCLA includes a preference for the use of treatment as a principal element for the reduction of toxicity, mobility or volume of hazardous substances.

CERCLA requires that if a remedial action is selected that results in hazardous substances, pollutants, or contaminants remaining at a site above levels that allow for unlimited use and unrestricted exposure, EPA must review the action no less often than every five years after initiation of the action. In addition, institutional controls (e.g., a deed notice, an easement or a covenant) to limit the use of portions of the property may be required. These use restrictions are discussed in each alternative as appropriate. Consistent with expectations set out in the National Contingency Plan (NCP), none of the remedies rely exclusively on institutional controls to achieve protectiveness. The time frames below for construction do not include the time for remedial design or the time to procure contracts.

Remedial alternatives for the WS/EM Source Area are presented below.

**Alternative S-1: No Action**

Estimated Capital Cost: \$0  
Estimated Annual O&M Cost: \$0  
Estimated Present Worth: \$0  
Estimated Construction Time Frame: None

Regulations governing the Superfund program require that the "no action" alternative be evaluated to establish a baseline for comparison. Under this alternative, EPA would take no action at the WS/EM Source Area to prevent the migration of the contamination to the groundwater. Since this alternative would not result in contaminants remaining at the WS/EM Source Area at levels that would not allow for unlimited use and unrestricted exposure, a five-year review would not be required. This alternative would result in the continued contamination of the groundwater.

**Alternative S-2: Limited Action**

Estimated Capital Cost: \$27,000  
Estimated Annual O&M Cost: \$0  
Estimated Present Worth: \$0  
Estimated Construction Time Frame: None

The Limited Action Alternative would include implementation of administrative controls such as a deed notice. The deed notice, or comparable administrative controls, would be implemented to ensure that future activities at the WS/EM Source Area would be performed with knowledge of the WS/EM Source Area conditions. Since this alternative would not result in contaminants remaining at the WS/EM Source Area at levels that would not allow for unlimited use and unrestricted exposure, a five-year review would not be required. This alternative would result in the continued contamination of the groundwater.

**Alternative S-3: In-Situ Remediation (SVE) and Hot-Spot Excavation with Off-Site Treatment and/or Disposal**

Estimated Capital Cost: \$410,000  
Estimated Annual O&M Cost: \$0  
Estimated Present Worth: \$410,000  
Estimated Construction Time Frame: 1 year  
Estimated Time to Achieve RAO: 2 years

This alternative would include in-situ remediation via soil vapor extraction (SVE). SVE would be used to remediate PCE in the unsaturated (vadose) zone soil. To implement SVE, a vacuum is applied to the soil through a series of wells to induce the controlled flow of air to remove VOCs from the soil. The captured vapors are then treated to applicable air standards. The estimated area of PCE-impacted soil that would be addressed, based on information provided in the RI Report and the April 2006 Focused Field Sampling, would be 195 square feet.

A hot-spot excavation would occur in parallel with the SVE system to remove approximately 20 cubic yards of PCE-contaminated soil in a parking area at 21 Maple Avenue.

The excavated soils would be transported off site for treatment, as needed, and disposed of in accordance with federal and state regulations. Upon completion of contaminated soil removal, the excavation would be backfilled and compacted, and the surface would be restored. Both the SVE and excavation would remove contaminated soil and meet the remediation goal of 1 mg/kg, and post-excavation sampling would confirm that the criterion has been met.

Because this alternative would be expected to achieve the remediation goal and would not leave hazardous substances, pollutants or contaminants at the site above levels that would not allow for unlimited use and unrestricted exposure, a five-year review would not be required.

**Alternative S-4: Excavation with Off-Site Treatment and/or Disposal with SVE**

Estimated Capital Cost: \$320,000

Estimated Annual O&M Cost: \$0

Estimated Present Worth: \$320,000

Estimated Construction Time Frame: 3 to 6 months

Estimated Time to Achieve RAO: 6 months

In this alternative, PCE-contaminated soils would be excavated. The estimated volume of impacted soil, based on information in the RI report, is approximately 40 cubic yards, excluding contamination that may be located beneath the 2 Wall Street building.

The excavated soils would be transported off site for treatment, as needed, and disposed of in accordance with federal and state regulations. Upon completion of contaminated soil removal, the excavation would be backfilled and compacted, and the surface would be restored. Excavation would remove contaminated soil and meet the remediation goal of 1 mg/kg, and post-excavation sampling would confirm that the criterion has been met.

If physical removal is not feasible for the soil under the 2 Wall Street building, an SVE system may be utilized to address the remaining soil contamination. The capital costs for this alternative reflect the use of an SVE system.

Because this alternative would be expected to achieve the remediation goal and not leave hazardous substances, pollutants or contaminants remaining at the site above levels that would not allow for unlimited use and unrestricted exposure, a five-year review would not be required.

#### COMPARATIVE ANALYSIS OF ALTERNATIVES

In selecting the remedies, EPA considered the factors set out in CERCLA Section 121, 42 U.S.C. § 9621, by conducting a detailed analysis of the viable remedial alternatives pursuant to the NCP, 40 CFR § 300.430(e)(9) and OSWER Directive 9355.3-01. The detailed analysis consisted of an assessment of the individual alternatives against each of nine evaluation criteria and a comparative analysis focusing upon the relative performance of each alternative against those criteria.

*Threshold Criteria* - The first two criteria are known as "threshold criteria" because they are the minimum requirements that each response measure must meet in order to be eligible for selection as a remedy.

1. **Overall Protection of Human Health and the Environment**  
*Overall protection of human health and the environment addresses whether or not a remedy provides adequate protection and describes how risks posed through each exposure pathway (based on a reasonable maximum exposure scenario) are eliminated, reduced, or controlled through treatment, engineering controls, or institutional controls.*

Alternatives S-1 and S-2 would provide protection of human health since there is no unacceptable human health risk associated with the soil. However, they would not be protective of the environment since the contamination would continue to migrate into the groundwater. Alternatives S-3 and S-4 would provide protection of human health and the environment by eliminating, reducing, or controlling risk through the removal and/or treatment of contaminated material. Alternatives S-3 and S-4 would achieve the remediation goal at the completion of the excavation and/or treatment.

Because the "no action" alternative (S-1) and the "limited action" alternative (S-2) are not protective of the environment, they were eliminated from consideration under the remaining eight criteria.

**2. Compliance with applicable or relevant and appropriate requirements (ARARs)**

Section 121(d) of CERCLA, 42 U.S.C. § 9621(d), and 40 CFR §300.430(f)(1)(ii)(B) require that remedial actions at CERCLA sites at least attain legally applicable or relevant and appropriate federal laws and state environmental or facility siting laws, collectively referred to as "ARARs", unless such ARARs are waived under CERCLA Section 121(d)(4).

Applicable requirements are those cleanup standards, standards of control, and other substantive requirements, criteria, or limitations promulgated under federal environmental or state environmental or facility siting laws that specifically address a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstance found at a CERCLA site. Only those state standards that are identified by a state in a timely manner and that are more stringent than federal requirements may be applicable. Relevant and appropriate requirements are those cleanup standards, standards of control, and other substantive requirements, criteria, or limitations promulgated under federal environmental or state environmental or facility siting laws that, while not "applicable" to a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstance at a CERCLA site, address problems or situations sufficiently similar to those encountered at the CERCLA site that their use is well-suited to the particular site. Only those state standards that are identified in a

timely manner and are more stringent than federal requirements may be relevant and appropriate.

Compliance with ARARs addresses whether a remedy will meet all of the applicable or relevant and appropriate requirements of other federal and state environmental statutes or provides a basis for invoking a waiver.

Actions taken at any Superfund site must meet all ARARs or provide grounds for invoking a waiver of these requirements. These include chemical-specific, location-specific, and action-specific ARARs. There are no chemical-specific ARARs for soil. The New Jersey Impact to Groundwater Soil Criteria are not promulgated regulations, so they are not ARARs but TBCs. However, EPA has identified the Impact to Groundwater Soil Cleanup Criterion for PCE of 1 mg/kg as a remediation goal. Alternatives S-3 and S-4 would meet EPA's PCE remediation goal for the contaminated soils.

Location-specific ARARs would not be triggered for any of the alternatives. However, should the remediation area expand to the former Morris Canal, National Register of Historical Places requirements would be triggered.

Alternatives S-3 and S-4 would attain action-specific ARARs for the contaminated soils, which would include RCRA transportation and disposal requirements.

**Primary Balancing Criteria** - The next five criteria are known as "primary balancing criteria". These criteria are factors with which tradeoffs between response measures are assessed so that the best option will be chosen, given site-specific data and conditions.

### **3. Long-term Effectiveness and Permanence**

Long-term effectiveness and permanence refers to the ability of a remedy to maintain reliable protection of human health and the environment over time, once cleanup goals have been met. It also addresses the magnitude and effectiveness of the measures that may be required to manage the risk posed by treatment residuals and/or untreated wastes.

Alternatives S-3 and S-4 both permanently remediate the ongoing source of groundwater contamination. Alternative

S-3 uses limited excavation and *in-situ* treatment to reduce contaminant mass in the vadose zone. Alternative S-4 uses excavation to remove the contaminant mass from the WS/EM Source Area with the contingency to use *in-situ* treatment should physical removal be infeasible.

Alternatives S-3 and S-4 are both permanent remedies and effective in the long-term.

#### 4. Reduction of Toxicity, Mobility, or Volume of Contaminants through Treatment

*Reduction of toxicity, mobility, or volume through treatment refers to a remedial technology's expected ability to reduce the toxicity, mobility, or volume of hazardous substances, pollutants or contaminants at the site.*

Alternative S-3 would reduce contaminant toxicity, mobility, and volume through removal and treatment of PCE. PCE would be adsorbed onto granular activated carbon (GAC) and treated at an off-site facility. Alternative S-4 would reduce the mobility of contamination through removal of contaminated soil and disposal at an off-site facility. If treated, the toxicity and volume of contamination would also be reduced.

#### 5. Short-term Effectiveness

*Short-term effectiveness addresses short-term risks to the community, workers and the environment during the construction and implementation of the remedial alternatives, and the effectiveness and reliability of protective and mitigative measures.*

Alternative S-3 would present short-term risks to the community relating to potential inhalation exposure, but those risks would be mitigated by engineering controls and air monitoring. Risks relating to potential inhalation exposure by workers would be mitigated by air monitoring and a health and safety program.

Alternative S-4 would present short-term risks to the community relating to excavation and handling of contaminated soil. This potential exposure would be mitigated with the use of dust suppression, restricted site access, and air monitoring. Risks relating to potential inhalation exposure by workers would be mitigated by dust suppression, a health and safety program, and air monitoring.

## 6. Implementability

Implementability addresses the technical and administrative feasibility of a remedy from design through construction and operation. Factors such as availability of services and materials, administrative feasibility, and coordination with other governmental entities are considered.

Alternative S-3 (and possibly Alternative S-4 if the SVE is needed) would be somewhat difficult to implement because of limited available space to install a treatment building. Coordination with state and local governments in addition to property owners and their tenants would be required for placement of soil vapor extraction wells and associated treatment equipment.

Alternative S-4 would be easily implemented using conventional construction equipment and materials; however, some specialized techniques may be required for excavation in close proximity to buildings and would require coordination with state and local governments in addition to property owners and tenants. This alternative could also potentially impact business operations since the excavation would occur near buildings as well. Also it will be necessary to close a portion of a municipal parking lot during excavation work.

## 7. Cost

Includes estimated capital and operation and maintenance costs, and net present-worth values.

The estimated present worth costs of the Alternatives are:

Alternative S-3 (In-situ Treatment and Hot Spot Excavation): the estimated capital costs plus the operating costs needed until remediation goal is achieved are \$410,000.

Alternative S-4 (Excavation with Off-Site Treatment and/or Disposal and SVE): the estimated capital costs and potential operating costs if SVE treatment is needed are \$320,000.

**Modifying Criteria** - The final two evaluating criteria, criteria 8 and 9, are called "modifying criteria" because new information or comments from the state or the community on the Proposed Plan may lead to modification of the

preferred response measure or cause another response measure to be considered.

#### **8. State Acceptance**

State acceptance indicates whether, based on its review of the RI/FS reports and the Proposed Plan, the state supports, opposes, and/or has identified any reservations with the selected response measure.

The State of New Jersey concurred with the Selected Remedy on September 27, 2006. A copy of the state's concurrence letter is included in Appendix V.

#### **9. Community Acceptance**

Community acceptance summarizes the public's general response to the response measures described in the Proposed Plan and the RI/FS reports. This assessment includes determining which of the response measures the community supports, opposes, and/or has reservations about.

EPA solicited input from the community on the remedial alternatives proposed for the WS/EM Source Area of the Rockaway Borough Wellfield Site. The community was generally supportive of EPA's Proposed Plan. Appendix III, The Responsiveness Summary, addresses the comments received at the public meeting.

#### **PRINCIPAL THREAT WASTE**

EPA's findings to date indicate the presence of "principal threat" waste at the WS/EM Source Area. Principal threat wastes are considered source area materials, i.e., materials that include or contain hazardous substances, pollutants or contaminants that act as a reservoir for migration of contamination to groundwater, surface water, or as a source for direct exposure.

Contaminated groundwater is generally not considered to be a "principal threat". However, the contaminated soil in the WS/EM Source Area associated with this Record of Decision is considered to be a "principal threat" to the groundwater. The OU3 remedy will address this "principal threat" via excavation and, if necessary, SVE treatment of the contaminated soil, which acts as a source for groundwater contamination.

## **SELECTED REMEDY**

Based upon consideration of the Site investigation results, the requirements of CERCLA, the detailed analysis of the response measures, and public comments, EPA has determined that Alternative S4 is the appropriate remedy for OU3 of the Site, because it best satisfies the requirements of CERCLA Section 121 and the NCP's nine evaluation criteria for remedial alternatives, 40 CFR § 300.430(e)(9).

The major components of the Selected Remedy include:

- Excavation of an estimated 40 cubic yards of soil contaminated with volatile organic compounds;
- Off-site treatment and/or disposal; and
- Soil Vapor Extraction (SVE), if necessary to augment the soil excavation.

The estimated present worth cost of the Selected Remedy - Alternative S4 is \$320,000.

The selection of Alternative S4 is believed to provide the best balance of trade-offs among the alternatives with respect to the evaluation criteria. EPA and NJDEP believe that the Selected Remedy will be protective of human health and the environment, comply with federal and state requirements that are legally applicable or relevant and appropriate to the remedial action, is cost effective, and will utilize permanent solutions and treatment technologies to the maximum extent practicable.

## **STATUTORY DETERMINATIONS**

As previously noted, CERCLA Section 121(b)(1) mandates that a remedial action must be protective of human health and the environment, cost-effective, and utilize permanent solutions and alternative treatment technologies or resource recovery technologies to the maximum extent practicable. CERCLA Section 121(b)(1) also establishes a preference for remedial actions that employ treatment to permanently and significantly reduce the volume, toxicity, or mobility of the hazardous substances, pollutants, or contaminants at a site. CERCLA Section 121(d) further specifies that a remedial action must attain a degree of

cleanup that satisfies ARARs under federal and state laws, unless a waiver can be justified pursuant to CERCLA Section 121(d)(4). For the reasons discussed below, EPA has determined that the Selected Remedy meets the requirements of CERCLA Section 121.

### Protection of Human Health and the Environment

The Selected Remedy for the WS/EM Source Area will adequately protect human health and the environment through excavation and/or off-site treatment or disposal. Excavation, with possible SVE, of the contaminated soil to the remediation goal of 1 mg/kg PCE will prevent the contaminants from continuing to adversely impact the groundwater, which is being drawn into the Rockaway Borough Wellfield.

### Compliance with ARARs

The action-specific criteria, location-specific criteria, and chemical-specific criteria are shown in Appendix II, Table 7. At the completion of the response action, the Selected Remedy will meet the identified ARARs.

### Cost-Effectiveness

In EPA's judgment, the Selected Remedy is cost-effective and represents reasonable value for the money to be spent. Overall effectiveness was evaluated by assessing three of the five balancing criteria in combination (long-term effectiveness and permanence; reduction in toxicity, mobility and volume through treatment; and short-term effectiveness). Overall effectiveness was then compared to costs to determine cost-effectiveness. The overall effectiveness of the Selected Remedy has been determined to be proportional to the costs, and the Selected Remedy, therefore, represents reasonable value for the money to be spent. The estimated present worth cost of Alternative S4 is \$320,000.

### Utilization of Permanent Solutions and Alternative Treatment Technologies to the Maximum Extent Practicable

EPA has determined that the Selected Remedy represents the maximum extent to which permanent solutions and treatment technologies can be utilized in a practical manner for OU3. EPA has determined that the Selected Remedy provides the

best balance of trade-offs with respect to the five balancing criteria.

The Selected Remedy satisfies the criteria for long-term effectiveness and permanence by removing the VOC contamination from the soil. The selected alternative presents a higher short-term risk different from the other alternatives because of the greater potential for exposure associated with the excavation and transportation of a greater quantity of contaminated soils. However, these short-term risks will be mitigated through implementation of measures such as engineering controls, use of personal protective equipment, safe work practices and perimeter air monitoring. The Selected Remedy is implementable since it employs standard technologies that are readily available.

#### Preference for Treatment as a Principal Element

Based on sampling performed to date, the contaminated soil may not require treatment to meet the requirements of off-site disposal facilities. Therefore, the Selected Remedy may not meet the statutory preference for the use of remedies that employ treatment that reduces toxicity, mobility, or volume as a principal element.

#### Five Year Review Requirement


Because the selected remedy will not result in hazardous substances, pollutants, or contaminants remaining above levels that allow for unlimited use and unrestricted exposure, a five-year review will not be required.

#### **DOCUMENTATION OF SIGNIFICANT CHANGES**

The Proposed Plan for the WS/EM Source Area was released to the public on August 11, 2006. The Proposed Plan identified the preferred alternative for WS/EM Source Area, OU3 of the Site. EPA and NJDEP reviewed all comments received during the 30-day public comment period. Upon review of these comments, EPA and NJDEP determined that no significant changes to the selected remedy as originally identified in the Proposed Plan were necessary.

APPENDIX I



FIGURES



TITLE:  
 SITE LOCATION MAP  
 RECORD OF DECISION  
 ROCKAWAY BOROUGH WELLFIELD RI/FS

DWN:	CTS	DES:	CTS
CHKD:	BS	APPD:	LH
DATE:	9/20/06	REV.:	0

PROJECT NO.:	
FIGURE NO.:	1



**LEGEND**

- APPROXIMATE FOOTPRINT OF THE FORMER MORRIS CANAL
- SITE STUDY AREA BOUNDARY


500038



**TETRA TECH EC, INC.**

**TITLE**  
**STUDY AREA**  
**RECORD OF DECISION**  
**ROCKAWAY BOROUGH WELLFIELD RI/FS - WALL STREET/EAST MAIN STREET SITE**

<b>DRAWN:</b> CTS	<b>DATE:</b> 9/20/06	<b>PROJECT NO.:</b>
<b>CHECKED:</b> BS	<b>REV.:</b> 0	
<b>DESIGNED:</b> CTS	<b>APPROVED:</b> LH	<b>FIGURE NO.:</b> 2



**LEGEND**


Estimated Extent of Excavation

D-03  
22 ● 2003 shallow soil boring location and PCE concentration

S18  
32 ● 2008 shallow soil boring location and PCE concentration

**NOTES:**

1. Concentrations are provided in ug/lg.
2. Non-detects are contoured as 0 ug/lg and posted as "ND."
3. PCE - Tetrachloroethane
4. D - From a diluted sample
5. J - Estimated value
6. ND - Non-detect



500039

**TETRA TECH EC, INC.**

**TITLE:**  
 CONCEPTUAL EXCAVATION AREA  
 RECORD OF DECISION  
 ROCKAWAY BOROUGH WELLFIELD SUPERFUND SITE RI/FS

DWN:	LMB	DATE:	9/20/2008	PROJECT NO.:	
CHKD:	LHH	REV.:	0	FIGURE NO.:	
DEB.:	EEP	APPD:	LHH		3

APPENDIX II

TABLES

**TABLE 1**

**Summary of Chemicals of Concern and  
Medium-Specific Exposure Point Concentrations**

**Scenario Timeframe:** Current/Future  
**Medium:** Soil  
**Exposure Medium:** Lusardi's Backyard Surface Soil

Exposure Point	Chemical of Concern	Concentration Detected		Concentration Units	Frequency of Detection	Exposure Point Concentration (EPC)	EPC Units	Statistical Measure
		Min	Max					
Surface soil	Tetrachloroethene	0.005	12	mg/kg	6/7	12	mg/kg	Max.

Max = Maximum value detected

**Scenario Timeframe:** Current/Future  
**Medium:** Soil  
**Exposure Medium:** Lusardi's Backyard All Soil

Exposure Point	Chemical of Concern	Concentration Detected		Concentration Units	Frequency of Detection	Exposure Point Concentration (EPC)	EPC Units	Statistical Measure
		Min	Max					
Surface soil	Tetrachloroethene	0.001	12	mg/kg	14/20	6.62	mg/kg	99% Cheb.

99% Cheb. = 99% Chebyshev (mean, STD) Upper-confidence limit

**Scenario Timeframe:** Current/Future  
**Medium:** Soil  
**Exposure Medium:** Former Foundry Property Surface Soil

Exposure Point	Chemical of Concern	Concentration Detected		Concentration Units	Frequency of Detection	Exposure Point Concentration (EPC)	EPC Units	Statistical Measure
		Min	Max					
Surface soil	Tetrachloroethene	14	14	mg/kg	1/4	14	mg/kg	Max.

Max = Maximum value detected

**Scenario Timeframe:** Current/Future  
**Medium:** Soil  
**Exposure Medium:** Former Foundry Property All Soil

Exposure Point	Chemical of Concern	Concentration Detected		Concentration Units	Frequency of Detection	Exposure Point Concentration (EPC)	EPC Units	Statistical Measure
		Min	Max					
Surface soil	Tetrachloroethene	0.004	14	mg/kg	2/10	14	mg/kg	Max.

Max = Maximum value detected

**TABLE 2**

**Selection of Exposure Pathways**

Scenario Timeframe	Medium	Exposure Medium	Exposure Point	Receptor Population	Receptor Age	Exposure Route	Onsite/ Offsite	Rationale for Selection/Exclusion of Exposure Pathway			
Current/Future	Soil	Lusardi's Basement Surface Soil	Lusardi's Basement Surface Soil	Maintenance Worker	Adult	Ingestion	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.			
						Dermal	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.			
						Inhalation of Particulates	Onsite	Inhalation of soil particulates from earthen floor during maintenance activities in the Lusardi's Dry Cleaners is not considered to be a significant pathway due to limited potential for ground disturbance and dust suspension in the air.			
						Inhalation of Volatiles	Onsite	No volatile organic compounds were retained as COPCs in this area. Therefore, this indoor air exposure pathway was not quantitatively evaluated. Soil gas samples collected at this exposure point were screened against EPA risk-based criteria.			
		Indoor Air	Dry cleaning Worker	Adult	Inhalation of Volatiles	Onsite	No volatile organic compounds were retained as COPCs in this area. Therefore, this indoor air exposure pathway was not quantitatively evaluated. Soil gas samples collected at this exposure point were screened against EPA risk-based criteria.				
							Recreational User (Gym)	Adult	Inhalation of Volatiles	Onsite	A recreational user works out in the gym on the second floor of Lusardi's Dry- Cleaning. Since no volatile organic compounds were retained as COPCs in the area, this indoor air exposure pathway was not quantitatively evaluated. Soil gas samples collected at this exposure point were screened against EPA risk-based criteria.
											Dry cleaning Customer
		Lusardi's Backyard Soil	Lusardi's Backyard Surface Soil	Dry cleaning Worker	Adult	Ingestion	Onsite	Direct exposure through contact with outdoor surface soil during breaks taken near the Lusardi's Dry Cleaners during the work day was evaluated.			

						Dermal	Onsite	Direct exposure through contact with outdoor surface soil during breaks taken near the Lusardi's Dry Cleaners during the work day was evaluated.
						Inhalation of Particulates	Onsite	Inhalation of soil particles entrained into the ambient air by wind during breaks taken near the Lusardi's Dry Cleaners during the work day was evaluated.
						Inhalation of Volatiles	Onsite	Inhalation of volatile organic compounds released from the soil into the outdoor air during breaks taken near the Lusardi's Dry Cleaners during the work day was evaluated.
				Dry cleaning Customer	Adult	Ingestion	Onsite	No quantitative analysis was performed for a dry cleaning customer since the dry cleaning worker would have greater potential exposure to soil contaminants than the dry cleaning customer.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	
						Inhalation of Volatiles	Onsite	
		Memorial Park Surface Soil	Memorial Park Surface Soil	Park User	Adult	Ingestion	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	
						Inhalation of Volatiles	Onsite	
					Child (0-6)	Ingestion	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	
						Inhalation of Volatiles	Onsite	
					Groundskeeper	Ingestion	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	

						Inhalation of Volatiles	Onsite	
		Former Foundry Property (All Soils)	Indoor Air	Commercial Worker	Adult	Inhalation of Volatiles	Onsite	Inhalation of volatile organic compounds released from the soil into the first floor indoor air of nearby businesses (i.e., Police Station, hairdressers, and scrapbook shop) was qualitatively evaluated using the results from the residential assessment.
					Resident	Adult	Inhalation of Volatiles	Onsite
				Child (0-6)		Inhalation of Volatiles	Onsite	
Future	Soil	Lusardi's Backyard All Soil (surface and subsurface)	Lusardi's Backyard All Soil	Construction Worker	Adult	Ingestion	Onsite	Direct exposure through contact with the surface and subsurface soil that may be disturbed and exposed during future excavation activities at Lusardi's Property was evaluated.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	Inhalation of soil particles entrained into the ambient air by future excavation and construction activity at the Lusardi's Property was evaluated.
						Inhalation of Volatiles	Onsite	Inhalation of volatile organics released from the surface and subsurface soil into the ambient air during future excavation and construction activities at the Lusardi's Property was evaluated.
		Memorial Park All Soil (surface and subsurface)	Memorial Park All Soil	Construction Worker	Adult	Ingestion	Onsite	No COPCs were retained in this area, therefore these exposure pathways were not evaluated.
						Dermal	Onsite	
						Inhalation of Particulates	Onsite	
						Inhalation of Volatiles	Onsite	
		Former Foundry Property All Soil (surface and subsurface)	Former Foundry Property All Soil	Construction Worker	Adult	Ingestion	Onsite	Direct exposure through contact with the surface and subsurface soil that may be disturbed and exposed during future construction activities at the former foundry property was evaluated.
						Dermal	Onsite	
Inhalation of Particulates	Onsite					Inhalation of soil particulates entrained into the ambient air by future excavation and construction activity at the former foundry property was evaluated.		

						Inhalation of Volatiles	Onsite	Inhalation of volatile organic compounds released from the surface and subsurface soil into the ambient air during future excavation and construction activities at the former foundry was evaluated.
--	--	--	--	--	--	-------------------------	--------	---

**Summary of Selection of Exposure Pathways**

The table describes the exposure pathways associated with the soil that were evaluated for the risk assessment, and the rationale for the inclusion of each pathway. Exposure media, exposure points, and characteristics of receptor populations are included.

**TABLE 3**

**Non-Cancer Toxicity Data Summary**

**Pathway: Oral/Dermal**

Chemical of Concern	Chronic/ Subchronic	Oral RfD Value	Oral RfD Units	Absorp. Efficiency (Dermal)	Adjusted RfD (Dermal)	Adj. Dermal RfD Units	Primary Target Organ	Combined Uncertainty /Modifying Factors	Sources of RfD: Target Organ	Dates of RfD:
Tetrachloroethene	Chronic	1.0E-2	(mg/kg-day) <sup>-1</sup>	NA	1.0 E-2	(mg/kg-day) <sup>-1</sup>	Liver	1000	IRIS	04/19/04

**Pathway: Inhalation**

Chemical of Concern	Chronic/ Subchronic	Inhalation RfC	Inhalation RfC Units	Inhalation RfD	Inhalation RfD Units	Primary Target Organ	Combined Uncertainty /Modifying Factors	Sources of RfD: Target Organ	Dates:
Tetrachloroethene	NA	NA	NA	NA	NA	NA	NA	NA	NA

**Key**

NA: No information available

IRIS: Integrated Risk Information System, U.S. EPA

**Summary of Toxicity Assessment**

This table provides non-carcinogenic risk information which is relevant to the contaminants of concern in soil. When available, the chronic toxicity data have been used to develop oral reference doses (RfDs) and inhalation reference doses (RfDi).

**TABLE 4**

**Cancer Toxicity Data Summary**

**Pathway: Oral/Dermal**

Chemical of Concern	Oral Cancer Slope Factor	Units	Adjusted Cancer Slope Factor (for Dermal)	Slope Factor Units	Weight of Evidence/ Cancer Guideline Description	Source	Date
Tetrachloroethene	5.40E-1	(mg/kg/day) <sup>-1</sup>	5.4E-1	(mg/kg/day) <sup>-1</sup>	---	CalEPA	06/03/04

**Pathway: Inhalation**

Chemical of Concern	Unit Risk	Units	Inhalation Slope Factor	Slope Factor Units	Weight of Evidence/ Cancer Guideline Description	Source	Date
Tetrachloroethene	6.0E-3	(mg/m <sup>3</sup> ) <sup>-1</sup>	2.1E-2	(mg/kg-day) <sup>-1</sup>	---	CalEPA	06/03/04

**Key**

NA: No information available  
 CalEPA: California EPA

**Summary of Toxicity Assessment**

This table provides carcinogenic risk information which is relevant to the contaminants of concern in soil. Toxicity data are provided for both the oral and inhalation routes of exposure.

**TABLE 5**  
**Risk Characterization Summary - Noncarcinogens**

<b>Scenario Timeframe:</b>		Current/Future						
<b>Receptor Population:</b>		Drycleaning worker						
<b>Receptor Age:</b>		Adult						
Medium	Exposure Medium	Exposure Point	Chemical of Concern	Primary Target Organ	Non-Carcinogenic Risk			
					Ingestion	Inhalation	Dermal	Exposure Routes Total
Soil	Lusardi's Backyard Surface Soil	Lusardi's Backyard Surface Soil	Tetrachloroethene	Liver	5.87E-4	---	---	5.87E-04
<b>Groundwater Hazard Index Total =</b>								0.00059

**Summary of Risk Characterization - Non-Carcinogens**

The table presents hazard quotients (HQs) for each route of exposure and the hazard index (sum of hazard quotients) for all routes of exposure. The Risk Assessment Guidance for Superfund states that, generally, a hazard index (HI) greater than 1 indicates the potential for adverse non-cancer effects.

**TABLE 6****Risk Characterization Summary - Carcinogens**

Scenario Timeframe: Current/Future  
Receptor Population: Drycleaning worker  
Receptor Age: Adult

Medium	Exposure Medium	Exposure Point	Chemical of Concern	Carcinogenic Risk			
				Ingestion	Inhalation	Dermal	Exposure Routes Total
Soil	Lusardi's Backyard Surface Soil	Lusardi's Backyard Surface Soil	Tetrachloroethene	1.13E-6	6.63E-6	---	7.761E-6
<b>Total Risk =</b>							7.76E-6

**Summary of Risk Characterization - Carcinogens**

The table presents cancer risks (CRs) for each route of exposure and for all routes of exposure combined. The Risk Assessment Guidance for Superfund states that, generally, the acceptable cancer risk range is  $10^{-4}$  to  $10^{-6}$ .

TABLE 7

Selected Standards  
Rockaway Borough Wellfield Site, Soil (OU-3)

Standard, Requirement, Criterion, or Limitation	Citation or Reference	Type	Description	Status	Comments
<b>FEDERAL</b>					
Resource Conservation and Recovery Act (RCRA) - Groundwater Protection Standards	40 CFR 264.94	Chemical specific	Maximum contaminant concentrations for groundwater protection at hazardous waste management facilities	Relevant and Appropriate	Potential ARAR for groundwater cleanup and replacement standard.
Resource Conservation and Recovery Act (RCRA) - Groundwater Protection Standards	40 CFR 264.18	Location specific	Regulates the design, construction, operation and maintenance of hazardous waste management facilities within the 100-year floodplain.	Relevant and Appropriate	Potential ARAR for on-site treatment, storage, or disposal of hazardous waste.
Hazardous Waste Generation	40 CFR 262	Action specific	Specifies requirements for hazardous waste packaging, labeling, manifesting, and storage.	Applicable	Applicable for on-site storage of hazardous waste.
Transportation of Hazardous Waste	40 CFR 263	Action specific	Specifies requirements for transporters of hazardous waste to obtain an EPA identification number, comply with manifest procedures, and spill response.	Applicable	Applicable for the use of transporters for off-site disposal of hazardous waste.
Treatment Storage, and Disposal of Hazardous Waste	40 CFR 264/265	Action specific	Specifies requirements for the operation of hazardous waste treatment, storage, and disposal facilities.	Applicable	Applicable for on-site hazardous waste treatment and storage and disposal activities.
<b>Standard, Requirement, Criterion, or Limitation</b>	<b>Citation or Reference</b>	<b>Type</b>	<b>Description</b>	<b>Status</b>	<b>Comments</b>
Land Disposal Restrictions	40 CFR 268	Action specific	Sets out prohibitions and establishes standards for the land disposal of hazardous waste.	Applicable	Applicable for on-site hazardous waste disposal activities.

500050

Nation Ambient Air Quality Standards -Particulates	40 CFR 50	Action specific	Establishes maximum concentrations for particulates and fugitive dust emissions.	Applicable	Applicable for on-site activities which would generate particulate emissions.
United States Department of Transportation (USDOT) Hazardous Materials Transportation Regulations	49 CFR 171-180	Action specific	Establishes classification, packaging, and labeling requirements for shipments of hazardous materials.	Applicable	Applicable for the preparation and off-site shipment of hazardous materials generated on-site.
EPA Test Methods for Evaluation of Solid Waste	SW-846	Action specific	Establishes primary and secondary NAAQS under Section 109 of the Clean Air Act.	Applicable	Applicable to alternatives that may emit to the air.

**STATE OF NEW JERSEY**

Standard, Requirement, Criterion, or Limitation	Citation or Reference	Type	Description	Status	Comments
Soil Cleanup Criteria	State Guidance	Chemical specific	Identified restricted (non-residential) and unrestricted (residential) soil cleanup guidelines, as well as guidelines for protection of groundwater.	Relevant and Appropriate	Potential TBC for contaminants in on-site soils.
Hazardous Waste Management Regulations	NJAC 7:26G	Action specific	Provides requirements for the generation, accumulation, on-site management, and transportation of hazardous wastes.	Relevant and Appropriate	Potential ARAR for on-site management and disposal of hazardous waste.
Air Quality Regulations	NJAC 7:27	Action specific	Provides requirements applicable to air pollution sources.	Relevant and Appropriate	Potential ARAR for the generation and emission of air pollutants.
Industrial Site Recovery Act	NJSA 13:1K	Action specific	Requires soil remediation standards for human carcinogens in excess of established standards.	Relevant and Appropriate	Potential ARAR for setting soil remediation criteria where NJDEP standards are more stringent.
Soil Erosion and Sediment Control	NJSA 4:24	Action specific	Requires the implementation of soil erosion and sediment control measures for activities disturbing more than 5,000 square feet of surface area of land.	Relevant and Appropriate	Potential ARAR for site activities involving excavation, grading, or other soil disturbance activities.

500051

APPENDIX III

RESPONSIVENESS SUMMARY

**RESPONSIVENESS SUMMARY  
ROCKAWAY BOROUGH WELLFIELD SUPERFUND SITE  
ROCKAWAY, MORRIS COUNTY, NEW JERSEY**

This Responsiveness Summary summarizes the public's comments and concerns regarding the Proposed Plan and preferred cleanup alternatives to address contamination at the Rockaway Borough Wellfield Superfund Site (the Site). This summary also presents the U.S. Environmental Protection Agency's (EPA's) responses to the public's comments and concerns. At the time of the public comment period, August 11, 2006 to September 11, 2006, EPA proposed a preferred alternative for remediating soil at the Site. Subsequently, EPA has considered all comments received and summarized them in this document. Based on the consideration of all comments, EPA has developed a final decision for the selection of a remedial alternative for the Site.

This Responsiveness Summary is divided into the following sections:

I. **BACKGROUND ON COMMUNITY INVOLVEMENT AND CONCERNS:** This section provides the history of the community involvement and interests regarding the Rockaway Borough Wellfield Superfund Site.

II. **COMPREHENSIVE SUMMARY OF MAJOR QUESTIONS, COMMENTS, CONCERNS, AND RESPONSES:** This section contains summaries of oral comments received by EPA at the public meeting. EPA did not receive any written comments on the Proposed Plan during the public comment period.

III. **ATTACHMENTS:** The last section of this Responsiveness Summary provides attachments that document public participation in the remedy-selection process for this Site including:

Attachment A: the Proposed Plan that was distributed to the public for review and comment;

Attachment B: the public notice that appeared in the *The Daily Record* and *The Citizen*;

Attachment C: the EPA Press Release announcing EPA to Remove Contaminated Soil from the Rockaway Borough Wellfield Site; and

Attachment D: the meeting agenda and transcript of the public meeting.

I. **BACKGROUND ON COMMUNITY INVOLVEMENT AND CONCERNS**

- On August 23, 2006, EPA held a public meeting to present the preferred remedial alternative for the Wall Street/East Main Street Area (WS/EM), OU3, at the Rockaway Borough Community Center, Rockaway, New Jersey. Previously,

EPA has held numerous meetings with local officials to update them on the status of the Site. In addition, EPA meets annually at the Site with Congressman Rodney Frelinhuysen and local and state officials to discuss the Site. Although interest in the Site by local residents has been generally low, EPA has provided the community with fact sheets and has scheduled public information sessions on the Site. Additionally, EPA has had public outreach during the residential indoor air sampling events.

## II. SUMMARY OF COMMENTS RECEIVED DURING THE PUBLIC COMMENT PERIOD AND AGENCY RESPONSES

During the August 23, 2006 public meeting, comments from the public touched upon a number of topics of concern to stakeholders including: methods considered for use in remediation of the WS/EM Area; the quality of local drinking water; EPA communication with stakeholders; schedule for remediation activities; road closings; site security; long-term EPA oversight; the plume; identification of the PRP; source of funds for remediation; impact of the local Superfund sites on property values; and prevention of further contamination. A summary of the comments received during the August 23, 2006 public meeting and EPA's responses follows.

### **Methods considered for use in remediation of the WS/EM Area**

1. Comment: A stakeholder asked if EPA had considered use of Ultraviolet (UV) light as a mechanism to destroy chlorinated hydrocarbons at the WS/EM Area. He suggested that if successful, this would be a highly economical method for breaking down chlorinated compounds.

EPA Response: UV oxidation is a treatment process that oxidizes organic compounds by the addition of strong oxidizers and irradiation with UV light. Wide varieties of organic contaminants are susceptible to destruction by UV oxidation, including chlorinated hydrocarbons, such as PCE, which is the contaminant of concern at this Site. However, this technology has only been demonstrated/applied for treatment of water streams and air streams. The application of this technology for the in-situ or ex-situ treatment of contaminated soil, which is the objective of the selected remedy, has not been demonstrated.

2. Comment: One resident asked EPA what type of air monitoring will be used during remediation and what types of protections are in place to prevent exposure of stakeholders to high volumes of vapor during remediation activities? Will random monitoring take place throughout the community?

EPA Response: The preferred remedy consists of a controlled excavation of contaminated soils for the WS/EM Area. The remedial design will develop air

monitoring requirements to ensure that no contaminants are released from the Site above levels that could cause a health concern.

#### **Quality of local drinking water**

3. Comment: A resident expressed concern that local residents had been possibly drinking contaminated water for a long time.

EPA Response: It is a misconception that the citizens of Rockaway Borough are drinking contaminated water. In fact, the drinking water is doubly treated. Carbon treatment of the water was initially installed in 1981 and in 1993 an air stripper was added to enhance the treatment of the water. EPA is currently addressing how to prevent the contaminated groundwater from getting into the drinking water system. This is being done in two ways. First, the potentially responsible parties (PRs) have constructed a groundwater pump and treat system to contain and remediate the contaminated groundwater plume emanating from the Klockner and Klockner groundwater plume area. In addition, EPA is currently preparing to install a groundwater pump and treat system to address the contaminated groundwater plume emanating from the EM/WS groundwater plume area.

#### **EPA communication with stakeholders**

4. Comment: Will EPA publish a newsletter that will keep stakeholders up-to-date with what is happening during remediation activities and will there be publicity planned for when the site is remediated?

EPA Response: EPA periodically issues community updates. EPA will have a public information session prior to the start-up of remedial action activities and EPA can also host additional information sessions focused on specific topics or issues as necessary. Because the Rockaway Borough Wellfield Superfund Site consists of two soil and two groundwater remedial actions, a final construction completion press release will not be issued until all of the remedial actions have been completed.

#### **Schedule for remediation activities**

5. Comment: When will remediation activities begin?

EPA Response: EPA will not have a schedule for remediation until after the remedial design has been completed, which normally takes one to two years.

6. Comment: A stakeholder asked if there is a timeline for the remediation project?

EPA Response: As indicated above, EPA will not have a schedule for remediation until after the remedial design has been completed, however, once initiated, the remedial action activities are anticipated to take three to six months.

7. Comment: A stakeholder expressed concern because nothing has been accomplished in 15 years.

EPA Response: EPA has accomplished a lot in the last 15 years. The second Record of Decision for the site was signed in 1991 and since that time, EPA negotiated Consent Decrees with two Potentially Responsible Parties (PRPs) to address source area and groundwater contamination at the K&K portion of the site, conduct two source area investigations, and ultimately develop a list of alternatives to remediate the WS/EM contaminated source area, which is the subject of this meeting. In addition, during this time period two groundwater extraction and treatment systems have been designed. The first of the groundwater extraction and treatment systems, for the Klockner and Klockner plume, was constructed by Alliant Techsystems, Inc. and has been in operation since January 2006. EPA is presently preparing to initiate construction of the WS/EM Area groundwater extraction and treatment system.

#### **Road Closings**

8. Comment: Will there be road closings to accommodate remediation work? How much of the parking lot will be impeded from public use and for how long?

EPA Response: The parking lot located behind 1 Wall Street will be at least partially closed off during remediation activities and there could be some temporary road closings to allow drill rigs, backhoes, trucks, and other large equipment to be moved in and out of the remediation area. While most of the work should only be short-term, approximately three months or so for excavation, the amount of time needed will depend upon the actual design of the remedy. EPA will continue to coordinate with the Mayor and local police to assure that when activities are scheduled, they will avoid, as much as possible, adding traffic on local roads when school buses and local rush hour traffic are prevalent, etc. EPA does not anticipate nighttime activity because associated noise levels would most likely disturb local residents.

#### **Site security**

9. Comment: Will there be on-site security at the locations of remediation activity?

EPA Response: If it is determined during planning that on-site security is necessary, then EPA will make appropriate arrangements. EPA will coordinate with local police to determine if there is a need for additional security. As normal precautions, keys will be removed from large equipment so that no one may interfere with the equipment after working hours.

### **Long-term EPA oversight**

10. Comment: Is there a requirement for a periodic or five-year progress report on all Superfund sites?

EPA Response: No. Five year reviews are only required if contaminants are left on-site at levels that would not allow for unlimited use and unrestricted exposure. In addition, it is EPA policy to conduct five year reviews at sites where it will take longer than five years to reach an unrestricted clean-up goal. At the Rockaway Borough site, a policy review will be conducted for the groundwater remedies because it will take longer than five years to reach drinking water standards. However, a five year review will not be needed for the WS/EM soil remedy since the cleanup will allow for unrestricted exposure.

### **Plume**

11. Comment: A stakeholder requested a definition of a plume.

EPA Response: A plume is any visible or measurable discharge of a contaminant from a given point of origin. In the case of the Rockaway Borough Wellfield Site, this refers to the amount of contamination in groundwater that was traced back to the specific source areas.

12. Comment: A resident asked if the contamination that is off-gassing or vaporizing is coming off of the plume?

EPA Response: The vapor intrusion pathway that EPA is evaluating at some local residences could have come from the contaminated groundwater.

13. Comment: A stakeholder asked if the Klockner and Klockner plume was completely cleaned at this point?

EPA Response: The groundwater treatment system has been operating since January 2006 and is still a long way from the restoration of the groundwater to New Jersey Drinking water standards. The 1991 ROD estimated that it would take 30 years to complete the groundwater cleanup.

14. Comment: A local resident asked how long the plume has been present at the Site and for how long has it been harming the drinking water?

EPA Response: EPA responded that it was difficult to know this since some of the procedures now used for testing for contaminants did not exist prior to 1980. However, the Borough of Rockaway installed a carbon treatment system in 1981 to

treat the contaminants in the drinking water and, following an agreement with a PRP in 1993, an air stripper was installed to enhance the treatment of the water.

#### **Identification of the PRP**

15. Comment: A stakeholder asked if a PRP has been identified for the Klockner and Klockner plume and for the WS/EM Area and has there been any litigation or payment settlements? He asked the identities of the parties that settled.

EPA Response: The responsible parties at the Klockner and Klockner plume are the owners of the property and they are investigating the soil. The tenants at the time the soil was contaminated are the ones who are cleaning up the groundwater (Alliant Techsystems, Inc.). There was never a defined responsible party for the WS/EM Area. There were a few small parties that settled, by contributing money, because they did not have the ability to fund the cleanup of WS/EM. EPA is funding this cleanup.

#### **Source of funds for remediation**

16. Comment: A stakeholder ask why cleanup responsibility is based upon a responsible party's ability to pay when there is a tax that companies pay that created the Superfund?

EPA Response: The Superfund was a tax that was levied on corporations and industries that created or processed hazardous waste. That tax expired in the mid-1990s and therefore, the funding now comes from general tax revenues appropriated to EPA. When a site is discovered that requires the removal of contamination, EPA will first attempt to identify responsible parties and offer them an opportunity to perform the cleanup under EPA oversight. If they do not have the financial wherewithal, then EPA funds the cleanup.

17. Comment: What part of the cleanup will Rockaway Borough be responsible for paying?

EPA Response: Rockaway Borough will not be responsible to pay for any of this cleanup.

#### **Impact of local Superfund sites on property values**

18. Comment: How will the Superfund status of this site affect property values in Rockaway Borough?

EPA Response: The Site has been on the Superfund National Priorities List since 1980 and there has been no indications that property values were adversely affected.

EPA's experience at other sites indicate that the presence of a Superfund site in a neighborhood appears to have little impact on property values.

**Prevention of further contamination**

19. Comment: A resident asked if measures were being taken to prevent further contamination in the area?

EPA Response: Industries in the United States must follow strict guidelines for hazardous waste. They must document what they do with waste. They must show that they have properly handled whatever chemicals they utilize for their operations. EPA monitors industries to assure they are following the guidelines.

**Other site related issues**

20. Comment: A local citizen asked what kinds of properties were selected for vapor intrusion testing in basements and homes in the area of the Klockner and Klockner plume.

EPA Response: EPA identified residences that could potentially be impacted by vapors from the two groundwater plumes based on their proximity to the groundwater plumes. EPA wrote letters to 30 local residents requesting access to sample their homes, but only received replies from 17 residents. In both the Klockner and Klockner Area and EM/WS Area, EPA initially took a representative sample from every other home. EPA evaluated the data and has since conducted follow-up sampling at some of the residents. Based on the results of the sampling, EPA will perform a more extensive study in early winter 2006.

**ATTACHMENT A  
PROPOSED PLAN**

Superfund Program  
Proposed Plan

U.S. Environmental Protection Agency  
Region II



Rockaway Borough Wellfield  
Superfund Site

August 2006

**EPA ANNOUNCES PROPOSED PLAN**

This Proposed Plan identifies the Preferred Alternative for addressing soils at one of the source areas at the Rockaway Borough Wellfield Superfund Site and provides the rationale for this preference. This particular source area is known as the Wall Street/East Main Street (WS/EM) area. The U.S. Environmental Protection Agency (EPA) evaluated a number of remedial measures to address contaminated soil and as explained below, the Preferred Alternative is Excavation with Off-Site Treatment and/or Disposal with Soil Vapor Extraction.

The Proposed Plan includes summaries of all the soil cleanup alternatives evaluated for use at this site. EPA, the lead agency for site activities, issues this document. The New Jersey Department of Environmental Protection (NJDEP) is the support agency. EPA, in consultation with NJDEP, will select a final remedy for the site after reviewing and considering all information submitted during the 30-day public comment period. EPA, in consultation with NJDEP, may modify the Preferred Alternative or select another response action presented in this Plan based on new information or public comments. Therefore, the public is encouraged to review and comment on all the alternatives presented in this Proposed Plan.

EPA is issuing this Proposed Plan as part of its public participation responsibilities under Section 117(a) of the Comprehensive Environmental Response, Compensation and Liability Act of 1980, as amended (CERCLA) and Section 300.430(f) of the National Oil and Hazardous Substances Pollution Contingency Plan (NCP). This Proposed Plan summarizes information that can be found in greater detail in

Dates to remember:

**MARK YOUR CALENDAR**

**PUBLIC COMMENT PERIOD:**

**August 11 – September 11, 2006**

EPA will accept written comments on the Proposed Plan during the public comment period.

**PUBLIC MEETING: August 23, 2006 - 7:00 pm**

EPA will hold a public meeting to explain the Proposed Plan. EPA will also accept oral and written comments at the meeting. The meeting will be held at **Rockaway Borough Community Center, 21-25 Union Street, Rockaway, New Jersey**. Prior to the start of the meeting, EPA will be available from 6:00 p.m. to 7:00 p.m. to answer questions.

**For more information, see the Administrative Record at the following locations:**

U.S. EPA Records Center, Region II  
290 Broadway, 18<sup>th</sup> Floor  
New York, New York 10007-1866  
(212)-637-3261  
Hours: Monday-Friday – 9:00 am to 5:00 pm

Rockaway Borough Free Public Library  
82 East Main Street  
Rockaway, NJ 07866  
(973) 627-5709  
Hours: Monday & Wednesday – 12:00 to 8:00 PM  
Tuesday, Thursday and Friday – 10:00 am to 8:00 pm

the Operable Unit 3 (OU3) Remedial Investigation/Feasibility Study (RI/FS) reports and other site-related documents contained in the Administrative Record file for this site. EPA encourages the public to review these documents to gain a more comprehensive understanding of the Rockaway Borough Wellfield Site and the Superfund process.

## SITE HISTORY

The Rockaway Borough Wellfield Site is located in Rockaway Borough in Morris County, New Jersey (See Figure 1). Rockaway Borough is situated in the center of Morris County, approximately 10 miles north of Morristown and 20 miles northwest of Newark in the north-central portion of the state.

Rockaway Borough is approximately 2.1 square miles in size and is located in the central part of Morris County, New Jersey. It is bordered to the north and west by Rockaway Township and to the east and south by Denville Township. Land use in the Borough is a mix of commercial, industrial, and residential. The Rockaway Borough Wellfield Superfund Site includes three municipal water supply wells (nos. 1, 5, and 6), which are located in the eastern section of the Borough. The municipal wells range in depth from 54 to 84 feet below ground surface (bgs) and are located in a glacial aquifer. EPA designated the aquifer a sole source aquifer for the Borough and surrounding communities. The wells supply potable water to approximately 11,000 people.

In 1981, a granular carbon treatment system was installed by the Borough after contamination was discovered in the municipal water supply system. The principal contaminants found in the glacial aquifer include volatile organic compounds (VOCs), primarily tetrachloroethene (PCE) and trichloroethene (TCE). In 1993, an air stripping system was added to improve the treatment of the contaminated groundwater and reduce operating costs.

The WS/EM Area is a portion of the larger Rockaway Borough Wellfield Superfund Site. The sources of the TCE and PCE contamination include industrial operations within the Borough, including the Klockner and Klockner (K&K) facility, and a dry cleaning operation.

In 1985, the NJDEP initiated a Phase I RI/FS. The Phase I report concluded that contamination of the municipal water supply was emanating from multiple source areas within the Borough.

Based on the findings of the 1986 RI/FS, EPA initiated a Phase II RI/FS to identify the contaminant sources, further delineate the full extent of contamination and evaluate remedial action alternatives to address the sources of contamination. Some of the major findings and conclusions of Phase II RI/FS were as follows:

- Groundwater in the northeast portion of Rockaway Borough was contaminated with VOCs, primarily TCE and PCE.
- A PCE groundwater contamination plume originating in the WS/EM Area was affecting Municipal Wells No. 1 and 5. However, the source area was not identified.
- Groundwater contamination from TCE was emanating from the K&K property and impacting the Rockaway Borough Well Field, specifically Municipal Well No. 6;

The remedy selected in a September 30, 1991 Record of Decision (ROD) called for extraction and treatment of two areas of groundwater contamination referred to as the K&K and WS/EM plumes. The remedy also called for further investigations to determine the source of the PCE and TCE plumes. In 2003, EPA began an RI/FS for the WS/EM Area.

The WS/EM Area is primarily a commercial area in the heart of downtown Rockaway Borough. The RI Study Area encompassed businesses located in this area including dry cleaning, auto body repair, auto service and repair, banking, hardware, hairdressing, convenience stores, and food establishments. In addition, Borough Police and Fire Departments, Memorial Park, and municipal parking lots are located within the Study Area.

The developed portions of the WS/EM Area are covered by impervious surfaces including asphalt roadways, driveways, and parking areas; and concrete building slabs and sidewalks. A limited

number of small, fragmented areas of exposed soils comprising suburban parkland, mowed lawns, ball fields and playgrounds, and fragmented areas of forested habitats, occur in the WS/EM Area.

## **CURRENT STATUS**

A potentially responsible party is presently performing the groundwater cleanup for the K&K plume. Construction of the groundwater extraction and treatment system has been completed and operation of the system began in January 2006.

The Remedial Design for the WS/EM Area, which was completed in February 2006, includes development of engineering drawings and specifications. Construction of the groundwater extraction and treatment system is scheduled to begin in early 2007. The United States Army Corps of Engineers, under an agreement with EPA, will be constructing the system.

The groundwater treatment system for the WS/EM Area will consist of three extraction wells, forcemains, air stripping and the discharge of treated water to the Rockaway River. The projected timeframe to restore the aquifer is 30 years.

An RI/FS is currently in progress to characterize the K&K source Area and one for the WS/EM source Area has been completed. The WS/EM Area RI/FS is the subject of this Proposed Plan.

## **SITE CHARACTERISTICS**

There have been numerous investigations conducted at the Rockaway Borough Wellfield Superfund Site to define the nature and extent of groundwater contamination, examine potential migration routes by which contamination could reach the Borough's Wellfield, and to identify potential sources of contamination.

The following discussion relates only to the results of the source area RI/FS conducted at the WS/EM Area.

Samples were collected from surface and subsurface soil. In general, the samples were analyzed for VOCs, semivolatile organic compounds, pesticides, and metals. VOCs are the only contaminant of concern at the site. Therefore, the investigations focused on just the nature and extent of VOCs. A summary of the findings for each media sampled is presented below.

### **Surface Contamination**

Surface soils (i.e., 0 to 1 foot below ground surface (bgs)) were collected from 17 boring locations, along with two duplicate samples (for a total of 19 soil samples). Eleven individual VOCs were detected in the surface soils; PCE was the only constituent that exceeded the NJDEP Impact to Groundwater Soil Cleanup Criteria (IGSCC). PCE was present in 10 of the 19 surface soil samples.

PCE occurred at concentrations exceeding its most conservative criteria value [the NJDEP IGSCC (1,000 micrograms per kilogram (ug/kg))] in surface soil samples. Lower concentrations of PCE were present in five other locations (i.e., detected range: 4 to 49 ug/kg). PCE was not detected in any of the three background locations. The more elevated concentrations of PCE in surface soil are present in the WS/EM Area.

### **Subsurface Contamination**

Shallow subsurface soils (i.e., 1 to about 10 feet bgs) were collected from ten locations, while deeper subsurface soils (i.e., about 8 to 42 feet bgs) were collected from five locations. A total of 46 subsurface soil samples and two duplicate samples were analyzed.

Although 10 VOCs were detected, only PCE exceeded its most conservative criteria value (i.e., 1,000 ug/kg) in four depth interval samples from three boring locations.

**WHAT ARE THE POTENTIAL  
"CONTAMINANTS OF CONCERN"?**

PCE, benzene, methylene chloride, chromium and lead were detected at the Site above the NJDEP Impact to Groundwater Soil Cleanup Criteria. Based on validity of the analytical results, frequency of occurrence, toxicological, physical, and chemical characteristics, the Baseline Human Health Risk Assessment identified only PCE as a Contaminant of Concern.

Contaminated groundwater is generally not considered to be a "principal threat". However, the source area associated with this proposed plan is considered to be a "principal threat" to the groundwater. The OU3 remedy will address this "principal threat" via excavation of the contaminated soil, which acts as a source for groundwater contamination.

**WHAT IS A "PRINCIPAL THREAT"?**

The NCP establishes an expectation that EPA will use treatment to address the principal threats posed by a site wherever practicable (NCP Section 300.430(a)(1)(iii)(A)). The "principal threat" concept is applied to the characterization of "source materials" at a Superfund site. A source material is material that includes or contains hazardous substances, pollutants or contaminants that act as a reservoir for migration of contamination to groundwater, surface water or air, or acts as a source for direct exposure. Contaminated groundwater generally is not considered to be a source material; however, Non-Aqueous Phase Liquids (NAPLs) in groundwater may be viewed as source material. Principal threat wastes are those source materials considered to be highly toxic or highly mobile that generally cannot be reliably contained, or would present a significant risk to human health or the environment should exposure occur. The decision to treat these wastes is made on a site-specific basis through a detailed analysis of the alternatives using the nine remedy selection criteria. This analysis provides a basis for making a statutory finding that the remedy employs treatment as a principal element

**Summary**

The nature and extent of soil contamination present in the WS/EM Area was assessed through sampling of surface, shallow subsurface and deep subsurface soils. In addition, an evaluation of available historical information and the results of the geophysical and soil gas surveys were performed to assist in the determination of potential contaminant source areas.

PCE is the primary contaminant at the site, and is present at elevated concentrations in the soil (i.e., up to 14,000 ug/kg) in the surface and 730 ug/kg in the subsurface) specifically in the vicinity of Lusardi's Cleaners, the southeastern portion of Municipal Parking Lot #2, and the parking lot west of the Rockaway Borough Police Station.

**SCOPE AND ROLE OF ACTION**

As in many complex Superfund sites, this site has been divided into three Operable Units (OUs) or phases. OU1 was the site-wide investigation to identify the contaminants in the Borough water supply. OU2 was created when the remedy was selected to treat the groundwater plumes. This action, referred to as OU3, is intended to be the first of two source area remedial actions for the site. This Proposed Plan summarizes the remedial alternatives detailed in the Feasibility Study, and discusses the preferred alternative for addressing contaminated soil.

#### Human Health Risk Assessment:

A Superfund baseline human health risk assessment is an analysis of the potential adverse health effects caused by hazardous substance releases from a site in the absence of any actions to control or mitigate these under current- and future-land uses. A four-step process is utilized for assessing site-related human health risks for reasonable maximum exposure scenarios.

*Hazard Identification:* In this step, the chemicals of concern (COCs) at the site in various media (i.e., soil, groundwater, surface water, and air) are identified based on such factors as toxicity, frequency of occurrence, and fate and transport of the contaminants in the environment, concentrations of the contaminants in specific media, mobility, persistence, and bioaccumulation.

*Exposure Assessment:* In this step, the different exposure pathways through which people might be exposed to the contaminants identified in the previous step are evaluated. Examples of exposure pathways include incidental ingestion of and dermal contact with contaminated soil. Factors relating to the exposure assessment include, but are not limited to, the concentrations that people might be exposed to and the potential frequency and duration of exposure. Using these factors, a "reasonable maximum exposure" scenario, which portrays the highest level of human exposure that could reasonably be expected to occur, is calculated.

*Toxicity Assessment:* In this step, the types of adverse health effects associated with chemical exposures, and the relationship between magnitude of exposure and severity of adverse effects are determined. Potential health effects are chemical-specific and may include the risk of developing cancer over a lifetime or other non-cancer health effects, such as changes in the normal functions of organs within the body (e.g., changes in the effectiveness of the immune system). Some chemicals are capable of causing both cancer and non-cancer health effects.

*Risk Characterization:* This step summarizes and combines outputs of the exposure and toxicity assessments to provide a quantitative assessment of site risks. Exposures are evaluated based on the potential risk of developing cancer and the potential for non-cancer health hazards. The likelihood of an individual developing cancer is expressed as a probability. For example, a  $10^{-4}$  cancer risk means a "one-in-ten-thousand excess cancer risk"; or one additional cancer may be seen in a population of 10,000 people as a result of exposure to site contaminants under the conditions explained in the Exposure Assessment. Current Superfund guidelines for acceptable exposures are an individual lifetime excess cancer risk in the range of  $10^{-4}$  to  $10^{-6}$  (corresponding to a one-in-ten-thousand to a one-in-a-million excess cancer risk) with  $10^{-6}$  being the point of departure. For non-cancer health effects, a "hazard index" (HI) is calculated. An HI represents the sum of the individual exposure levels compared to their corresponding reference doses. The key concept for a non-cancer HI is that a "threshold level" (measured as an HI of less than 1) exists below which non-cancer health effects are not expected to occur.

## SUMMARY OF SITE RISKS

As part of the RI/FS, EPA conducted a baseline risk assessment to determine the current and future effects of the contaminants on human health and the environment. The site is currently used as a commercial facility, and any future use is expected to be the same. Therefore, the baseline risk assessment focused on health effects for populations typically associated with commercial facilities, site workers and future construction workers that could result from current and future direct contact with contaminated surface and subsurface soils.

#### Human Health Risk Assessment Findings

The carcinogenic risks and non-carcinogenic hazards for soil exposures at the WS/EM Area showed values that were within EPA's target risk range for carcinogens and below the Hazard Index (HI) of 1 for non-carcinogens (please see the box on this page for an explanation of these terms) for all populations evaluated under both current and future use scenarios. A complete discussion of the risks and hazards can be found in the Baseline Human Health Risk Assessment.

Although the risks and hazards associated with soil exposure are within or below EPA's acceptable values, the soil concentrations of PCE are above the concentrations that are associated with an adverse impact to groundwater; thus, there is a need to address the soil through a remedial action.

#### Ecological Risks

A Screening Level Ecological Risk Assessment (SLERA) was performed for the Area. The SLERA determined that because the majority of the observed concentrations is comparable to background or below screening level benchmark values and due to the lack of usable terrestrial habitat for ecological receptors at the WS/EM Area, risks to ecological receptors are deemed to be low. Therefore, ecologically based screening criteria are not presented and will not be utilized to assist in the interpretation of the nature and extent of soil contamination at the Area.

## Remedial Action Objectives

The overall remediation goal for this area is to protect human health and the environment. The remedial action objective (RAO) has been identified to mitigate the potential risks associated with the WS/EM Area.

### Soil

The RAO for the contaminated soil at the WS/EM Area is:

1. Reduce the potential for further migration of PCE from the contaminated soil into groundwater.

The Preliminary Remediation Goal for PCE in soil was identified from the New Jersey Impact to Groundwater Soil Criteria and is 1 mg/kg.

### Summary of Remedial Alternatives

Based on technology screening and process option evaluation, the potential soils remedial alternatives developed for the site are as follows:

- S-1: No Action
- S-2: Limited Action
- S-3: *In-Situ* Treatment (SVE) and Hot-Spot Excavation with Off-Site Treatment and/or Disposal
- S-4: Excavation with Off-Site Disposal with SVE

#### Alternative S-1: No Action

*Estimated Capital Cost: \$0*  
*Estimated Annual O&M Cost: \$0*  
*Estimated Present Worth: \$0*  
*Estimated Construction Time Frame: None*

Regulations governing the Superfund program require that the "no action" alternative be evaluated to establish a baseline for comparison. Under this alternative, EPA would take no action at the site to prevent the migration of the contamination to the groundwater. Since this alternative results in contaminants remaining on the site above levels that would not allow for

unlimited use and unrestricted exposure, a review of the site at least every five years would be required.

#### Alternative S-2: Limited Action

*Estimated Capital Cost: \$27,000*  
*Estimated Annual O&M Cost: \$0*  
*Estimated Present Worth: \$0*  
*Estimated Construction Time Frame: None*

The Limited Action Alternative would include implementation of administrative controls such as deed notices. The deed notices, or comparable administrative control, would be implemented to ensure that future activities at the WS/EM Area (e.g., excavation) would be performed with knowledge of the WS/EM Area conditions and implementation of appropriate health and safety controls. Since this alternative results in contaminants remaining on the site above levels that would not allow for unlimited use and unrestricted exposure, a review of the site at least every five years would be required.

#### Alternative S-3: In-Situ Remediation (SVE) and Hot-Spot Excavation with Off-Site Treatment and/or Disposal

*Estimated Capital Cost: \$410,000*  
*Estimated Annual O&M Cost: \$0*  
*Estimated Present Worth: \$410,000*  
*Estimated Construction Time Frame: 1 year*  
*Estimated Time to Achieve RAO: 2 years*

This alternative includes *in-situ* remediation via soil vapor extraction (SVE) in an effort to address the RAO by removing PCE as a potential ongoing source of groundwater contamination. SVE would be used to remediate PCE in the unsaturated (vadose) zone soil. To implement SVE, a vacuum is applied to the soil through a series of wells to induce the controlled flow of air to remove VOCs from the soil. The captured vapors are then treated to applicable air standards. An estimated area of PCE-impacted soil, based on information provided in the RI Report and the April 2006 Focused Field Sampling, is 195 ft<sup>2</sup>.

A hot-spot excavation will occur in parallel with the SVE system to remove approximately 20 cubic yards (yd<sup>3</sup>) of PCE-contaminated soil in a parking area southwest of the Rockaway Borough Police Station.

Excavated soils would be analyzed for disposal parameters and would be containerized for off-site disposal. The excavated soils would be trucked off-site for treatment, as needed, and disposed of in accordance with federal and state regulations. Upon completion of contaminated soil removal, the excavation would be backfilled and compacted, and the surface would be restored.

Excavation would remove contaminated soil and meet the NJDEP Impact to Groundwater criteria, and post-excavation sampling would confirm that the criteria have been met.

If during pre-design investigation sampling it is determined that soil under the Lusardi's Dry Cleaner building would need to be remediated, the SVE system may be expanded to address the remaining soil contamination.

Because this alternative is expected to achieve the cleanup goals and not leave hazardous substances, pollutants or contaminants remaining at the site above levels that allow for unlimited use and unrestricted exposure, a five-year review may not be required.

#### **Alternative S-4: Excavation with Off-Site Treatment and/or Disposal with SVE**

*Estimated Capital Cost: \$320,000*

*Estimated Annual O&M Cost: \$0*

*Estimated Present Worth: \$320,000*

*Estimated Construction Time Frame: 3-6 months*

*Estimated Time to Achieve RAO: 6 months*

In this alternative, PCE-contaminated soils are removed via excavation. The excavated material would be transported off-site for treatment and/or disposal, at a facility designed and permitted for disposal of PCE-contaminated soil. The estimated volume of impacted soil, based on information in the RI report is approximately 40 cubic yards, excluding contamination that may

be located beneath the Lusardi's Dry Cleaner building. However, additional action level exceedences could be detected during post-excavation confirmatory sampling, which could increase the scope during remedial construction.

Excavated soils would be analyzed for disposal parameters and would be containerized for off-site disposal. The excavated soils would be trucked off-site for treatment, as needed, and disposed of in accordance with federal and state regulations. Upon completion of contaminated soil removal, the excavation would be backfilled and compacted, and the surface would be restored.

Excavation would remove contaminated soil and meet the NJDEP Impact to Groundwater criteria, and post-excavation sampling would confirm that the criteria have been met.

If during pre-design investigation sampling it is determined that soil under the Lusardi's Dry Cleaner building would need to be remediated, an SVE component may be added to this alternative to address the remaining soil contamination. The capital costs for this alternative reflect the use of the SVE system.

Because this alternative is expected to achieve the cleanup goals and not leave hazardous substances, pollutants or contaminants remaining at the site above levels that allow for unlimited use and unrestricted exposure, a five-year review may not be required.

#### **EVALUATION OF ALTERNATIVES**

Nine criteria are used to evaluate the different remediation alternatives individually and against each other in order to select the best alternative. This section of the Proposed Plan profiles the relative performance of each alternative against the nine criteria, noting how it compares to the other options under consideration. The nine evaluation criteria are discussed below. A "Detailed Analysis of Alternatives" can be found in the Feasibility Study.

## 1. Overall Protection of Human Health and the Environment

Alternative S-1 would provide no protection of human health and the environment since the contamination is left on-site. Alternative S-2 would provide limited protection of human health and the environment by reducing potential risks by utilizing institutional controls. Alternatives S-3 and S-4 would provide protection of human health and the environment by eliminating, reducing, or controlling risk through the removal or treatment of contaminated material.

Because the "no action" alternative (S-1) is not protective of human health and the environment, it was eliminated from consideration under the remaining eight criteria.

## 2. Compliance with ARARs

Actions taken at any Superfund site must meet all Applicable or Relevant and Appropriate Requirements (ARARs) of federal and state law or provide grounds for invoking a waiver of these requirements. These include chemical-specific, location-specific, and action-specific ARARs. There are no chemical-specific ARARs for soil, only To-Be-Considered cleanup numbers (TBC). The New Jersey Impact to Groundwater Soil Criteria are TBCs. Alternatives S-3 and S-4 would meet the TBCs for the contaminated soils. Alternative S-2 would not meet the TBCs for the contaminated soils. Location-specific ARARs would not be triggered for any of the alternatives, however, should the remediation area expand to the former Morris Canal, National Register of Historical Places requirements would be triggered. Alternatives S-3 and S-4 would attain action-specific ARARs for the contaminated soils, which would include RCRA Transportation and Disposal requirements. Alternative S-2 would not attain action-specific ARARs for the contaminated soils.

## 3. Long-Term Effectiveness and Permanence

Of the remaining alternatives, the magnitude of residual risks is highest for Alternative S-2.

Alternative S-2 relies on land use restrictions and public education programs aimed at informing the public about potential hazards posed by exposure to contaminants in the soil.

Alternatives S-3 and S-4 both mitigate the ongoing source of groundwater contamination. Alternative S-3 uses limited excavation and *in-situ* treatment to reduce contaminant mass in the vadose zone. Alternative S-4 uses excavation and off-site disposal to remove contaminant mass from the Site with the contingency to use *in-situ* treatment should additional sources be located. Alternatives S-3 and S-4 are both permanent remedies and effective in the long-term.

## 4. Reduction of Toxicity, Mobility, or Volume of Contaminants Through Treatment

Alternative S-2 would not reduce toxicity, volume or mobility through treatment. Alternatives S-3 and S-4 would reduce contaminant mobility through removal and disposal or regeneration of the spent granular activated carbon (GAC) and removal and disposal of soils at approved off-site facilities. Alternative S-3 (and potentially Alternative S-4 if the SVE contingency is implemented) would also reduce the volume of contaminated media by transferring contaminants from soil to GAC. For Alternatives S-3 and S-4, pre-disposal treatment, if necessary, could potentially reduce the toxicity and volume of the contaminated soils.

## 5. Short-Term Effectiveness

Alternative S-2 does not involve any physical treatment; there are no short-term risks to the community or workers as well as no environmental effects.

Alternative S-3 would present short-term risks to the community relating to inhalation exposure that would be mitigated by air monitoring and engineering controls. Risks relating to inhalation exposure by workers, would be mitigated by air monitoring and a health and safety program. The *in-situ* remediation is anticipated to create

minimal environmental effects since the WS/EM Area is highly developed.

Alternative S-4 would present short-term risks to the community relating to exposure to contaminated soil. This exposure will be mitigated with the use of air monitoring, dust suppression, and restricted site access. Risks relating to inhalation exposure by workers, would be mitigated by air monitoring, dust suppression, and a health and safety program. Excavation is anticipated to create minimal environmental effects since the WS/EM Area is highly developed.

#### **6. Implementability**

Alternative S-2 could be easily implemented. Coordination with state and local governments will be required for implementing institutional controls and educational programs. Coordination with state and local authorities will be required for five-year reviews.

Alternative S-3 and possibly S-4 (if the SVE is needed) would be somewhat difficult to implement because of limited available space to install a treatment building. Coordination with state and local governments in addition to property owners and tenants would be required for placement of extraction wells and associated treatment equipment.

Alternative S-4 would be easily implemented using conventional construction equipment and materials; however, some specialized techniques may be required for excavation in close proximity to building foundations and would require coordination with state and local governments in addition to property owners and tenants. This alternative would also potentially impact businesses since the excavation would occur near buildings as well as the need to close a portion of a municipal parking lot during excavation work

#### **7. Cost**

The estimated present worth costs of the Alternatives are:

Alternative S-2 (Limited Action): potential capital costs involved with the implementation of the institutional controls -\$27,000 .

Alternative S-3 (*In-situ* Treatment and Hot Spot Excavation): operating costs are only needed until RAO is achieved -\$410,000.

Alternative S-4 (Excavation with Off-Site Disposal and SVE): have capital costs until RAO is achieved and may have operating costs if SVE treatment is needed - \$320,000.

#### **8. State/Support Agency Acceptance**

The State of New Jersey is currently evaluating EPA's Preferred Alternative in this Proposed Plan.

#### **9. Community Acceptance**

EPA will evaluate community acceptance of the Preferred Alternative after the public comment period ends. EPA will discuss community acceptance in the Record of Decision, the document that formalizes the selection of the remedy for the Area.

### **SUMMARY OF THE PREFERRED ALTERNATIVES**

Based on the evaluation of remedial alternatives that was presented in the previous section, EPA has selected Alternative S-4 as its Preferred Alternative. This alternative involves excavation and off-site treatment and/or disposal of contaminated soils, and use of an SVE system for contamination beneath the Lusardi's Dry Cleaner building at the WS/EM Area.

The Preferred Alternative satisfies the remedial action objectives and the requirements of CERCLA, as amended, and the NCP. It will require 1-2 years of operation for the remedy to meet the cleanup criteria, which are the New Jersey Impact to Ground Water Soil Cleanup Criteria.

The Preferred Alternative provides the best balance of trade-offs among alternatives with respect to the nine CERCLA evaluation criteria. The Preferred Alternative is protective of human health and the environment, complies with ARARs and cleanup criteria, is cost-effective, and uses permanent solutions and alternative treatment technologies or resource recovery technologies to the maximum extent practicable. The Preferred Alternative also meets the statutory preference for the use of treatment as a principal element to the maximum extent practicable.

### COMMUNITY PARTICIPATION

EPA provides information regarding the cleanup of the Rockaway Borough Wellfield Superfund Site to the public through public meetings, the Administrative Record file for the site, and announcements published in the local newspaper. EPA and the State encourage the public to gain a more comprehensive understanding of the site and the Superfund activities that has been conducted there. The front page of this Proposed Plan shows the dates for the public comment period, the date, location, and time of the public meeting, and the locations of the Administrative Record files.

EPA Region 2 has designated a point-of-contact for community concerns and questions about the Superfund program. To support this effort, the Agency has established a 24-hour, toll-free number the public can call to request information, express concerns or register complaints about Superfund. The Public Liaison Manager for EPA's Region 2 office is:

George H. Zachos  
Toll-free (888) 283-7626  
(732) 321-6621

U.S. EPA Region 2  
2890 Woodbridge Avenue, MS-211  
Edison, New Jersey 08837

**For further information on the Rockaway Borough Wellfield site, please contact:**


Brian Quinn  
Project Manager

(212) 637-4381  
[quinn.brian@epa.gov](mailto:quinn.brian@epa.gov)

Cecilia Echols  
Community Involvement  
Coordinator

(212) 637-3678  
[echols.cecilia@epa.gov](mailto:echols.cecilia@epa.gov)

U.S. EPA  
290 Broadway  
New York, New York 10007-1866



TITLE: <b>SITE LOCATION MAP</b> <b>PROPOSED PLAN</b> <b>ROCKAWAY BOROUGH WELLFIELD RI/FS</b>	DWN:	DES:	PROJECT NO.:
	CTS	CTS	
	CHKD:	APPD:	FIGURE NO.:
LH	BQ		
DATE:	REV.:	1	
8/8/2006	0		

**ATTACHMENT B  
PUBLIC NOTICE ANNOUNCING PROPOSED PLAN  
AND COMMUNITY MEETING**



**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
INVITES PUBLIC COMMENT ON THE  
PROPOSED PLAN FOR THE  
ROCKAWAY BOROUGH WELLFIELD SUPERFUND SITE  
ROCKAWAY, MORRIS COUNTY, NEW JERSEY**

The U.S. Environmental Protection Agency (EPA) announces the opening of a **30-day comment period** on the Proposed Plan and preferred cleanup alternatives to address contamination at the Rockaway Borough Wellfield site in Rockaway, New Jersey. The comment period began on **August 11, 2006** and ends on **September 11, 2006**. EPA will hold a public meeting on **Wednesday, August 23, 2006 at 7:00PM at the Rockaway Borough Community Center, 21-25 Union Street, Rockaway, NJ 07866**. Please contact Ms. Cecilia Echols, EPA's Community Involvement Coordinator, at 212-637-3678 or 1-800-346-5009 for more information.

The site is listed on the Superfund National Priorities List. EPA recently concluded a Remedial Investigation/Feasibility Study (RI/FS) for the site to assess the nature and extent of contamination in site media and to evaluate alternatives to cleanup the site. Based upon the results of the RI/FS, EPA has prepared a Proposed Plan which describes the findings of the RI and potential cleanup alternatives detailed in the feasibility study and provides the rationale for recommending the preferred alternative.

**EPA's preferred cleanup remedy for the site consists of the following components:**

- Excavation and off-site disposal of Tetrachloroethylene (PCE) contaminated soils with the installation of a soil vapor extraction system (Alternative S4) at the Wall Street/East Main Street area of the Rockaway Borough Wellfield site.
- Institutional controls, monitoring, and periodic reviews would also be part of the remedy to ensure that the remedy remains protective of public health and the environment.

During the **August 23, 2006** public meeting, EPA representatives will be available to discuss the reasons for recommending the preferred cleanup remedy and public comments will be received.

The RI Report, FS Report, Risk Assessment, Proposed Plan and other site-related documents are available for public review at the information repositories established for the site at the following locations:

**Rockaway Borough Free Public Library:** 82 East Main Street, Rockaway, New Jersey 07866,  
(973) 627-5709.

**USEPA Region II:** Superfund Records Center, 290 Broadway, 18<sup>th</sup> Floor, New York, NY 10007-1866,  
(212) 637-3261.

EPA relies on public input to ensure that the selected cleanup alternative for each Superfund site meets the needs and concerns of the local community. It is important to note that although EPA has identified a preferred cleanup remedy for the site, no final decision will be made until EPA has considered all public comments received during the public comment period. EPA will summarize these comments along with EPA's responses in a Responsiveness Summary, which will be included in the Administrative Record file as part of the Record of Decision. **Written comments and questions regarding the Rockaway Borough Wellfield site, postmarked no later than Wed., September 11, 2006, may be sent to:**

Brian Quinn, Project Manager  
U.S. Environmental Protection Agency  
290 Broadway, 19th Floor  
New York, New York 10007-1866  
Telefax: (212) 637-4393  
email: [quinn.brian@epa.gov](mailto:quinn.brian@epa.gov)

For more information on the Rockaway Borough Wellfield site: [epa.gov/region02/superfund/npl/0200766c.htm](http://epa.gov/region02/superfund/npl/0200766c.htm)

**ATTACHMENT C**  
**EPA PRESS RELEASE ANNOUNCING EPA TO REMOVE CONTAMINATED SOIL**  
**FROM THE ROCKAWAY BOROUGH WELLFIELD SITE.**

# Press Release

Region 2 - New York, New Jersey, Puerto Rico and the U.S. Virgin Islands



290 Broadway, New York, New York 10007-1866 [www.epa.gov/region2](http://www.epa.gov/region2)

## EPA To Remove Contaminated Soil From the Rockaway Borough Wellfield Site

Contact: Patricia Carr 212-637-3652, [carr.patricia@epa.gov](mailto:carr.patricia@epa.gov); Benjamin Barry 212-637-3651, [barry.benjamin@epa.gov](mailto:barry.benjamin@epa.gov)

(New York, NY – August 18, 2006) – The U.S. Environmental Protection Agency is proposing to remove soil contaminated with tetrachloroethene (PCE), a commonly used industrial solvent, from the Rockaway Borough Wellfield site located in Morris County, New Jersey. EPA will dig up the contaminated soil and move it to a location specially certified to treat and dispose of it.

“Soil contamination at the Rockaway Borough site has already affected the ground water, and we are now taking action to eliminate a potential avenue to further contamination,” said Regional Administrator Alan J. Steinberg. “We have already installed a treatment system to address the ground water contamination.”

EPA will also hold a public meeting on August 23, 2006 at 7:00 PM at the Rockaway Borough Community Center, 21-25 Union Street, Rockaway, NJ 07866. The public can comment on the proposed plan through September 11, 2006.

The Rockaway Borough Wellfield Site includes three municipal water supply wells where the ground water is contaminated with PCE and TCE, another industrial solvent. In 1985, the New Jersey Department of Environmental Protection investigated the site and concluded that contamination of the municipal water supply was emanating from multiple source areas within the Borough. Based on these findings, EPA initiated a follow-up investigation to identify the sources of contamination, determine the extent of the contamination, and evaluate potential cleanup methods.

**ATTACHMENT D  
MEETING AGENDA AND TRANSCRIPT OF  
23 AUGUST 2006 PUBLIC MEETING**



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION 2  
290 BROADWAY  
NEW YORK, NY 10007-1866

## Public Information Session

Rockaway Borough Wellfield Superfund Site  
Rockaway, New Jersey

Rockaway Borough Community Center

Wednesday, August 23, 2006 7:00PM

### AGENDA

#### I. Welcome & Introduction

Cecilia Echols - Community Involvement Coordinator,  
Intergovernmental & Community Affairs Branch, USEPA

#### II. Site History

Brian Quinn, Project Manager, New Jersey Remediation Section,  
USEPA

#### III. Remedial Investigation

Louis Hahn, Project Manager, Tetra Tech EC, Inc.

#### IV. Human Health and Screening Level Ecological Risk Assessment

Mike Sivak, Risk Assessor, USEPA

#### V. Feasibility Study

Robert Chozick, Feasibility Study Manager, Tetra Tech EC, Inc.

#### VI. Preferred Remedy

Brian Quinn

#### VII. Questions, Comments, & Answers

Cecilia Echols

#### Other Representatives in Attendance

Brian McKnight, Chief, Northern Jersey Remediation Section, USEPA

ROCKAWAY BOROUGH WELLFIELD SUPERFUND SITE  
ROCKAWAY, NEW JERSEY

COPY

Rockaway Borough Community Center

Wednesday, August 23, 2006

7:15 p.m.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25

P R E S E N T:

- Cecilia Echols, Community Involvement Coordinator
- Brian Quinn, Project Manager
- Louis Hahn, Project Manager
- Mike Sivak, Risk Assessor, USEPA
- Robert Chozick, Feasibility Study Manager
- Bob McKnight, Chief, Northern Jersey Remediation Section, USEPA

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25

T R A N S C R I P T of the  
above-entitled matter as taken stenographically  
by and before SERAFINA R. ZINCKGRAF, a Certified  
Shorthand Reporter, Registered Professional  
Reporter and Notary Public of the State of New  
Jersey at the offices of Rockaway Borough  
Community Center, 21-25 Union Street, Rockaway,  
New Jersey on Wednesday, August 23, 2006,  
commencing at 7:15 in the evening.

1 MS. ECHOLS: Hello everyone.  
2 Thank you for your patience. I'm Cecelia  
3 Echols. I'm the Community Involvement  
4 Coordinator for the Rockaway Borough Wellfield  
5 Superfund Site.

6 The purpose of tonight's meeting  
7 is to discuss the proposed plan of cleanup for  
8 the contaminated soils within the Wall Street/  
9 East Main Street area.

10 I hope everyone has taken the  
11 handout. If you haven't, you can come up and  
12 get a package because we will be, in particular,  
13 discussing the proposed plan, and we have,  
14 overhead, a Power Point presentation of the  
15 overheads.

16 On our agenda, as you can see,  
17 I'm Cecelia. We have Brian Quinn. He will  
18 discuss the site history. He's a project  
19 manager for this site. He's in the New Jersey  
20 remediation section for the EPA.

21 Then we will have Louis Hahn.  
22 He's in the back right here standing up. He  
23 will discuss the remedial investigation. He's  
24 the project manager for Tetra Tech. That's the  
25 contractor for EPA.

1           Then we'll have Mike Sivak to the  
2 far right. He will discuss the human health and  
3 screening level ecological risk assessment. He  
4 is a risk assessor for the EPA.

5           Next, we'll have Robert Chozick.  
6 He will discuss the Feasibility Study. He's a  
7 Feasibility Study manager for Tetra Tech, as  
8 well.

9           Then we'll have Brian discuss the  
10 preferred remedy of cleanup for the site, and  
11 then we'll open up for questions, comments and  
12 answers.

13           Also, as a representative of EPA,  
14 I have Brian McKnight down now. I'm sorry, it  
15 should be Bob McKnight. He is the Chief of the  
16 Northern Jersey Remediation Section. He's also  
17 with EPA.

18           I would also like to recognize  
19 Mayor Lockwood. She's here. If you would like  
20 to stand for a moment.

21           (Mayor Lockwood stands.)

22           MS. ECHOLS: I guess there's some  
23 members from your staff here?

24           MAYOR LOCKWOOD: Bob Schaefer,  
25 Joe Vicente(ph), two of my councilmen; my

1 Superintendent of Public Works, Joe Rossi and  
2 Peter DeJeckyl(ph), licensed operator for the  
3 water.

4 MS. ECHOLS: Thank you for  
5 coming. Just to bring an overview, it is a  
6 program designed within the Superfund Program to  
7 seek community involvement from the community to  
8 have you become involved in the decision-making  
9 process for cleaning up a site within your  
10 community. We cannot just cleanup a site  
11 without your involvement. So I'm very happy to  
12 see so many of you have come out tonight.

13 Just to mention, there is an  
14 information repository. One is at the Rockaway  
15 Borough Free Public Library, and the other one  
16 is at the EPA office in Manhattan. I would like  
17 to mention that we mailed approximately 300 of  
18 these proposed plans to the community. If you  
19 have not received one, I hope that you have  
20 signed in, and you will be placed on the mailing  
21 list.

22 If you know of anyone or if you  
23 have any neighbors who would like to be placed  
24 on the mailing list, please give me a phone  
25 call, and I'll make sure they're on the mailing

1 list.

2                   The Public Comment period began  
3 on August 11th; it ends on September 11th.  
4 There was a Public Notice placed today in The  
5 Citizen as part of the Record of Decision. We  
6 have a Responsiveness Summary, and that will be  
7 a collaboration of all of your comments that we  
8 receive by fax, by E-mail or any tonight that  
9 are taken by the stenographer, which becomes a  
10 part of the transcript.

11                   I only have one ground rule and  
12 that is please hold all of your questions,  
13 comments and answers to the end of the  
14 presentation. Now, we'll have Brian. Could you  
15 all hear me? Great.

16                   MR. QUINN: Good evening. I'm  
17 Brian Quinn, the project manager for Rockaway  
18 Borough site. Just to give a quick overview of  
19 the site, it's a little complicated so just bear  
20 with me. We can clear up some economist  
21 misconceptions you have or anything lighter.

22                   What contamination was first  
23 found in the drinking water in 1980. At that  
24 time, a treatment system was built and began  
25 operation in July of 1981, and is still

1 operating at this time. To make sure the water  
2 that leaves the plant that comes into the  
3 Borough is all completely removed, the  
4 contaminants are removed before it's sent to  
5 everybody to drink.

6           After that, we did what's called  
7 the Remedial Investigation and Feasibility  
8 Study, both which we're going to discuss  
9 tonight. An earlier version of these were done  
10 to investigate what caused the contamination,  
11 where it came from; and at the end of that, a  
12 Record of Decision was signed which identified  
13 three of the source areas which was the East  
14 Main/Wall Street area, the Klockner and Klockner  
15 area which is over on Stickel (ph) and Elm  
16 Street, as well as Raynag (ph) Realty area,  
17 which is a little further on the other side of  
18 the railroad tracks. It wasn't necessary to do  
19 any further investigation to the realty.

20           A second Record of Decision was  
21 issued in 1991, which called for the treatment  
22 of the groundwater by a groundwater extraction  
23 and treatment system for both the East Main/Wall  
24 Street area, the plume that was generated from  
25 contamination, and one from the Klockner and

1 Klockner area. Both of those areas are  
2 distinctly different chemicals. The one that's  
3 coming from the Klockner and Klockner area is  
4 called Trichloroethene, TCE is the chemical  
5 name, and also Tetrachloroethene was coming from  
6 the East Main/Wall Street area, which is called  
7 PCE. They're two different treatment systems  
8 being built. One is already built, which is on  
9 Cobb Street, which is built by a  
10 potentially-responsible party, and it's  
11 operating now to start cleaning that plume up.

12 EPA is in the process of  
13 constructing a plume, a groundwater treatment  
14 system to clean up the East Main/Wall Street  
15 area, and then there were two separate source  
16 area investigations, one which we have completed  
17 for the East Main/Wall Street, and one that's  
18 still ongoing at the Klockner and Klockner site.

19 So tonight we're here to discuss  
20 the investigation for the East Main/Wall Street  
21 area, and then the preferred remedy for the  
22 contamination. I'll turn it over to Lou to  
23 discuss the remedial investigations.

24 MR. HAHN: I'm Lou Hahn, the  
25 project manager with Tetra Tech, contractor to

1 EPA. We performed the remedial investigation  
2 and the Feasibility Study for the most recent  
3 face of work here related to soil.

4           Based on the findings of the last  
5 RI that was done in 1991, it was determined that  
6 it was necessary to go back out and do  
7 additional work to try to determine the source  
8 of contamination and soil.

9           As part of this current phase of  
10 work, we delineated a study area to perform our  
11 investigation, which is kind of shown here.  
12 It's the heart of the downtown area, Wall Street  
13 and East Main Street.

14           You can also see on this figure  
15 where the municipal wells are located. Within  
16 this area, we had the footprint of the former  
17 Morris Canal that was investigated as a  
18 potential pathway. We also had various other  
19 types of facilities, including some auto body  
20 shops, service stations, two dry cleaning  
21 facilities, the former M. Hoagland Union Foundry  
22 property which is currently occupied by the  
23 police department, and the former scrapbook shop  
24 here, and then also Memorial Park, because that  
25 was part of the current or the former Morris

1 Canal after it had been filled.

2           Current study area conditions  
3 right now, as you're all familiar with, we're  
4 talking about the intersection here of East Main  
5 and Wall Street. So here's a view looking up  
6 Wall Street from East Main from in front of the  
7 PNC Bank building. An area behind the dry  
8 cleaning facility, we have parking lot and  
9 Municipal Parking Lot No. 2, an area where we  
10 did some of our drilling, and then a parking lot  
11 at 21 Maple Avenue. That actually comprises  
12 part of the former foundry property.

13           Primary objective of the remedial  
14 investigation was to define how far and extent  
15 of the soil contamination, and try to determine  
16 the location of the contamination, the type of  
17 contamination, and the amount of the  
18 contamination.

19           The media that we investigated  
20 during this included soil gas, surface soil,  
21 shallow subsurface soil and deep subsurface oil.  
22 The surface oil really comprises of zero to  
23 one-foot depth interval of soil. The shallow  
24 subsurface area comprised of one to ten-foot  
25 depth interval of soil, and the deep subsurface

1 soil was the interval from ten feet to  
2 approximately 40 feet below ground surface.

3           The field work during the  
4 remedial investigation was conducted in two  
5 phases. We did a sight recognizance phase, that  
6 was the initial phase work we did, we conducted  
7 some geophysical techniques in the field looking  
8 for potential underground storm tanks and  
9 piping, things that could be construed as  
10 possible sources of contaminants.

11           We also conducted a soil gas  
12 survey, a screen technique used to try to  
13 identify where there may be hot spots of  
14 contamination in soil. You look for the actual  
15 vapors coming off of the contaminated soil.

16           We did some topographic mapping  
17 during that phase, and we also did an ecological  
18 survey to determine if there were any threatened  
19 and dangerous species in the area and also, if  
20 there were any sensitive environments in the  
21 area within that study area and also a cultural  
22 resources survey where we looked at the  
23 potential for any significant cultural resources  
24 that were there or architectural resources that  
25 could be impacted by the work.

1           We did a field investigation  
2 phase where we collected soils, soil samples  
3 from surface soils from the shallow subsurface  
4 oil, and the deep subsurface oils; and during  
5 that, we would take the soil samples and send  
6 them off for analysis, volatile organic analysis  
7 via laboratory.

8           We also did some archaeological  
9 monitoring during that sampling just to watch  
10 for the potential cultural resources that may  
11 come up, since the area has some significant  
12 history being associated with some of the former  
13 Morris Canal and some of the older buildings  
14 on-site.

15           In summary, based on the soil  
16 sampling activities, the field investigation  
17 that was conducted between October and November  
18 of 2003, we collected 19 surface samples, and we  
19 had 48 subsurface soil samples between the two  
20 intervals, and then we came back out this past  
21 April and we did a focused field sampling at the  
22 parking lot of 21 Maple Avenue to confirm the  
23 existence of a hot spot there.

24           Based on the soil sample results,  
25 we had determined that volatile organic

1 compounds are present in the soil.  
2 Tetrachloroethene, the PCE, was determined to  
3 impact the groundwater soil cleanup area which  
4 is one milligram per kilogram. Of the surface  
5 subsoil collected, PCE was present in ten of the  
6 19, and with a maximum concentration of one  
7 sample of 14 milligram per kilogram. PCE was  
8 detected in concentrations of up to .73  
9 milligram per kilogram.

10                   During the April 2006 focused  
11 field sampling, we confirmed the presence of a  
12 hot spot at 21 Maple. Here we have a couple  
13 photographs. We have an example of the direct  
14 push sampling drill rig that was used on-site.  
15 Some of you may have seen the equipment out  
16 there that was used to collect some of the  
17 shallow soil samples to ten feet below grade.

18                   We also employed the use of a  
19 rotosonic drilling rig to collect both shallow  
20 and deep soil sampling. This rig was to collect  
21 soil samples down to the water table, which was  
22 approximately 40 feet at the site.

23                   This figure introduces our  
24 cross-section as part of the investigation in  
25 the soil. We characterized the soil at the site

1 determine what it is comprised of, in terms of  
2 like what they call lithology.

3 I'm going to present a  
4 cross-section of this point here, B to B Prime.  
5 It comprises the deeper soil borings that we  
6 took to the top of the water table in the study  
7 area. Here is the cross-section showing that  
8 same B to B Prime transection here. We have  
9 illustrated here the surface cover of asphalt in  
10 this area. Out in this area, we had no asphalt  
11 so it's most likely vegetated cover in the park.

12 We have a layer of film material  
13 underlying the surface cover comprised mostly  
14 with sand, cobble, boulders. We saw some  
15 cynders present in the former foundry property  
16 fill; and then underlying, we have a layer of  
17 sand with gravel and cobbles to the top of the  
18 water table, which was approximately 40 feet  
19 below ground surface.

20 So it's kind of a summary of the  
21 remedial investigation activities; and at that  
22 point, Michael Sivak will talk about the risk  
23 assessment findings.

24 MR. SIVAK: Well, I am EPA's Risk  
25 Assessor tonight, and I'm going to present what

1 we found in the human health and the screening  
2 level ecological risk assessments, and we're  
3 going to start with the human health.

4           As part of the RIFS process, the  
5 remedial investigation feasibility process, EPA  
6 conducts a human health assessment to determine  
7 what are the affects of exposure to these  
8 contaminants that we found on human health and  
9 on ecological receptors.

10           We're going to start with the  
11 human health. Basically, the purpose of the  
12 human health risk assessment is to answer two  
13 primary questions. The first question is what  
14 are the risks to people that are exposed to this  
15 contamination right the way the situation  
16 currently is with the lay of the land the way it  
17 is, and the second question is what are the  
18 risks in the future if no remedial action is  
19 taken?

20           So what are the risks in the  
21 future if no remedial action is taken to people  
22 who can come in contact with the site in the  
23 future? We look at how people might be exposed,  
24 and what kind of scenarios they might be exposed  
25 under. So, for example, we looked at potential

1 pathways are incidental ingestion of  
2 contaminated soil. Dermal absorbing of  
3 contaminated soil, you get some contaminated  
4 soil on your skin, that could be absorbed or  
5 across in your skin. Partly inhalation could be  
6 dust kicked up. Volatile compound inhalation.

7                   The contaminants that we're  
8 looking for at this site are volatile, which  
9 means they can vaporized. If you spill --  
10 probably the best example that everyone is most  
11 familiar with is fingernail polish remover or  
12 gasoline. When you're pumping gasoline and you  
13 see those vapors coming off of it when you're  
14 pumping it into your car, those are volatile  
15 vapors. Part of that gasoline that you're  
16 pumping in is pumping off gas vapors that go up  
17 off of that. We look to see those conditions  
18 here. We looked for these kinds of exposure  
19 pathways.

20                   In the area that we were  
21 investigating, the surface soils beneath the  
22 parking lot by the populations that are likely  
23 to be exposed to them, which are workers in  
24 these facilities, as well as future construction  
25 workers. If, for example, there needs to be

1 some kind of utility work that's done for  
2 subsurface utilities or if there needs to be  
3 construction work where people would have to  
4 access soils that are a little bit deeper.

5                   So we looked at the surface soils  
6 and we looked at all of the soils which includes  
7 the surface and the subsurface, and what did we  
8 find from the results of this investigation?  
9 Well, basically we looked for carcinogenic  
10 health affects and noncarcinogenic risk  
11 assessment ability.

12                   The site workers, the  
13 construction workers who might be exposed under  
14 any or all of those pathways that we just talked  
15 about, they're risks within or below our  
16 acceptable risk levels. So there really are no  
17 health risks, no unacceptable levels of health  
18 risks now and in the future.

19                   It's important to point out that  
20 although these risks and hazards are associated  
21 with soil exposure are below these acceptable  
22 levels, the results of the remedial  
23 investigation did identify PCE concentrations  
24 above this impact to groundwater, which means  
25 even though we have contamination in the soil

1 that's not associated with unacceptable health  
2 risks, there's still enough of it in there that  
3 it might continue to leech out to the  
4 groundwater, and it still might pose an impact  
5 to the groundwater.

6                   These are the results of the  
7 human health risk assessment. While we were  
8 conducting this risk assessment, EPA also  
9 recognized that because of the type of  
10 contaminants and the levels we're seeing out  
11 here, we needed to look into the possibilities  
12 of vapor intrusion, which is the likelihood of  
13 these contaminants volatilizing off of this  
14 deeper soil collecting underneath structures and  
15 also the groundwater, excuse me, collecting  
16 underneath these structures, and possibly  
17 infiltrating indoor airspaces where people live  
18 or where people work.

19                   So this wasn't really part of  
20 this particular risk assessment; but because we  
21 kind of conducted some of these investigations  
22 over the last few months, I wanted to just bring  
23 that up here tonight. So we have that effort  
24 ongoing.

25                   We have collected some data.

1 We're currently looking at it. We will be back  
2 to collect some more data regarding this vapor  
3 intrusion concern, and we can talk about that  
4 more in the question-and-answer session, if  
5 there are some questions.

6           The screening level ecological  
7 risk assessment is the other type of health  
8 evaluation that the EPA performs, and this is on  
9 ecological receptors. These are the three basic  
10 findings, and really what it comes down to is  
11 the concentrations that we found in our soil  
12 investigation are pretty much below or  
13 consistent with background areas, or they're  
14 below sort of our reference concentrations for  
15 ecological health effect. So that's good.

16           The other thing that is really  
17 important to know is that there's just not a lot  
18 of usable terrestrial habitat in this study.  
19 We're talking about some pretty suburban areas;  
20 the areas are pretty much paved. So there's not  
21 a whole lot of ecological habitat in the studies  
22 we looked at, and we take those factors into  
23 account, low levels of these volatile chemicals  
24 and the lack of real viable habitat.

25           We just did not have any

1 ecological risks that were of concern from this  
2 site. With that, I will turn it over to Bob.

3 MR. CHOZICK: Bob Chozick with  
4 Tetra Tech. I'm going to talk about the  
5 Feasibility Study, which is the next phase in  
6 the process of collecting a remedy. In the  
7 Feasibility Study, we evaluate the data from  
8 remedial investigation and risk assessment, and  
9 develop our remedial goal, what we want to  
10 achieve through our remedial alternative. We  
11 look at technologies, alternatives, and evaluate  
12 them to come up with the performed remedy that  
13 we'll talk about at the end of the presentation.

14 The first step is to develop  
15 objectives. We know what the remedial  
16 investigation found, and the risk assessment, as  
17 Mike said, there were no unacceptable risks to  
18 human health found based on the contaminated  
19 concentrations in the soils. However, there is  
20 the potential for contamination to migrate into  
21 the groundwater based on the levels observed.

22 So we have set the goal and was  
23 based on The New Jersey Department of  
24 Environmental Protection Soil Cleanup criteria  
25 to protect groundwater, basically. It's one

1 milligram per kilogram of PCE in the soils, and  
2 it's the number they determined is protective of  
3 groundwater.

4           The next phase of the Feasibility  
5 Study, we look at a full range of treatment  
6 technologies that can be used to address the  
7 contaminants in the soil. They're screened  
8 through several criteria based on the site  
9 conditions, the access conditions, and the  
10 contaminants that are found, and a short list of  
11 those technologies is then developed, and then  
12 combined to come up with the potential remedial  
13 alternatives that can be implemented to clean up  
14 the contaminated soils and meet the remedial  
15 objective.

16           After the alternatives are  
17 developed, the EPA has come up with nine  
18 criteria that they use to look at the  
19 alternatives to compare them and to select the  
20 best alternative to address the soils.

21           The first two criteria are  
22 considered threshold criteria. One is overall  
23 protection of human health and the environment.  
24 That's to prevent any risks to human health, the  
25 risk to the environment.

1           The second is the compliance with  
2 applicable or relevant and appropriate  
3 requirements. That refers to regulatory  
4 requirements developed by the EPA or state,  
5 cleanup goals, guidance values that should be  
6 achieved by any remedial alternative.

7           The EPA considers these threshold  
8 criteria, any alternative that can't meet these  
9 two criteria is basically considered an  
10 unacceptable alternative.

11           The next five criteria are  
12 balancing criteria. Basically, these five  
13 criteria are used to compare the various  
14 alternatives and rank them which are the best  
15 alternatives to address the contamination.

16           The first long-term effectiveness  
17 and permanence deals with the risks remaining  
18 after the remedy is implemented. That's how  
19 much contamination is left, what risks are  
20 associated with that, and is it possible for  
21 those risks to increase again or is it a  
22 permanent remedy that the risk cannot return?

23           The second, reduction in  
24 toxicity, mobility or volume through treatment  
25 deals with eliminating the contamination, making

1 the contaminants less toxic, stabilizing them so  
2 they can't move. For example, the area from the  
3 groundwater to the soils or reducing the overall  
4 quantity of contaminated material.

5           The short-term effectiveness  
6 refers to the risk during the implementation of  
7 the alternative. If the material is suggesting  
8 to be treated or removed, what risks are there  
9 to workers performing the work, the community  
10 around the area and the environment during those  
11 activities?

12           The implementability criteria is  
13 how easily or difficult it is to implement an  
14 alternative; are there access restrictions that  
15 prevent us from being easily implemented?  
16 Criterias such as that, and the last is the cost  
17 of the alternatives is compared. That's the  
18 capital cost to actually do implement the  
19 remedy, as well as any long-term operating costs  
20 to maintain a treatment system if there is one  
21 in the alternative.

22           The last two criteria, modifying  
23 criteria, State's answer. The state DEP has the  
24 opportunity to review the preferred remedy and  
25 Feasibility Study and concur or comment on the

1 EPA's preferred remedy. That process is  
2 currently underway. The EPA is, at the same  
3 time we're here and the public is reviewing this  
4 information, the DEP is also reviewing the  
5 Feasibility Study for their recommendations, and  
6 the last criteria is community acceptance, and  
7 that's how the community, you, feel about the  
8 remedy that's selected.

9                   We have this presentation, the  
10 Public Comment period where we take your input  
11 and consider that in the selection of the final  
12 remedy for the site.

13                   In the Feasibility Study, we went  
14 through the screening process I described, and  
15 ultimately four alternatives were developed to  
16 deal with the contaminated soil areas that have  
17 PCE contamination that may be impacting the  
18 groundwater.

19                   The first is no action  
20 alternative. The second is a limited action  
21 alternative. The third is In-Situ remediation,  
22 SVE, Soil Vapor Extraction, and the fourth is  
23 excavation of the contaminated soils.

24                   The no-action alternative does  
25 not meet the threshold of criteria. The EPA

1 Superfund Program requires that this alternative  
2 be retained, to compare the other alternatives  
3 to compare the risks reduction, other factors of  
4 the alternative.

5           This will not meet the cleanup  
6 criteria. It won't protect the groundwater if  
7 the soils are currently impacting the  
8 groundwater. There's no cost associated with  
9 that alternative.

10           Limited-action alternatives are  
11 generally institutional controls or access  
12 restrictions that don't actively remediate  
13 contaminated soil, but do prevent exposures  
14 through education programs, notices, access  
15 restrictions, deed notices, those types of  
16 actions.

17           This alternative, this scenario,  
18 because the objective is to protect migration of  
19 contaminants to groundwater, this alternative  
20 also does not meet the remedial action objective  
21 for the site and would have a cost of about  
22 \$27,000 to implement those controls.

23           The third alternative includes  
24 soil vapor extraction treatment at the soil area  
25 near the dry cleaning building under the parking

1 lot, and an excavation of contaminant of the hot  
2 spot of contamination at the 21 Maple Street  
3 parking lot. This alternative through the soil  
4 extraction, the excavation, would remove all of  
5 the contamination that's been determined to be  
6 potentially impacting the groundwater, and also  
7 includes a contingency system, the area behind --  
8 these are the two areas I'm discussing. The  
9 hot spot in the parking lot at 21 Maple is right  
10 here.

11                   These green samples show the  
12 additional work that was done just in April of  
13 this year. That would be excavated under this  
14 alternative. The other area is right here, and  
15 the parking lot behind the cleaners. That would  
16 be street treated by Soil Vapor Extraction.  
17 This one has not been totally delineated, as  
18 this one has, and there's the potential that  
19 there may be some contamination under the  
20 building.

21                   This alternative includes the  
22 potential to add additional wells beneath the  
23 building to provide additional treatment if  
24 contaminated soils are found underneath the dry  
25 cleaning building.

1           The last alternative we looked at  
2 is excavation of the two areas. Again, this  
3 would remove the contamination, prevent  
4 potential migration of contamination into the  
5 groundwater; and again, this also includes the  
6 contingency to do soil vapor extraction beneath  
7 the building if the contamination is found to be  
8 present under there above the cleanup criteria.

9           Again, this slide shows the same  
10 hot spot area out at 21 Maple Street, and here  
11 this area behind the dry cleaner building.  
12 Again, it's not been fully defined, and there is  
13 the potential that that could extend under the  
14 building. During the design phase, which is the  
15 next phase of the project, a pre-design  
16 investigation would be conducted, additional  
17 sampling in this area to be determine if there  
18 is contamination below the building that needs  
19 to be treated; and if that's the case, the  
20 contingency plan can be implemented.

21           Again, it's the same plan that's  
22 shown on the previous slide with soil vapor  
23 extraction wells beneath the building.

24           With that, I'm going to turn it  
25 over to Brian who is going to talk about the

1 selected remedy.

2                   MR. QUINN: Well, you just  
3 finished hearing everything we discussed tonight  
4 about the investigations that led us, the  
5 remedial investigation to define the extent of  
6 the contamination, the Feasibility Study which  
7 then evaluated the best ways to get rid of the  
8 contamination, and now what we did is after we  
9 got these reports we evaluated the alternatives  
10 of the four that Bob had just gone through  
11 before, the no action, the limited action, the  
12 Soil Vapor Extraction with hot spot removal, as  
13 well as the fourth one which is the one that's  
14 on the board, the excavation with off-site  
15 treatment of the excavated material, and  
16 potential SVE Soil Vapor Extraction system  
17 installed.

18                   The EPA prefers the remedy that's  
19 on the board, the fourth remedy, basically,  
20 because it would -- the first two really do not  
21 remove the soil. So there is a continuing  
22 source to the groundwater, and the ultimate goal  
23 of us being in this Borough is to clean the  
24 groundwater so that the Borough is not  
25 responsible to be treating the water any longer,

1 at least as far as the contaminants in the  
2 water.

3                   If you keep the source area, it's  
4 the longer that the treatment systems that are  
5 installed will have to operate. If we eliminate  
6 the source, it shortens the treatment time for  
7 the groundwater treatment buildings.

8                   The other way we looked at it, we  
9 looked at all of the evaluation criteria that  
10 Bob had gone through, and this one we felt was  
11 the best fit for all points as well as the cost.

12                   The third remedy and fourth  
13 remedy are closest in accomplishing the goal of  
14 removing the contaminants, and the fourth one  
15 seems to remove it with the potential for if we  
16 need to add on the extra Soil Vapor Extraction,  
17 it extends the cost a little higher; but if we  
18 don't find any need to, it's obviously the most  
19 cost-effective way to remove it.

20                   As well as Bob just eluded to  
21 before, during the design process, we will be  
22 working closely with the Borough, the business  
23 owners, the police, and anybody else that would  
24 be involved to make sure that once the design of  
25 the process is ongoing, we know what we're going

1 to do. The impacts to the parking area or  
2 anything else, we'll try to in minimize those  
3 things with trying to time things or to allow  
4 for the businesses to continue operation as well  
5 as try to keep as much of the parking lot  
6 available for use as we can.

7 With that, we'll open it up to  
8 questions and answers.

9 MS. ECHOLS: We're going to open  
10 up for any comments, questions. One person at a  
11 time, and please stand and state your name for  
12 the stenographer so that she can take that down  
13 correctly.

14 Would you like to come up?

15 MR. BORIS: My name is Dr. John  
16 Boris. I was a former councilman with the  
17 Borough for 13 years, on the planning board for  
18 three. My credentials, I was with the EPA as an  
19 inspector of, let me give you, The Chief of  
20 Sampling of Analysis For the Emergency Response  
21 Team of Region II. So I worked with Joe.

22 I'm going to change my thought  
23 process here a bit and sort of ask some  
24 questions of the EPA, which have been on my mind  
25 for a while.

1 About 15 years ago, I stood in  
2 this very office, and I said why don't you try  
3 Soil Vapor Extraction. Fifteen years later,  
4 we're going to try it. Congratulations to you,  
5 but I have to ask the question why not then?

6 EPA, I was part of the team, did  
7 a study at Massachusetts and noticed it with  
8 under the Superfund Investigation Technology  
9 Assessment Or Evaluation, the site program. We  
10 removed most of the volatile organic chemicals  
11 in a machine manufacturing process like  
12 Klockner's within 90 days. I said at the time  
13 why don't we try and look at it. They said,  
14 well, we're going to evaluate it later. It's  
15 now 15 years later.

16 What I'm worried about is the  
17 time element here. We have been under this  
18 pressure of drinking contaminated water or the  
19 possibility of it; and luckily, Joe has the  
20 process whereby we remove with carbon and even  
21 the second guy in charge of research and  
22 development said at EPA that's not the best way  
23 to go, okay? So now we're at this point and  
24 congratulations to you; you finally saw the  
25 wisdom of doing something different. It was a

1 soil type. We all know what resides in the  
2 soil. What concerns me is how long it takes to  
3 get these evaluations done. You know, I'm on  
4 many Superfunds. I've been on Love Canal. I do  
5 Superfund sites in Brooklyn, New York. We get  
6 thousands of samples per day. I see 19 samples  
7 and 46 samples respectfully. That's a picnic,  
8 really, to get an idea of what's happening here.

9 My point here is this: We got to  
10 really operate to get things going here. Last  
11 time we met here 15 years ago, the project, when  
12 the time was, to be for not treating the water  
13 any longer, 27 years. We can look that up;  
14 27 years. You know what it is now? It's  
15 30 years. I'm saying to myself, did we fail  
16 somehow? Now, I'm glad we're doing this, but it  
17 sort of takes me aback to ask these questions in  
18 front of you. It's sort of embarrassing because  
19 I do wear an EPA hat. I'm an unpaid consultant  
20 to the EPA of environmental education. I have  
21 to tell people we're really moving forward, but  
22 Rockaway Borough is my interest, and I want to  
23 see it done quicker.

24 For example, I would ask the  
25 question: How much remediation of the

1 groundwater have we done? Are we 15 years into  
2 it? Are we going to reach 27 years? I don't  
3 think so. Could you answer that question? When  
4 we will stop treating water? Is there an answer  
5 to that question? Fifteen years ago, it was  
6 27 years. Look up those records. Maybe some of  
7 you people weren't even here, people here may be  
8 retired.

9                   How about UV light? UV light  
10 destroys chlorinated hydrocarbons. I mentioned  
11 that years ago. I said put a UV light in the  
12 system. They do that in Roxbury. They use a UV  
13 light, it breaks down chlorinators. Boom. You  
14 know what a UV light costs? Maybe a thousand  
15 dollars, \$2,000.

16                   I think that's about what I  
17 wanted to address. My chagrin as to seeing  
18 Rockaway Borough, not the short end of the  
19 stick, but I think we're talking a lot about  
20 controlling our contamination. I see more and  
21 more contamination occurring. Joe has no  
22 control over it. I find more and more  
23 particles, charcoal particles in my water  
24 system. You know, every one of those is  
25 removing some sort of volatile organic chemical.

1 The system is incomplete.

2           So I want you to consider that  
3 I'm on your side, and don't tell my boss at EPA  
4 in Region II; but as an unpaid consultant, I  
5 really would like to see this move a little bit  
6 faster. Thank you.

7           MS. ECHOLS: Thank you.

8           MR. QUINN: I think it's a common  
9 misconception here. I think the Mayor has  
10 expressed it to me as well as the town clerk,  
11 the water you drink is not contaminated. So it  
12 is well treated. It's doubly treated.

13           The system was installed with the  
14 addition of carbon a couple of years later to  
15 help polish the water. The water that comes  
16 through is fine. As far as the rest of the  
17 stuff, we'll look into that. I want to make  
18 sure that I clear up that misconception. The  
19 water you drink is not contaminated. The  
20 groundwater before it gets into the system is  
21 contaminated, and that's what we're here to  
22 address.

23           MS. ECHOLS: Anyone else have a  
24 question? Sir, would you please come forward.  
25 Thank you. State your name.

1 MR. BERNARD: Bernard, my name is  
2 Arnold Bernard. I live on Union Street. My  
3 question to you is during this remediation, what  
4 type of air monitoring are you going to be  
5 doing? When I say air monitoring, I don't only  
6 mean particle in the air from soil disruption,  
7 but also vapor and what protections are in  
8 place, as far as I go to the barber shop there.  
9 What are the concerns there as far as high  
10 volume collection of vapor in that shop? Is  
11 there anything being done with that?

12 My other concern is when would  
13 this work be done? During the evening hours,  
14 the daytime hours, and what's in place for that  
15 when the work is done? That's all.

16 MR. SIVAK: The way I hear it,  
17 sir, you asked two questions. The first is what  
18 type of community health and safety plan will be  
19 in place while the work is being done while the  
20 remediation is being done, and the second was --  
21 shoot, I forgot the second. What was your  
22 second question? I'm sorry.

23 MR. QUINN: The time.

24 MR. SIVAK: When will the work be  
25 done. Okay. The next phase, once a remedy is

1 selected, once we gather everybody's comments  
2 tonight and answer them, we will select a remedy  
3 and that's memorialized in a document called a  
4 Record of Decision. It's signed by our regional  
5 administrator, and it becomes the official  
6 record of EPA's decision on how we will  
7 remediate the soils at the Wall Street site.

8           After that, the next step is what  
9 we call remedial design. We're going to come  
10 out and collect a little more data to try to  
11 figure out exactly where is the contamination.  
12 That's part of the remedial design.

13           Another component of the remedial  
14 design is to develop a community health and  
15 safety plan. EPA has a lot of experience in  
16 excavating soils in communities. Unfortunately,  
17 we have a lot of experience in dealing with  
18 sites like that, particularly in our region  
19 where we deal with sites in New York and New  
20 Jersey; and fortunately, we have funded sites in  
21 communities all of the time. We understand the  
22 types of controls that we need to have in place.  
23 The types of fence line monitoring that we need  
24 to have in place to make sure that the people  
25 who live right on the other side of those fences

1 are the people who work right on the other side  
2 of those fences. We can provide a level of  
3 confidence that nothing is getting off of the  
4 site; and if our fence line monitoring does  
5 suggest that perhaps something is going  
6 off-site, we typically introduce controls like  
7 shutting down the site, wetting down the soils  
8 to reduce the dust and things like that that  
9 might escape.

10                   The other part of your first  
11 question was what about the vapors that may be  
12 released as we go on and dig up some of the  
13 soil? That's going to be part of our plan  
14 system.

15                   The one thing about the vapors  
16 though especially in the ambient air and  
17 especially at the concentrations that we have  
18 seen here, once these vapors are introduced,  
19 there's a lot of dispersion. There's a lot of  
20 dissolution to often times very, very quickly to  
21 levels that are below levels of concern. So we  
22 will certainly monitor for that, and that is  
23 something that is not an unlikely phenomenon.

24                   MR. BERNARD: Will there be  
25 random monitoring throughout the community?

1 MR. SIVAK: Ambient monitoring  
2 throughout the community?

3 MR. BERNARD: Random, different  
4 streets, different neighborhoods.

5 MR. SIVAK: We can do that as we  
6 develop our community health and safety plan.

7 MR. QUINN: We'll probably have  
8 more information, not as formal as this session,  
9 but we've had in the past informational sessions  
10 where we can have more focused things to  
11 discuss, specific topics, especially once we  
12 talk with the Mayor and we keep them informed,  
13 when they find that there's a need that we may  
14 need to further inform the public. We would  
15 like -- we have come out twice before to meet  
16 with the residents to discuss the project, and  
17 we will just continue to come out anytime we  
18 need to.

19 MR. BERNARD: Is there going to  
20 be any type of newsletters where we can go to  
21 the town hall and pick them up to keep us  
22 abreast of what's going on as far as that?

23 MS. ECHOLS: We prepare Community  
24 Updates. If you feel that you need -- if the  
25 community feels that they need more than the

1 community Updates we put out -- we usually put  
2 out one every six months; but if you feel you  
3 need one every month or every two weeks, we can  
4 do that.

5 MR. BERNARD: While the work is  
6 going on?

7 MS. ECHOLS: Absolutely.

8 MR. BERNARD: Weekly updates  
9 printed out where I can stop there on my way to  
10 work and pick something up, just to keep updated  
11 what's going on.

12 MS. ECHOLS: We can prepare that  
13 for you.

14 MR. QUINN: The second part of  
15 your question as far as the timing, we can't  
16 tell you when it's going to start, because the  
17 first phase is we have to design, then the  
18 design puts a cost element together to go to our  
19 headquarters to give us money to do it. Once it  
20 falls into place, we'll be able to get out there  
21 and do the actual physical work.

22 While the design is going on,  
23 we'll be working with the community. We already  
24 had several meetings with the groundwater  
25 treatment plan with the Borough, the police

1 force and everybody that make sure we don't do  
2 something during school hours so the buses can  
3 have free use of the roads; things of that  
4 nature.

5                   Nighttime excavation is probably  
6 not a smart thing because it's loud. We don't  
7 want -- people are going to try to sleep. We're  
8 probably going to do things after rush hour,  
9 before rush hour, things of that nature. We're  
10 sensitive to those things, and that will come  
11 out during the design process.

12                   MR. BERNARD: Will there be road  
13 closings for this?

14                   MR. QUINN: The parking lot that  
15 will be closed off, and there could be something  
16 temporarily while rigs are being moved in and  
17 out. We may have to stop traffic so a truck or  
18 backhoe or whatever we use has to get out on the  
19 roads, because it's not like it's easy for a big  
20 Mack truck to make a left-hand turn in that  
21 area.

22                   MR. BERNARD: One other thing I  
23 didn't bring up is how about on-site security?  
24 Who is going to be responsible for that.

25                   MR. QUINN: That will be part of

1 the project, if it's necessary; and again, if  
2 the police feel they can handle it, they'll do  
3 it. If they feel it's something outside of  
4 their thing, it's something that could be  
5 brought up when we go out and do the work, like  
6 we have a security guard on-site.

7 MR. BERNARD: To make sure that  
8 drums and something --

9 MR. QUINN: Correct.

10 MR. BERNARD: -- doesn't leave  
11 the site and in the middle of the street  
12 someplace by some child?

13 MR. QUINN: Right. With this one  
14 we have been talking to the police about  
15 securing when we stage our stuff for the  
16 groundwater, to protect -- they'll usually take  
17 the keys out of the rigs, but to make sure  
18 windows don't get broken, gages, things like  
19 that that kids could say let's play on it and  
20 break it.

21 We did ask them to make extra  
22 spins by it every so often; and if the need  
23 arises, we can hire someone.

24 MR. SCHAEFER: Bob Schaefer,  
25 Councilman Schaefer. How much of the parking

1 lot is actually going to be impeded and for how  
2 long? It's a pretty busy thoroughfare. As you  
3 know, the police department is right there. We  
4 use that for ingress in from Wall Street and  
5 over, as well as the businesses there. There  
6 are businesses there that continue to operate  
7 that rely on the parking and access from the  
8 rear, deliveries and such.

9           So, you know, those are things  
10 that we here about from the Mayor and Council,  
11 and I think we need to take particular care if  
12 there is going to be interruption, to make -- be  
13 well indicated an coordinated.

14           MR. QUINN: That will come out  
15 during the design. Until we get out there and  
16 see how much area, how much room the rigs need  
17 to work, you know, they may be able to work in a  
18 minimal area or a different area. That will all  
19 dictate how much the parking lot will have to be  
20 taken out.

21           Most of the work should only take  
22 a short-term, like around three months or so to  
23 do the excavation; hopefully less, but, you  
24 know, for the excavation.

25           MR. SCHAEFER: You're only take

1 taking 40 yards?

2 MR. QUINN: Twenty yards from one  
3 spot and 20 from the other spot. You got to  
4 excavate it, and then you have to sample it to  
5 make sure you got all of it, excavate a little  
6 more to make sure you didn't miss. You have to  
7 get a piece, get it off-site, logistical issue  
8 that extends the timeline, but that's the  
9 answer.

10 DR. BORIS: Is there a  
11 requirement for a periodic or a five-year  
12 progress report on all Superfund sites; and if  
13 so, have they been added to the library's  
14 progress report?

15 MR. QUINN: They're called  
16 five-year reviews, and they're required at the  
17 completion of the remedial action; and because  
18 when I started talking tonight, I mentioned how  
19 complex the site is, there's two groundwater  
20 plumes and two source areas. Each one of those  
21 is ongoing. Until all four of those are  
22 completed, then the remedial action for the site  
23 is considered closed; and at that point, then,  
24 once the final remedial action is completed,  
25 from that date that that's assigned, we do a

1 remedial action report five years from then and  
2 five years from then --

3 DR. BORIS: It's about 20 years.

4 MR. BERNARD: Arnold Bernard  
5 again. I have one question. Could you define  
6 to us, the public, what you mean by the word  
7 plume?

8 MR. QUINN: Sure. The plume is  
9 the contamination that's in the groundwater.  
10 The best way I can think to give you an idea is  
11 an oil slick on water. It's basically water --  
12 contamination of the water that travels with the  
13 path water flow and it sits there. That's what  
14 a plume is considered, the amount of  
15 contamination in the groundwater that they refer  
16 to it as a plume to tell you that that's to  
17 signify what part of the groundwater is  
18 contaminated.

19 MR. BERNARD: That contamination  
20 is what's off-gassing or vaporizing, I should  
21 say, off of that plume?

22 MR. QUINN: Yes. When we were at  
23 your house, part of the vapor intrusion stuff,  
24 that's what we would look at.

25 MS. ECHOLS: Anyone else have a

1 question or a comment? Please come up.

2 MR. HILER: Hiler, H-i-l-e-r,  
3 Scott Hiler. I have a couple of questions. I  
4 have a whole file of this case and of both  
5 contamination plumes. My question, first  
6 question, I know you're dealing with the Main  
7 Street plume at this point, but is the Klockner  
8 and Klockner plume completely cleaned at this  
9 point? That's my first question.

10 MR. QUINN: No. The treatment  
11 system was just turned on in January of this  
12 year and just started operation. It's still  
13 brand new.

14 MR. HILER: In regards to that  
15 contamination plume, what sort of properties  
16 were tested for vapor intrusion in their  
17 basements and in their homes in that area?

18 MR. QUINN: In the Klockner and  
19 Klockner portion again, over in the Elm, Stickel  
20 location of town. We initially went out and did  
21 17 homes, a combination down Maple Avenue; and  
22 to cover both applications, we did nine and  
23 eight homes of -- we tried to take a  
24 representative sample of every other home.

25 Based on those samples, we are

1 still evaluating the data and going out to do  
2 some further data, a more extensive study in the  
3 next couple of months. We're going to send  
4 letters out asking people to come in.

5 I initially sent out 30 letters  
6 to people, and a lot of people weren't -- didn't  
7 reply back and weren't interested in part of the  
8 study to begin with. These are people that  
9 allowed to us come into their homes; and  
10 hopefully, more will participate in the future.

11 MR. HILER: I find it really  
12 disturbing that New Jersey has 120 Superfunds,  
13 which is more than any other state in the  
14 nation, and has there been any responsible  
15 parties identified with either of these plumes;  
16 and if so, has there been any litigation,  
17 settlements or any payment on their behalf?

18 MR. QUINN: The Klockner and  
19 Klockner plume, the responsible parties are the  
20 owners of the property. They're the ones that  
21 are cleaning up both the soil, and the tenants  
22 at the time are the ones who are cleaning up the  
23 groundwater. Since then they've been bought and  
24 sold. They're the people that are doing the  
25 cleanup.

1           The East Main/Wall Street area,  
2 there was never a defined responsible party  
3 which is why EPA is doing the cleanup. There  
4 were a few smaller parties that settled.

5           MR. HILER: That's what I'm  
6 trying to determine. Who are those parties? Do  
7 we have them by name?

8           MR. QUINN: I have to go back to  
9 look at the settlement that was prior --

10          MR. HILER: They'll be  
11 responsible by the cleanup or EPA?

12          MR. QUINN: EPA is funding this.

13          MR. HILER: That concludes my  
14 questions.

15          DR. BORIS: I guess it's a  
16 monitoring question: What part of this  
17 remediation is Rockaway Borough going to pay, if  
18 any?

19          MR. QUINN: None.

20          DR. BORIS: Thank you. It makes  
21 me feel better.

22          MR. BERNARD: Arnold Bernard is  
23 the name. Has there been any kind of, I don't  
24 want to use the word study, for lack of a better  
25 word that comes to mind, but how this is going

1 to affect our property values? The reason why I  
2 bring that up is because I have a friend at work  
3 that was looking to purchase property up here, a  
4 house up here; and when they found out this was  
5 a Superfund site, they decided not to buy.

6 MR. SIVAK: I'll try to answer it  
7 and Bob you can --

8 MR. MCKNIGHT: The site has been  
9 around for a very long time. I think whatever  
10 impacts you would expect to see have already  
11 occurred. We're talking about a very small  
12 aspect of the overall site, which is cleanup.

13 MR. BERNARD: Is there any  
14 publicity that's going to be done when it has  
15 been cleaned up?

16 MR. MCKNIGHT: When it has.

17 MR. BERNARD: There hasn't -- is  
18 there any timeline at this point?

19 MR. MCKNIGHT: Not at this point.

20 MS. ECHOLS: Any more questions?  
21 State your name.

22 MR. HAFNER: H-a-f-n-e-r. It's  
23 rather vague: When are they going to start  
24 digging up the ground and when are they going to  
25 be done with the soil? The soil is -- getting

1 rid of the soil is a key issue, because that's  
2 where the contamination is. As long as the soil  
3 is there it continues to leech; is that correct?

4 MR. QUINN: Yes.

5 MR. HAFNER: When would they have  
6 treated the soil? When are they going to start,  
7 and when is it going to be done?

8 MR. QUINN: As I stated earlier,  
9 we come -- after we're finished here, the next  
10 is September 11th for the people who couldn't  
11 come here today. We take those comments and  
12 make the decision on the remedy which we prefer,  
13 the fourth remedy of excavation.

14 If that's the final remedy, we  
15 put it in the Record of Decision. From that  
16 point on, we start the process which we look at  
17 the area, we design the remedy, and then we fund  
18 the remedial action. I can't give you a  
19 timeline, because based on the EPA funding is  
20 how everything progresses.

21 If the fund suggests and the  
22 timing is right, it's going to move smooth, but  
23 if there's a blip because funding is cut, it's  
24 hard to say when we'll do stuff. That's the  
25 process. We have to design it first and then

1 actually go out.

2                   So we would love for it to happen  
3 tomorrow, but we still have steps in the process  
4 to go through.

5                   MR. HAFNER: My concern is it's  
6 been 15 years so far. Nothing has been done.  
7 Nothing has been done about the problem.

8                   MR. QUINN: We have one treatment  
9 that's up and running, and the other one which  
10 is about to be constructed.

11                   MR. HAFNER: That was done by a  
12 private party.

13                   MR. QUINN: Ours. The EPA is in  
14 the process of being installed. We have been  
15 talking about, like I mentioned earlier, with  
16 the Borough about coordinating the insulation of  
17 wells as well as other stuff.

18                   MR. HAFNER: That's the one  
19 design by the Army Corp. of Engineers to treat  
20 the water?

21                   MR. QUINN: It was designed by  
22 the BRB. They designed it as part of a  
23 settlement, both systems. The Army Corp. is  
24 actually putting it in place.

25                   MR. HAFNER: They're building it?

1 MR. QUINN: Correct.

2 MR. SIVAK: That design, even  
3 though it was designed and built by the  
4 responsible parties, it was still done under EPA  
5 oversight. We still reviewed that entire  
6 process.

7 MR. HAFNER: My concern is still  
8 you can come back here in five years for another  
9 meeting and still nothing has been dug up.

10 MR. QUINN: We're hoping that  
11 won't be the situation.

12 MR. HAFNER: But what you're  
13 telling me is you can't answer that question?

14 MR. QUINN: Unfortunately, I  
15 can't give you a concrete answer on that.

16 MR. HAFNER: Thank you.

17 MS. ECHOLS: Any more questions?

18 MR. HILER: Scott Hiler again.  
19 Back to the responsible parties, how come it was  
20 paid for by the responsible parties on the plume  
21 by Elm Street, but funded by the EPA on East  
22 Main Street, especially after there was a  
23 settlement where you say it was unknown or you  
24 claim to say it's unknown?

25 MR. QUINN: I just claim that I

1 don't know the specifics of the settlement. The  
2 reason the other parties are, they had the  
3 financial wherewithal to do the cleanup. The  
4 other parties, the reason they would settle such  
5 a small amount, they don't have the financial  
6 wherewithal. So they settled to the most of  
7 their capacity to help pay some past costs.

8           If there was somebody who was  
9 found to do it, we would gladly have them do it.  
10 It's either sit there or EPA has to do the work.  
11 That's the nature from the Superfund.

12           MR. HILER: From what I  
13 understand, it was an Act initiated by congress  
14 and designed for the polluters themselves to  
15 pay, not the tax payers. So I kind of don't  
16 understand how it's on the ability to pay  
17 principal where the polluters pay if they can,  
18 not, you know -- I don't understand that quite  
19 well.

20           MR. SIVAK: That concept of the  
21 polluter pays, the Superfund was a tax that was  
22 levied on corporations and industries that  
23 created or processed hazardous waste. That was  
24 the Polluter Pays Principal. That tax expired I  
25 think it was in '96, the mid 90s, somewhere in

1 there. So now that fund is just whatever is  
2 left of it. There's no more money going into it  
3 at all.

4                   When we have responsible parties,  
5 we offer them the opportunity to perform the  
6 cleanup under EPA oversight. If they have the  
7 financial wherewithal as I said before. If they  
8 don't have the financial wherewithal, then EPA  
9 funds the cleanup under the Superfund.

10                   MR. HILER: One more question:  
11 How long have we known the contamination has  
12 been here? I know we discussed it around 1981  
13 or 80. Do we know how long it's been here  
14 before then?

15                   MR. QUINN: No.

16                   MR. HILER: We don't. So  
17 potentially whoever did this, whether it was  
18 accidental or intentional, this could have been  
19 around for decades; is that a fair statement?

20                   MR. QUINN: Sure.

21                   MR. HILER: This could have been  
22 potentially harming the drinking water of the  
23 people up until 1980?

24                   MR. QUINN: I mean it could be.  
25 I don't know what the procedures were to test

1 water back in the day. So I can't...

2 MR. HILER: This further just  
3 disturbs -- makes me disturbed that if that was  
4 intentional, just to know that they could have  
5 affected the health of thousands of people for  
6 decades until this was discovered in 1980.

7 I was born in 1980. I probably  
8 escaped a lot of contamination where a lot of  
9 people in this room might have been subjected,  
10 and I think this should be criminal if this was  
11 found out to be intentional. Thank you.

12 MAYOR LOCKWOOD: Mary Lockwood,  
13 I'm the Mayor of Rockaway Borough. I happen to  
14 have been around at that time, and I remember at  
15 that time when our water was tested. There was  
16 nothing to actually test -- the test had not  
17 been invented yet for PCE and TCE. We were one  
18 of the first to find out we had pollution. The  
19 test hadn't been invented.

20 DR. BORIS: I'll confirm that  
21 with Mary. I was there before Mary. I was head  
22 of Public Works, Commission of Public Works.  
23 It's got to be 50 years. Our water came out  
24 bacteriologically sound, not one organism. Why?  
25 Because nothing could live in it. There were no

1 methods of determining.

2                   Mary is absolutely correct. The  
3 technology advances to a point where we're  
4 determining parts, one part per billion is one  
5 second in 33 years, and that's how far we're  
6 going down.

7                   We're locating those things that  
8 are dangerous, and we're trying to correct them.  
9 I'm on EPA's side of this, because we didn't  
10 have the technology which to work with before.

11                   MS. ECHOLS: Thank you. Any more  
12 questions? Anymore comments?

13                   MS. HOOK: Bonnie Hook, 23  
14 Jackson Avenue. I want to know if anything has  
15 been done, or do we know that we're preventing  
16 any further contamination?

17                   MR. QUINN: Well, the people in  
18 the areas, they have to follow strict guidelines  
19 for hazardous waste. They have to document with  
20 anything they do with waste. So there's a lot  
21 less chance of somebody doing something. If  
22 they get so much in, they have to show that they  
23 get rid of so much.

24                   MS. HOOK: You're monitoring  
25 them?

1 MR. QUINN: Different people  
2 monitor. The State has some responsibilities  
3 and I'm guessing the county.

4 MS. HOOK: Is there any  
5 difference now than it was years ago?

6 MR. QUINN: Yes.

7 MS. HOOK: Especially since we  
8 know it's a site, it's being more aggressive.

9 MR. QUINN: Just in general, the  
10 requirements for people who do deal with any  
11 kind of hazardous materials is a lot stricter  
12 nowadays than it was 15, ten years ago.

13 MS. HOOK: Nothing special  
14 because it's a site?

15 MR. QUINN: No.

16 MS. HOOK: Thank you.

17 MS. ECHOLS: Any more questions?

18 (No response.)

19 MS. ECHOLS: Any more comments?

20 (No response.)

21 MS. ECHOLS: My name is, as well  
22 as Brian's are on the slide, also in your  
23 handouts. You can E-mail Brian or myself with  
24 any more comments or questions. You can call  
25 us, and all of your comments and questions will

1 be part of the Responsiveness Summary, which is  
2 part of the transcript which will be included in  
3 the Record of Decision signed by the regional  
4 administrator.

5 DR. BORIS: Is that to one person  
6 or both of you?

7 MS. ECHOLS: You can send it to  
8 either one of us. You probably want to send it  
9 to Brian.

10 DR. BORIS: Thank you.

11 MS. ECHOLS: If you want, you can  
12 send to it me and I will send it to Brian or you  
13 can call the 800 number.

14 DR. BORIS: Okay.

15 MS. ECHOLS: In the future  
16 regarding this project, you can always reach out  
17 to Brian or myself. We're always available to  
18 answer any of your questions or concerns about  
19 the site.

20 I would like to thank everyone  
21 for coming out this evening, and the Public  
22 Comment period will end on September 11th.  
23 Thank you.

24 (Hearing concluded at 8:23 p.m.)

25


## C E R T I F I C A T E

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25

I, SERAFINA R. ZINCKGRAF, a Certified Shorthand Reporter, Registered Professional Reporter and Notary Public of the State of New Jersey do hereby certify that prior to the commencement of the examination the witness was duly sworn by me to testify the truth, the whole truth and nothing but the truth.

I DO FURTHER CERTIFY that the foregoing is a true and accurate transcript of the testimony as taken stenographically by and before me at the time, place and on the date hereinbefore set forth, to the best of my ability.

I DO FURTHER CERTIFY that I am neither a relative nor employee nor attorney nor counsel of any of the parties to the action; and that I am neither a relative nor employee of such attorney or counsel; and that I am not financially interested in the action.



SERAFINA R. ZINCKGRAF, CSR, RPR  
License No. XI01637

A			
<p>aback 32:17 ability 17:11 52:16 58:14 able 39:20 42:17 above-entitled 2:3 abreast 38:22 absolutely 39:7 55:2 absorbed 16:4 absorbing 16:2 acceptable 17:16,21 acceptance 24:6 access 17:4 21:9 23:14 25:11,14 42:7 accidental 53:18 accomplishing 29:13 account 19:23 accurate 58:11 achieve 20:10 achieved 22:6 Act 52:13 action 15:18,21 24:19 24:20 25:20 28:11 28:11 43:17,22,24 44:1 49:18 58:17,20 actions 25:16 actively 25:12 activities 12:16 14:21 23:11 actual 11:14 39:21 add 26:22 29:16 added 43:13 addition 34:14 additional 9:7 26:12 26:22,23 27:16 address 21:6,20 22:15 33:17 34:22 administrator 36:5 57:4 advances 55:3 affect 48:1 agenda 3:16 aggressive 56:8 ago 31:1 32:11 33:5 33:11 56:5,12 air 35:4,5,6 37:16 airspace 18:17 allow 30:3</p>	<p>allowed 46:9 alternative 20:10 21:20 22:6,8,10 23:7,14,21 24:20,21 24:24 25:1,4,9,17 25:19,23 26:3,14,21 27:1 alternatives 20:11 21:13,16,19 22:14 22:15 23:17 24:15 25:2,10 28:9 ambient 37:16 38:1 amount 10:17 44:14 52:5 analysis 12:6,6 30:20 answer 15:12 23:23 33:3,4 36:2 43:9 48:6 51:13,15 57:18 answers 4:12 6:13 30:8 anybody 29:23 Anymore 55:12 anytime 38:17 applicable 22:2 applications 45:22 appropriate 22:2 approximately 5:17 11:2 13:22 14:18 April 12:21 13:10 26:12 archaeological 12:8 architectural 11:24 area 3:9 7:14,15,16 7:24 8:1,3,6,15,16 8:21 9:10,12,16 10:2,7,9,24 11:19 11:21,21 12:11 13:3 14:7,10,10 16:20 23:2,10 25:24 26:7 26:14 27:10,11,17 29:3 30:1 40:21 42:16,18,18 45:17 47:1 49:17 areas 7:13 8:1 19:13 19:19,20 24:16 26:8 27:2 43:20 55:18 arises 41:23 Army 50:19,23 Arnold 35:2 44:4</p>	<p>47:22 asked 35:17 asking 46:4 aspect 48:12 asphalt 14:9,10 assessment 4:3 14:23 15:6,12 17:11 18:7 18:8,20 19:7 20:8 20:16 31:9 assessments 15:2 assessor 1:16 4:4 14:25 assigned 43:25 associated 12:12 17:20 18:1 22:20 25:8 attorney 58:16,19 August 1:5 2:9 6:3 auto 9:19 available 30:6 57:17 Avenue 10:11 12:22 45:21 55:14</p> <hr/> <p><b>B</b></p> <p>B 14:4,4,8,8 back 3:22 9:6 12:20 19:1 46:7 47:8 51:8 51:19 54:1 background 19:13 backhoe 40:18 bacteriologically 54:24 balancing 22:12 Bank 10:7 barber 35:8 based 9:4 12:15,24 20:18,21,23 21:8 45:25 49:19 basements 45:17 basic 19:9 basically 15:11 17:9 20:25 22:9,12 28:19 44:11 bear 6:19 began 6:2,24 behalf 46:17 beneath 16:21 26:22 27:6,23 Bernard 35:1,1,2</p>	<p>37:24 38:3,19 39:5 39:8 40:12,22 41:7 41:10 44:4,4,19 47:22,22 48:13,17 best 16:10 21:20 22:14 28:7 29:11 31:22 44:10 58:14 better 47:21,24 big 40:19 billion 55:4 bit 17:4 30:23 34:5 blip 49:23 board 28:14,19 30:17 Bob 1:18 4:15,24 20:2,3 28:10 29:10 29:20 41:24 48:7 body 9:19 Bonnie 55:13 Boom 33:13 borings 14:5 Boris 30:15,16 43:10 44:3 47:15,20 54:20 57:5,10,14 born 54:7 Borough 1:1,4 2:7 3:4 5:15 6:18 7:3 28:23,24 29:22 30:17 32:22 33:18 39:25 47:17 50:16 54:13 boss 34:3 bought 46:23 boulders 14:14 brand 45:13 BRB 50:22 break 41:20 breaks 33:13 Brian 1:14 3:17 4:9 4:14 6:14,17 27:25 56:23 57:9,12,17 Brian's 56:22 bring 5:5 18:22 40:23 48:2 broken 41:18 Brooklyn 32:5 brought 41:5 building 10:7 25:25 26:20,23,25 27:7,11 27:14,18,23 50:25</p>

<p><b>buildings</b> 12:13 29:7  <b>built</b> 6:24 8:8,8,9  51:3  <b>buses</b> 40:2  <b>business</b> 29:22  <b>businesses</b> 30:4 42:5  42:6  <b>busy</b> 42:2  <b>buy</b> 48:5</p> <hr/> <p style="text-align: center;"><b>C</b></p> <p><b>C</b> 2:2 58:1,1  <b>call</b> 5:25 14:2 36:9  56:24 57:13  <b>called</b> 7:6,21 8:4,6  36:3 43:15  <b>Canal</b> 9:17 10:1  12:13 32:4  <b>can't</b> 22:8 23:2 39:15  49:18 51:13,15 54:1  <b>capacity</b> 52:7  <b>capital</b> 23:18  <b>car</b> 16:14  <b>carbon</b> 31:20 34:14  <b>carcinogenic</b> 17:9  <b>care</b> 42:11  <b>case</b> 27:19 45:4  <b>caused</b> 7:10  <b>Cecelia</b> 3:2,17  <b>Cecilia</b> 1:13  <b>Center</b> 1:4 2:8  <b>certainly</b> 37:22  <b>Certified</b> 2:4 58:3  <b>certify</b> 58:6,10,15  <b>chagrin</b> 33:17  <b>chance</b> 55:21  <b>change</b> 30:22  <b>characterized</b> 13:25  <b>charcoal</b> 33:23  <b>charge</b> 31:21  <b>chemical</b> 8:4 33:25  <b>chemicals</b> 8:2 19:23  31:10  <b>Chief</b> 1:18 4:15 30:19  <b>child</b> 41:12  <b>chlorinated</b> 33:10  <b>chlorinators</b> 33:13  <b>Chozick</b> 1:17 4:5  20:3,3</p>	<p><b>Citizen</b> 6:5  <b>claim</b> 51:24,25  <b>clean</b> 8:14 21:13  28:23  <b>cleaned</b> 45:8 48:15  <b>cleaner</b> 27:11  <b>cleaners</b> 26:15  <b>cleaning</b> 5:9 8:11  9:20 10:8 25:25  26:25 46:21,22  <b>cleanup</b> 3:7 4:10 5:10  13:3 20:24 22:5  25:5 27:8 46:25  47:3,11 48:12 52:3  53:6,9  <b>clear</b> 6:20 34:18  <b>clerk</b> 34:10  <b>closed</b> 40:15 43:23  <b>closely</b> 29:22  <b>closest</b> 29:13  <b>closings</b> 40:13  <b>Cobb</b> 8:9  <b>cobble</b> 14:14  <b>cobbles</b> 14:17  <b>collaboration</b> 6:7  <b>collect</b> 13:16,19,20  19:2 36:10  <b>collected</b> 12:2,18  13:5 18:25  <b>collecting</b> 18:14,15  20:6  <b>collection</b> 35:10  <b>combination</b> 45:21  <b>combined</b> 21:12  <b>come</b> 3:11 5:12 12:11  15:22 20:12 21:12  21:17 30:14 34:24  36:9 38:15,17 40:10  42:14 45:1 46:4,9  49:9,11 51:8,19  <b>comes</b> 7:2 19:10  34:15 47:25  <b>coming</b> 5:5 8:3,5  11:15 16:13 57:21  <b>commencement</b> 58:6  <b>commencing</b> 2:10  <b>comment</b> 6:2 23:25  24:10 45:1 57:22  <b>comments</b> 4:11 6:7</p>	<p>6:13 30:10 36:1  49:11 55:12 56:19  56:24,25  <b>Commission</b> 54:22  <b>common</b> 34:8  <b>communities</b> 36:16  36:21  <b>community</b> 1:4,13  2:8 3:3 5:7,7,10,18  23:9 24:6,7 35:18  36:14 37:25 38:2,6  38:23,25 39:1,23  <b>compare</b> 21:19 22:13  25:2,3  <b>compared</b> 23:17  <b>completed</b> 8:16 43:22  43:24  <b>completely</b> 7:3 45:8  <b>completion</b> 43:17  <b>complex</b> 43:19  <b>compliance</b> 22:1  <b>complicated</b> 6:19  <b>component</b> 36:13  <b>compound</b> 16:6  <b>compounds</b> 13:1  <b>comprised</b> 10:24  14:1,13  <b>comprises</b> 10:11,22  14:5  <b>concentration</b> 13:6  <b>concentrations</b> 13:8  17:23 19:11,14  20:19 37:17  <b>concept</b> 52:20  <b>concern</b> 19:3 20:1  35:12 37:21 50:5  51:7  <b>concerns</b> 32:2 35:9  57:18  <b>concluded</b> 57:24  <b>concludes</b> 47:13  <b>concrete</b> 51:15  <b>concur</b> 23:25  <b>conditions</b> 10:2 16:17  21:9,9  <b>conducted</b> 11:4,6,11  12:17 18:21 27:16  <b>conducting</b> 18:8  <b>conducts</b> 15:6</p>	<p><b>confidence</b> 37:3  <b>confirm</b> 12:22 54:20  <b>confirmed</b> 13:11  <b>congratulations</b> 31:4  31:24  <b>congress</b> 52:13  <b>consider</b> 24:11 34:2  <b>considered</b> 21:22  22:9 43:23 44:14  <b>considers</b> 22:7  <b>consistent</b> 19:13  <b>constructed</b> 50:10  <b>constructing</b> 8:13  <b>construction</b> 16:24  17:3,13  <b>construed</b> 11:9  <b>consultant</b> 32:19  34:4  <b>contact</b> 15:22  <b>contaminant</b> 26:1  <b>contaminants</b> 7:4  11:10 15:8 16:7  18:10,13 21:7,10  23:1 25:19 29:1,14  <b>contaminated</b> 3:8  11:15 16:2,3,3  20:18 21:14 23:4  24:16,23 25:13  26:24 31:18 34:11  34:19,21 44:18  <b>contamination</b> 6:22  7:10,25 8:22 9:8  10:15,16,17,18  11:14 15:15 17:25  20:20 22:15,19,25  24:17 26:2,5,19  27:3,4,7,18 28:6,8  33:20,21 36:11 44:9  44:12,15,19 45:5,15  49:2 53:11 54:8  55:16  <b>contingency</b> 26:7  27:6,20  <b>continue</b> 18:3 30:4  38:17 42:6  <b>continues</b> 49:3  <b>continuing</b> 28:21  <b>contractor</b> 3:25 8:25  <b>control</b> 33:22</p>
---	---	---	--

<p><b>controlling</b> 33:20  <b>controls</b> 25:11,22  36:22 37:6  <b>coordinated</b> 42:13  <b>coordinating</b> 50:16  <b>Coordinator</b> 1:13 3:4  <b>Corp</b> 50:19,23  <b>corporations</b> 52:22  <b>correct</b> 41:9 49:3  51:1 55:2,8  <b>correctly</b> 30:13  <b>cost</b> 23:16,18 25:8,21  29:11,17 39:18  <b>costs</b> 23:19 33:14  52:7  <b>cost-effective</b> 29:19  <b>couldn't</b> 49:10  <b>Council</b> 42:10  <b>councilman</b> 30:16  41:25  <b>councilmen</b> 4:25  <b>counsel</b> 58:16,19  <b>county</b> 56:3  <b>couple</b> 13:12 34:14  45:3 46:3  <b>cover</b> 14:9,11,13  45:22  <b>created</b> 52:23  <b>credentials</b> 30:18  <b>criminal</b> 54:10  <b>criteria</b> 20:24 21:8,18  21:21,22 22:8,9,11  22:12,13 23:12,22  23:23 24:6,25 25:6  27:8 29:9  <b>Criteria</b> 23:16  <b>cross-section</b> 13:24  14:4,7  <b>CSR</b> 58:25  <b>cultural</b> 11:21,23  12:10  <b>current</b> 9:9,25 10:2  <b>currently</b> 9:22 15:16  19:1 24:2 25:7  <b>cut</b> 49:23  <b>cynders</b> 14:15</p>	<p>55:8  <b>data</b> 18:25 19:2 20:7  36:10 46:1,2  <b>date</b> 43:25 58:13  <b>day</b> 32:6 54:1  <b>days</b> 31:12  <b>daytime</b> 35:14  <b>deal</b> 24:16 36:19  56:10  <b>dealing</b> 36:17 45:6  <b>deals</b> 22:17,25  <b>decades</b> 53:19 54:6  <b>decided</b> 48:5  <b>decision</b> 6:5 7:12,20  36:4,6 49:12,15  57:3  <b>decision-making</b> 5:8  <b>deed</b> 25:15  <b>deep</b> 10:21,25 12:4  13:20  <b>deeper</b> 14:5 17:4  18:14  <b>define</b> 10:14 28:5  44:5  <b>defined</b> 27:12 47:2  <b>DeJeckyl(ph)</b> 5:2  <b>delineated</b> 9:10 26:17  <b>deliveries</b> 42:8  <b>DEP</b> 23:23 24:4  <b>department</b> 9:23  20:23 42:3  <b>depth</b> 10:23,25  <b>Dermal</b> 16:2  <b>described</b> 24:14  <b>design</b> 27:14 29:21  29:24 36:9,12,14  39:17,18,22 40:11  42:15 49:17,25  50:19 51:2  <b>designed</b> 5:6 50:21  50:22 51:3 52:14  <b>destroys</b> 33:10  <b>detected</b> 13:8  <b>determine</b> 9:7 10:15  11:18 14:1 15:6  27:17 47:6  <b>determined</b> 9:5 12:25  13:2 21:2 26:5  <b>determining</b> 55:1,4</p>	<p><b>develop</b> 20:9,14  36:14 38:6  <b>developed</b> 21:11,17  22:4 24:15  <b>development</b> 31:22  <b>dictate</b> 42:19  <b>didn't</b> 40:23 43:6  46:6 55:9  <b>difference</b> 56:5  <b>different</b> 8:2,7 31:25  38:3,4 42:18 56:1  <b>difficult</b> 23:13  <b>dig</b> 37:12  <b>digging</b> 48:24  <b>direct</b> 13:13  <b>discovered</b> 54:6  <b>discuss</b> 3:7,18,23 4:2  4:6,9 7:8 8:19,23  38:11,16  <b>discussed</b> 28:3 53:12  <b>discussing</b> 3:13 26:8  <b>dispersion</b> 37:19  <b>disruption</b> 35:6  <b>dissolution</b> 37:20  <b>distinctly</b> 8:2  <b>disturbed</b> 54:3  <b>disturbing</b> 46:12  <b>disturbs</b> 54:3  <b>document</b> 36:3 55:19  <b>doesn't</b> 41:10  <b>doing</b> 31:25 32:16  35:5 46:24 47:3  55:21  <b>dollars</b> 33:15  <b>don't</b> 25:12 29:18  31:2,13 33:2 34:3  35:5 40:1,6 41:18  47:23 52:1,5,15,18  53:8,16,25  <b>doubly</b> 34:12  <b>downtown</b> 9:12  <b>Dr</b> 30:15 43:10 44:3  47:15,20 54:20 57:5  57:10,14  <b>drill</b> 13:14  <b>drilling</b> 10:10 13:19  <b>drink</b> 7:5 34:11,19  <b>drinking</b> 6:23 31:18  53:22</p>	<p><b>drums</b> 41:8  <b>dry</b> 9:20 10:7 25:25  26:24 27:11  <b>dug</b> 51:9  <b>duly</b> 58:7  <b>dust</b> 16:6 37:8</p> <hr/> <p style="text-align: center;"><b>E</b></p> <hr/> <p><b>E</b> 1:10,10 58:1,1  <b>earlier</b> 7:9 49:8 50:15  <b>easily</b> 23:13,15  <b>East</b> 3:9 7:13,23 8:6  8:14,17,20 9:13  10:4,6 47:1 51:21  <b>easy</b> 40:19  <b>Echols</b> 1:13 3:1,3  4:22 5:4 30:9 34:7  34:23 38:23 39:7,12  44:25 48:20 51:17  55:11 56:17,19,21  57:7,11,15  <b>ecological</b> 4:3 11:17  15:2,9 19:6,9,15,21  20:1  <b>economist</b> 6:20  <b>education</b> 25:14  32:20  <b>effect</b> 19:15  <b>effectiveness</b> 22:16  23:5  <b>effort</b> 18:23  <b>eight</b> 45:23  <b>either</b> 46:15 52:10  57:8  <b>element</b> 31:17 39:18  <b>eliminate</b> 29:5  <b>eliminating</b> 22:25  <b>Elm</b> 7:15 45:19 51:21  <b>eluded</b> 29:20  <b>embarrassing</b> 32:18  <b>Emergency</b> 30:20  <b>employed</b> 13:18  <b>employee</b> 58:16,18  <b>ends</b> 6:3  <b>Engineers</b> 50:19  <b>entire</b> 51:5  <b>environment</b> 21:23  21:25 23:10  <b>environmental</b> 20:24</p>
<p style="text-align: center;"><b>D</b></p> <hr/> <p><b>dangerous</b> 11:19</p>			

<p>32:20  <b>environments</b> 11:20  <b>EPA</b> 3:20,25 4:4,13  4:17 5:16 8:12 9:1  15:5 18:8 19:8  21:17 22:4,7 24:2  24:25 28:18 30:18  30:24 31:6,22 32:19  32:20 34:3 36:15  47:3,11,12 49:19  50:13 51:4,21 52:10  53:6,8  <b>EPA's</b> 14:24 24:1  36:6 55:9  <b>equipment</b> 13:15  <b>escape</b> 37:9  <b>escaped</b> 54:8  <b>especially</b> 37:16,17  38:11 51:22 56:7  <b>evaluate</b> 20:7,11  31:14  <b>evaluated</b> 28:7,9  <b>evaluating</b> 46:1  <b>evaluation</b> 19:8 29:9  31:9  <b>evaluations</b> 32:3  <b>evening</b> 2:10 6:16  35:13 57:21  <b>everybody</b> 7:5 40:1  <b>everybody's</b> 36:1  <b>exactly</b> 36:11  <b>examination</b> 58:7  <b>example</b> 13:13 15:25  16:10,25 23:2 32:24  <b>excavate</b> 43:4,5  <b>excavated</b> 26:13  28:15  <b>excavating</b> 36:16  <b>excavation</b> 24:23  26:1,4 27:2 28:14  40:5 42:23,24 49:13  <b>excuse</b> 18:15  <b>existence</b> 12:23  <b>expect</b> 48:10  <b>experience</b> 36:15,17  <b>expired</b> 52:24  <b>exposed</b> 15:14,23,24  16:23 17:13  <b>exposure</b> 15:7 16:18</p>	<p>17:21  <b>exposures</b> 25:13  <b>expressed</b> 34:10  <b>extend</b> 27:13  <b>extends</b> 29:17 43:8  <b>extensive</b> 46:2  <b>extent</b> 10:14 28:5  <b>extra</b> 29:16 41:21  <b>extraction</b> 7:22 24:22  25:24 26:4,16 27:6  27:23 28:12,16  29:16 31:3  <b>E-mail</b> 6:8 56:23</p> <hr/> <p style="text-align: center;"><b>F</b></p> <hr/> <p><b>F</b> 58:1  <b>face</b> 9:3  <b>facilities</b> 9:19,21  16:24  <b>facility</b> 10:8  <b>factors</b> 19:22 25:3  <b>fail</b> 32:15  <b>fair</b> 53:19  <b>falls</b> 39:20  <b>familiar</b> 10:3 16:11  <b>far</b> 4:2 10:14 29:1  34:16 35:8,9 38:22  39:15 50:6 55:5  <b>faster</b> 34:6  <b>fax</b> 6:8  <b>feasibility</b> 1:17 4:6,7  7:7 9:2 15:5 20:5,7  21:4 23:25 24:5,13  28:6  <b>feel</b> 24:7 38:24 39:2  41:2,3 47:21  <b>feels</b> 38:25  <b>feet</b> 11:1,2 13:17,22  14:18  <b>felt</b> 29:10  <b>fence</b> 36:23 37:4  <b>fences</b> 36:25 37:2  <b>field</b> 11:3,7 12:1,16  12:21 13:11  <b>Fifteen</b> 31:3 33:5  <b>figure</b> 9:14 13:23  36:11  <b>file</b> 45:4  <b>fill</b> 14:16</p>	<p><b>filled</b> 10:1  <b>film</b> 14:12  <b>final</b> 24:11 43:24  49:14  <b>finally</b> 31:24  <b>financial</b> 52:3,5 53:7  53:8  <b>financially</b> 58:20  <b>find</b> 17:8 29:18 33:22  38:13 46:11 54:18  <b>findings</b> 9:4 14:23  19:10  <b>fine</b> 34:16  <b>finger nail</b> 16:11  <b>finished</b> 28:3 49:9  <b>first</b> 6:22 15:13 20:14  21:21 22:16 24:19  28:20 35:17 37:10  39:17 45:5,9 49:25  54:18  <b>fit</b> 29:11  <b>five</b> 22:11,12 44:1,2  51:8  <b>five-year</b> 43:11,16  <b>flow</b> 44:13  <b>focused</b> 12:21 13:10  38:10  <b>follow</b> 55:18  <b>footprint</b> 9:16  <b>force</b> 40:1  <b>foregoing</b> 58:10  <b>forgot</b> 35:21  <b>formal</b> 38:8  <b>former</b> 9:16,21,23,25  10:12 12:12 14:15  30:16  <b>forth</b> 58:14  <b>fortunately</b> 36:20  <b>forward</b> 32:21 34:24  <b>found</b> 6:23 15:1,8  19:11 20:16,18  21:10 26:24 27:7  48:4 52:9 54:11  <b>foundry</b> 9:21 10:12  14:15  <b>four</b> 24:15 28:10  43:21  <b>fourth</b> 24:22 28:13  28:19 29:12,14</p>	<p>49:13  <b>free</b> 5:15 40:3  <b>friend</b> 48:2  <b>front</b> 10:6 32:18  <b>full</b> 21:5  <b>fully</b> 27:12  <b>fund</b> 49:17,21 53:1  <b>funded</b> 36:20 51:21  <b>funding</b> 47:12 49:19  49:23  <b>funds</b> 53:9  <b>further</b> 7:17,19 38:14  46:2 54:2 55:16  58:10,15  <b>future</b> 15:18,21,23  16:24 17:18 46:10  57:15</p> <hr/> <p style="text-align: center;"><b>G</b></p> <hr/> <p><b>gages</b> 41:18  <b>gas</b> 10:20 11:11 16:16  <b>gasoline</b> 16:12,12,15  <b>gather</b> 36:1  <b>general</b> 56:9  <b>generally</b> 25:11  <b>generated</b> 7:24  <b>geophysical</b> 11:7  <b>getting</b> 37:3 48:25  <b>give</b> 5:24 6:18 30:19  39:19 44:10 49:18  51:15  <b>glad</b> 32:16  <b>gladly</b> 52:9  <b>go</b> 9:6 16:16 31:23  35:8 37:12 38:20  39:18 41:5 47:8  50:1,4  <b>goal</b> 20:9,22 28:22  29:13  <b>goals</b> 22:5  <b>going</b> 7:8 14:3,25  15:3,10 20:4 27:24  27:25 29:25 30:9,22  31:4,14 32:10 33:2  35:4 36:9 37:5,13  38:19,22 39:6,11,16  39:22 40:7,8,24  42:1,12 46:1,3  47:17,25 48:14,23</p>
---	--	---	---

48:24 49:6,7,22 53:2 55:6 good 6:16 19:15 grade 13:17 gravel 14:17 Great 6:15 green 26:11 ground 6:11 11:2 14:19 48:24 groundwater 7:22,22 8:13 13:3 17:24 18:4,5,15 20:21,25 21:3 23:3 24:18 25:6,8,19 26:6 27:5 28:22,24 29:7 33:1 34:20 39:24 41:16 43:19 44:9,15,17 46:23 guard 41:6 guess 4:22 47:15 guessing 56:3 guidance 22:5 guidelines 55:18 guy 31:21	headquarters 39:19 health 4:2 15:1,3,6,8 15:11,12 17:10,17 17:17 18:1,7 19:7 19:15 20:18 21:23 21:24 35:18 36:14 38:6 54:5 hear 6:15 35:16 hearing 28:3 57:24 heart 9:12 Hello 3:1 help 34:15 52:7 hereinbefore 58:13 here's 10:5 He's 3:18,19,22,23 4:6,16 high 35:9 higher 29:17 Hiler 45:2,2,3,14 46:11 47:5,10,13 51:18,18 52:12 53:10,16,21 54:2 hire 41:23 history 3:18 12:12 Hoagland 9:21 hold 6:12 home 45:24 homes 45:17,21,23 46:9 Hook 55:13,13,24 56:4,7,13,16 hope 3:10 5:19 hopefully 42:23 46:10 hoping 51:10 hot 11:13 12:23 13:12 26:1,9 27:10 28:12 hour 40:8,9 hours 35:13,14 40:2 house 44:23 48:4 human 4:2 15:1,3,6,8 15:11,12 18:7 20:18 21:23,24 hydrocarbons 33:10 H-a-f-n-e-r 48:22 H-i-l-e-r 45:2	identified 7:12 46:15 identify 11:13 17:23 II 30:21 34:4 illustrated 14:9 impact 13:3 17:24 18:4 impacted 11:25 impacting 24:17 25:7 26:6 impacts 30:1 48:10 impeded 42:1 implement 23:13,18 25:22 implementability 23:12 implementation 23:6 implemented 21:13 22:18 23:15 27:20 important 17:19 19:17 incidental 16:1 included 10:20 57:2 includes 17:6 25:23 26:7,21 27:5 including 9:19 incomplete 34:1 increase 22:21 indicated 42:13 indoor 18:17 industries 52:22 infiltrating 18:17 inform 38:14 information 5:14 24:4 38:8 informational 38:9 informed 38:12 ingestion 16:1 ingress 42:4 inhalation 16:5,6 initial 11:6 initially 45:20 46:5 initiated 52:13 input 24:10 inspector 30:19 installed 28:17 29:5 34:13 50:14 institutional 25:11 insulation 50:16 intentional 53:18	54:4,11 interest 32:22 interested 46:7 58:20 interruption 42:12 intersection 10:4 interval 10:23,25 11:1 intervals 12:20 introduce 37:6 introduced 37:18 introduces 13:23 intrusion 18:12 19:3 44:23 45:16 invented 54:17,19 investigate 7:10 investigated 9:17 10:19 investigating 16:21 investigation 3:23 7:7,19 8:20 9:1,11 10:14 11:4 12:1,16 13:24 14:21 15:5 17:8,23 19:12 20:8 20:16 27:16 28:5 31:8 investigations 8:16 8:23 18:21 28:4 involved 5:8 29:24 involvement 3:3 5:7 5:11 Involvement 1:13 In-Situ 24:21 issue 43:7 49:1 issued 7:21 it's 6:19 7:4 8:10 9:12 14:11,20 17:19 20:25 21:2 27:12,21 29:3,18 31:14 32:14 32:18 34:8,12 36:4 39:16 40:6,19,19 41:1,3,4 42:2 44:3 44:11 45:12 47:15 48:22 49:22,23 50:5 51:24 52:10,16 53:13 54:23 56:8,8 56:14 I'll 5:25 8:22 48:6 54:20 I'm 3:2,3,17 4:14
<b>H</b>			
habitat 19:18,21,24 hadn't 54:19 HAFNER 48:22 49:5 50:5,11,18,25 51:7 51:12,16 Hahn 1:15 3:21 8:24 8:24 hall 38:21 handle 41:2 handout 3:11 handouts 56:23 happen 50:2 54:13 happening 32:8 happy 5:11 hard 49:24 harming 53:22 hasn't 48:17 hat 32:19 haven't 3:11 hazardous 52:23 55:19 56:11 hazards 17:20 head 54:21	<b>I</b>		
	idea 32:8 44:10		

5:11 6:16 8:24 14:3 14:25 20:4 26:8 27:24 30:22 31:16 32:3,15,16,19 34:3 35:22 47:5 54:13 55:9 56:3 I've 32:4	<b>layer</b> 14:12,16 <b>leave</b> 41:10 <b>leaves</b> 7:2 <b>led</b> 28:4 <b>leech</b> 18:3 49:3 <b>left</b> 22:19 53:2 <b>left-hand</b> 40:20 <b>letters</b> 46:4,5 <b>let's</b> 41:19 <b>level</b> 4:3 15:2 19:6 37:2 <b>levels</b> 17:16,17,22 18:10 19:23 20:21 37:21,21 <b>levied</b> 52:22 <b>Library</b> 5:15 <b>library's</b> 43:13 <b>License</b> 58:25 <b>licensed</b> 5:2 <b>light</b> 33:9,9,11,13,14 <b>lighter</b> 6:21 <b>likelihood</b> 18:12 <b>limited</b> 24:20 28:11 <b>Limited-action</b> 25:10 <b>line</b> 36:23 37:4 <b>list</b> 5:21,24 6:1 21:10 <b>lithology</b> 14:2 <b>litigation</b> 46:16 <b>little</b> 6:19 7:17 17:4 29:17 34:5 36:10 43:5 <b>live</b> 18:17 35:2 36:25 54:25 <b>located</b> 9:15 <b>locating</b> 55:7 <b>location</b> 10:16 45:20 <b>Lockwood</b> 4:19,21 4:24 54:12,12 <b>logistical</b> 43:7 <b>long</b> 32:2 42:2 48:9 49:2 53:11,13 <b>longer</b> 28:25 29:4 32:13 <b>long-term</b> 22:16 23:19 <b>look</b> 11:14 15:23 16:17 18:11 20:11 21:5,18 31:13 32:13 33:6 34:17 44:24	47:9 49:16 <b>looked</b> 11:22 15:25 16:18 17:5,6,9 19:22 27:1 29:8,9 <b>looking</b> 10:5 11:7 16:8 19:1 48:3 <b>lot</b> 10:8,9,10 12:22 16:22 19:17,21 26:1 26:3,9,15 30:5 33:19 36:15,17 37:19,19 40:14 42:1 42:19 46:6 54:8,8 55:20 56:11 <b>Lou</b> 8:22,24 <b>loud</b> 40:6 <b>Louis</b> 1:15 3:21 <b>love</b> 32:4 50:2 <b>low</b> 19:23 <b>luckily</b> 31:19	<b>Mayor</b> 4:19,21,24 34:9 38:12 42:10 54:12,13 <b>McKnight</b> 1:18 4:14 4:15 48:8,16,19 <b>mean</b> 35:6 44:6 53:24 <b>means</b> 16:9 17:24 <b>media</b> 10:19 <b>meet</b> 21:14 22:8 24:25 25:5,20 38:15 <b>meeting</b> 3:6 51:9 <b>meetings</b> 39:24 <b>members</b> 4:23 <b>Memorial</b> 9:24 <b>memorialized</b> 36:3 <b>mention</b> 5:13,17 <b>mentioned</b> 33:10 43:18 50:15 <b>met</b> 32:11 <b>methods</b> 55:1 <b>Michael</b> 14:22 <b>mid</b> 52:25 <b>middle</b> 41:11 <b>migrate</b> 20:20 <b>migration</b> 25:18 27:4 <b>Mike</b> 1:16 4:1 20:17 <b>milligram</b> 13:4,7,9 21:1 <b>mind</b> 30:24 47:25 <b>minimal</b> 42:18 <b>minimize</b> 30:2 <b>misconception</b> 34:9 34:18 <b>misconceptions</b> 6:21 <b>mobility</b> 22:24 <b>modifying</b> 23:22 <b>moment</b> 4:20 <b>money</b> 39:19 53:2 <b>monitor</b> 37:22 56:2 <b>monitoring</b> 12:9 35:4 35:5 36:23 37:4,25 38:1 47:16 55:24 <b>month</b> 39:3 <b>months</b> 18:22 39:2 42:22 46:3 <b>Morris</b> 9:17,25 12:13 <b>move</b> 23:2 34:5 49:22 <b>moved</b> 40:16 <b>moving</b> 32:21
<b>J</b>			
<b>Jackson</b> 55:14 <b>January</b> 45:11 <b>Jersey</b> 1:2,18 2:7,9 3:19 4:16 20:23 36:20 46:12 58:5 <b>Joe</b> 4:25 5:1 30:21 31:19 33:21 <b>John</b> 30:15 <b>July</b> 6:25			
<b>K</b>			
<b>keep</b> 29:3 30:5 38:12 38:21 39:10 <b>key</b> 49:1 <b>keys</b> 41:17 <b>kicked</b> 16:6 <b>kids</b> 41:19 <b>kilogram</b> 13:4,7,9 21:1 <b>kind</b> 9:11 14:20 15:24 17:1 18:21 47:23 52:15 56:11 <b>kinds</b> 16:18 <b>Klockner</b> 7:14,14,25 8:1,3,3,18,18 45:7,8 45:18,19 46:18,19 <b>Klockner's</b> 31:12 <b>know</b> 5:22 19:17 20:15 29:25 32:1,3 32:14 33:14,24 42:3 42:9,17,24 45:6 52:1,18 53:12,13,25 54:4 55:14,15 56:8 <b>known</b> 53:11			
<b>L</b>			
<b>laboratory</b> 12:7 <b>lack</b> 19:24 47:24 <b>land</b> 15:16 <b>lay</b> 15:16			
		<b>M</b>	
		<b>M</b> 9:21 <b>machine</b> 31:11 <b>Mack</b> 40:20 <b>mailed</b> 5:17 <b>mailing</b> 5:20,24,25 <b>Main</b> 3:9 9:13 10:4,6 45:6 51:22 <b>maintain</b> 23:20 <b>Main/Wall</b> 7:14,23 8:6,14,17,20 47:1 <b>making</b> 22:25 <b>manager</b> 1:14,15,17 3:19,24 4:7 6:17 8:25 <b>Manhattan</b> 5:16 <b>manufacturing</b> 31:11 <b>Maple</b> 10:11 12:22 13:12 26:2,9 27:10 45:21 <b>mapping</b> 11:16 <b>Mary</b> 54:12,21,21 55:2 <b>Massachusetts</b> 31:7 <b>material</b> 14:12 23:4,7 28:15 <b>materials</b> 56:11 <b>matter</b> 2:3 <b>maximum</b> 13:6	

<p><b>municipal</b> 9:15 10:9</p> <hr/> <p><b>N</b></p> <p><b>N</b> 1:10 2:2</p> <p><b>name</b> 8:5 30:11,15 34:25 35:1 47:7,23 48:21 56:21</p> <p><b>nation</b> 46:14</p> <p><b>nature</b> 40:4,9 52:11</p> <p><b>near</b> 25:25</p> <p><b>necessary</b> 7:18 9:6 41:1</p> <p><b>need</b> 29:16,18 36:22 36:23 38:13,14,18 38:24,25 39:3 41:22 42:11,16</p> <p><b>needed</b> 18:11</p> <p><b>needs</b> 16:25 17:2 27:18</p> <p><b>neighborhoods</b> 38:4</p> <p><b>neighbors</b> 5:23</p> <p><b>neither</b> 58:15,18</p> <p><b>never</b> 47:2</p> <p><b>new</b> 1:2 2:6,9 3:19 20:23 32:5 36:19,19 45:13 46:12 58:5</p> <p><b>newsletters</b> 38:20</p> <p><b>Nighttime</b> 40:5</p> <p><b>nine</b> 21:17 45:22</p> <p><b>noncarcinogenic</b> 17:10</p> <p><b>Northern</b> 1:18 4:16</p> <p><b>Notary</b> 2:6 58:5</p> <p><b>Notice</b> 6:4</p> <p><b>noticed</b> 31:7</p> <p><b>notices</b> 25:14,15</p> <p><b>November</b> 12:17</p> <p><b>nowadays</b> 56:12</p> <p><b>no-action</b> 24:24</p> <p><b>number</b> 21:2 57:13</p>	<p><b>occurring</b> 33:21</p> <p><b>October</b> 12:17</p> <p><b>offer</b> 53:5</p> <p><b>office</b> 5:16 31:2</p> <p><b>offices</b> 2:7</p> <p><b>official</b> 36:5</p> <p><b>off-gassing</b> 44:20</p> <p><b>off-site</b> 28:14 37:6 43:7</p> <p><b>oil</b> 10:21,22 12:4 44:11</p> <p><b>oils</b> 12:4</p> <p><b>okay</b> 31:23 35:25 57:14</p> <p><b>older</b> 12:13</p> <p><b>once</b> 29:24 35:25 36:1 37:18 38:11 39:19 43:24</p> <p><b>ones</b> 46:20,22</p> <p><b>one-foot</b> 10:23</p> <p><b>ongoing</b> 8:18 18:24 29:25 43:21</p> <p><b>on-site</b> 12:14 13:14 40:23 41:6</p> <p><b>open</b> 4:11 30:7,9</p> <p><b>operate</b> 29:5 32:10 42:6</p> <p><b>operating</b> 7:1 8:11 23:19</p> <p><b>operation</b> 6:25 30:4 45:12</p> <p><b>operator</b> 5:2</p> <p><b>opportunity</b> 23:24 53:5</p> <p><b>organic</b> 12:6,25 31:10 33:25</p> <p><b>organism</b> 54:24</p> <p><b>outside</b> 41:3</p> <p><b>overall</b> 21:22 23:3 48:12</p> <p><b>overhead</b> 3:14</p> <p><b>overheads</b> 3:15</p> <p><b>oversight</b> 51:5 53:6</p> <p><b>overview</b> 5:5 6:18</p> <p><b>owners</b> 29:23 46:20</p>	<p><b>paid</b> 51:20</p> <p><b>park</b> 9:24 14:11</p> <p><b>parking</b> 10:8,9,10 12:22 16:22 25:25 26:3,9,15 30:1,5 40:14 41:25 42:7,19</p> <p><b>part</b> 6:5,10 9:9,25 10:12 13:24 15:4 16:15 18:19 31:6 36:12 37:10,13 39:14 40:25 44:17 44:23 46:7 47:16 50:22 55:4 57:1,2</p> <p><b>participate</b> 46:10</p> <p><b>particle</b> 35:6</p> <p><b>particles</b> 33:23,23</p> <p><b>particular</b> 3:12 18:20 42:11</p> <p><b>particularly</b> 36:18</p> <p><b>parties</b> 46:15,19 47:4 47:6 51:4,19,20 52:2,4 53:4 58:17</p> <p><b>Partly</b> 16:5</p> <p><b>parts</b> 55:4</p> <p><b>party</b> 8:10 47:2 50:12</p> <p><b>path</b> 44:13</p> <p><b>pathway</b> 9:18</p> <p><b>pathways</b> 16:1,19 17:14</p> <p><b>patience</b> 3:2</p> <p><b>paved</b> 19:20</p> <p><b>pay</b> 47:17 52:7,15,16 52:17</p> <p><b>payers</b> 52:15</p> <p><b>payment</b> 46:17</p> <p><b>pays</b> 52:21,24</p> <p><b>PCE</b> 8:7 13:2,5,7 17:23 21:1 24:17 54:17</p> <p><b>people</b> 15:14,21,23 17:3 18:17,18 32:21 33:7,7 36:24 37:1 40:7 46:4,6,6,8,24 49:10 53:23 54:5,9 55:17 56:1,10</p> <p><b>perform</b> 9:10 53:5</p> <p><b>performed</b> 9:1 20:12</p> <p><b>performing</b> 23:9</p> <p><b>performs</b> 19:8</p>	<p><b>period</b> 6:2 24:10 57:22</p> <p><b>periodic</b> 43:11</p> <p><b>permanence</b> 22:17</p> <p><b>permanent</b> 22:22</p> <p><b>person</b> 30:10 57:5</p> <p><b>Peter</b> 5:2</p> <p><b>ph</b> 7:15,16</p> <p><b>phase</b> 9:9 11:5,6,17 12:2 20:5 21:4 27:14,15 35:25 39:17</p> <p><b>phases</b> 11:5</p> <p><b>phenomenon</b> 37:23</p> <p><b>phone</b> 5:24</p> <p><b>photographs</b> 13:13</p> <p><b>physical</b> 39:21</p> <p><b>pick</b> 38:21 39:10</p> <p><b>picnic</b> 32:7</p> <p><b>piece</b> 43:7</p> <p><b>piping</b> 11:9</p> <p><b>place</b> 35:8,14,19 36:22,24 39:20 50:24 58:13</p> <p><b>placed</b> 5:20,23 6:4</p> <p><b>plan</b> 3:7,13 27:20,21 35:18 36:15 37:13 38:6 39:25</p> <p><b>planning</b> 30:17</p> <p><b>plans</b> 5:18</p> <p><b>plant</b> 7:2</p> <p><b>play</b> 41:19</p> <p><b>please</b> 5:24 6:12 30:11 34:24 45:1</p> <p><b>plume</b> 7:24 8:11,13 44:7,8,14,16,21 45:7,8,15 46:19 51:20</p> <p><b>plumes</b> 43:20 45:5 46:15</p> <p><b>PNC</b> 10:7</p> <p><b>point</b> 3:14 14:4,22 17:19 31:23 32:9 43:23 45:7,9 48:18 48:19 49:16 55:3</p> <p><b>points</b> 29:11</p> <p><b>police</b> 9:23 29:23 39:25 41:2,14 42:3</p> <p><b>polish</b> 16:11 34:15</p>
<hr/> <p><b>O</b></p> <p><b>objective</b> 10:13 21:15 25:18,20</p> <p><b>objectives</b> 20:15</p> <p><b>observed</b> 20:21</p> <p><b>obviously</b> 29:18</p> <p><b>occupied</b> 9:22</p> <p><b>occurred</b> 48:11</p>	<hr/> <p><b>P</b></p> <p><b>P</b> 1:10 2:2</p> <p><b>package</b> 3:12</p>		

<p>polluter 52:21,24  polluters 52:14,17  pollution 54:18  populations 16:22  portion 45:19  pose 18:4  possibilities 18:11  possibility 31:19  possible 11:10 22:20  possibly 18:16  potential 9:18 11:8  11:23 12:10 15:25  20:20 21:12 26:18  26:22 27:4,13 28:16  29:15  potentially 26:6  53:17,22  potentially-respon...  8:10  Power 3:14  prefer 49:12  preferred 4:10 8:21  23:24 24:1  prefers 28:18  prepare 38:23 39:12  presence 13:11  present 13:1,5 14:3  14:15,25 27:8  presentation 3:14  6:14 20:13 24:9  pressure 31:18  pretty 19:12,19,20  42:2  prevent 21:24 23:15  25:13 27:3  preventing 55:15  previous 27:22  pre-design 27:15  primary 10:13 15:13  Prime 14:4,8  principal 52:17,24  printed 39:9  prior 47:9 58:6  private 50:12  probably 16:10 38:7  40:5,8 54:7 57:8  problem 50:7  procedures 53:25  process 5:9 8:12 15:4</p>	<p>15:5 20:6 24:1,14  29:21,25 30:23  31:11,20 40:11  49:16,25 50:3,14  51:6  processed 52:23  Professional 2:5 58:4  program 5:6,6 25:1  31:9  programs 25:14  progress 43:12,14  progresses 49:20  project 1:14,15 3:18  3:24 6:17 8:25  27:15 32:11 38:16  41:1 57:16  properties 45:15  property 9:22 10:12  14:15 46:20 48:1,3  proposed 3:7,13 5:18  protect 20:25 25:6,18  41:16  protection 20:24  21:23  protections 35:7  protective 21:2  provide 26:23 37:2  public 2:6 5:1,15 6:2  6:4 24:3,10 38:14  44:6 54:22,22 57:21  58:5  publicity 48:14  pumping 16:12,14,16  16:16  purchase 48:3  purpose 3:6 15:11  push 13:14  put 33:11 39:1,1  49:15  puts 39:18  putting 50:24  p.m 1:6 57:24</p> <hr/> <p style="text-align: center;"><b>Q</b></p> <p>quantity 23:4  question 15:13,17  31:5 32:25 33:3,5  34:24 35:3,22 37:11  39:15 44:5 45:1,5,6</p>	<p>45:9 47:16 51:13  53:10  questions 4:11 6:12  15:13 19:5 30:8,10  30:24 32:17 35:17  45:3 47:14 48:20  51:17 55:12 56:17  56:24,25 57:18  question-and-answ...  19:4  quick 6:18  quicker 32:23  quickly 37:20  Quinn 1:14 3:17 6:16  6:17 28:2 34:8  35:23 38:7 39:14  40:14,25 41:9,13  42:14 43:2,15 44:8  44:22 45:10,18  46:18 47:8,12,19  49:4,8 50:8,13,21  51:1,10,14,25 53:15  53:20,24 55:17 56:1  56:6,9,15  quite 52:18</p> <hr/> <p style="text-align: center;"><b>R</b></p> <p>R 1:10 2:2,2,4 58:1,3  58:25  railroad 7:18  random 37:25 38:3  range 21:5  rank 22:14  Raynag 7:16  reach 33:2 57:16  real 19:24  really 10:22 17:16  18:19 19:10,16  28:20 32:8,10,21  34:5 46:11  realty 7:16,19  rear 42:8  reason 48:1 52:2,4  receive 6:8  received 5:19  receptors 15:9 19:9  recognizance 11:5  recognize 4:18  recognized 18:9</p>	<p>recommendations  24:5  record 6:5 7:12,20  36:4,6 49:15 57:3  records 33:6  reduce 37:8  reducing 23:3  reduction 22:23 25:3  refer 44:15  reference 19:14  refers 22:3 23:6  regarding 19:2 57:16  regards 45:14  region 30:21 34:4  36:18  regional 36:4 57:3  Registered 2:5 58:4  regulatory 22:3  related 9:3  relative 58:16,18  released 37:12  relevant 22:2  rely 42:7  remaining 22:17  remedial 3:23 7:7  8:23 9:1 10:13 11:4  14:21 15:5,18,21  17:22 20:8,9,10,15  21:12,14 22:6 25:20  28:5 36:9,12,13  43:17,22,24 44:1  49:18  remediate 25:12 36:7  remediation 1:18  3:20 4:16 24:21  32:25 35:3,20 47:17  remedy 4:10 8:21  20:6,12 22:18,22  23:19,24 24:1,8,12  28:1,18,19 29:12,13  35:25 36:2 49:12,13  49:14,17  remember 54:14  removal 28:12  remove 26:4 27:3  28:21 29:15,19  31:20  removed 7:3,4 23:8  31:10</p>
---	---	---	---

<p>remover 16:11  removing 29:14  33:25  reply 46:7  report 43:12,14 44:1  Reporter 2:5,6 58:4,4  reports 28:9  repository 5:14  representative 4:13  45:24  required 43:16  requirement 43:11  requirements 22:3,4  56:10  requires 25:1  research 31:21  residents 38:16  resides 32:1  resources 11:22,23  11:24 12:10  respectfully 32:7  response 30:20 56:18  56:20  responsibilities 56:2  responsible 28:25  40:24 46:14,19 47:2  47:11 51:4,19,20  53:4  Responsiveness 6:6  57:1  rest 34:16  restrictions 23:14  25:12,15  results 12:24 17:8,22  18:6  retained 25:2  retired 33:8  return 22:22  review 23:24  reviewed 51:5  reviewing 24:3,4  reviews 43:16  RI 9:5  rid 28:7 49:1 55:23  RIFS 15:4  rig 13:14,19,20  right 3:22 4:2 10:3  15:15 26:9,14 36:25  37:1 41:13 42:3</p>	<p>49:22  rigs 40:16 41:17  42:16  risk 1:16 4:3,4 14:22  14:24 15:2,12 17:10  17:16 18:7,8,20  19:7 20:8,16 21:25  22:22 23:6  risks 15:14,18,20  17:15,17,18,20 18:2  20:1,17 21:24 22:17  22:19,21 23:8 25:3  road 40:12  roads 40:3,19  Robert 1:17 4:5  Rockaway 1:1,2,4  2:7,8 3:4 5:14 6:17  32:22 33:18 47:17  54:13  room 42:16 54:9  Rossi 5:1  rotosonic 13:19  Roxbury 33:12  RPR 58:25  rule 6:11  running 50:9  rush 40:8,9</p> <hr/> <p style="text-align: center;"><b>S</b></p> <p>S 1:10 2:2  safety 35:18 36:15  38:6  sample 12:24 13:7  43:4 45:24  samples 12:2,5,18,19  13:17,21 26:11 32:6  32:6,7 45:25  sampling 12:9,16,21  13:11,14,20 27:17  30:20  sand 14:14,17  saw 14:14 31:24  saying 32:15  scenario 25:17  scenarios 15:24  Schaefer 4:24 41:24  41:24,25 42:25  school 40:2  Scott 45:3 51:18</p>	<p>scrapbook 9:23  screen 11:12  screened 21:7  screening 4:3 15:1  19:6 24:14  second 7:20 15:17  22:1,23 24:20 31:21  35:20,21,22 39:14  55:5  section 1:18 3:20  4:16  securing 41:15  security 40:23 41:6  see 3:16 5:12 9:14  16:13,17 32:6,23  33:20 34:5 42:16  48:10  seeing 18:10 33:17  seek 5:7  seen 13:15 37:18  select 21:19 36:2  selected 24:8 28:1  36:1  selection 24:11  send 12:5 46:3 57:7,8  57:12,12  sensitive 11:20 40:10  sent 7:4 46:5  separate 8:15  September 6:3 49:10  57:22  SERAFINA 2:4 58:3  58:25  service 9:20  session 19:4 38:8  sessions 38:9  set 20:22 58:13  settle 52:4  settled 47:4 52:6  settlement 47:9 50:23  51:23 52:1  settlements 46:17  shallow 10:21,23  12:3 13:17,19  She's 4:19  shoot 35:21  shop 9:23 35:8,10  shops 9:20  short 21:10 33:18</p>	<p>shortens 29:6  Shorthand 2:5 58:3  short-term 23:5  42:22  show 26:11 55:22  showing 14:7  shown 9:11 27:22  shows 27:9  shutting 37:7  side 7:17 34:3 36:25  37:1 55:9  sight 11:5  signed 5:20 7:12 36:4  57:3  significant 11:23  12:11  signify 44:17  sir 34:24 35:17  sit 52:10  site 1:1 3:5,18,19  4:10 5:9,10 6:18,19  8:18 13:22,25 15:22  16:8 17:12 20:2  21:8 24:12 25:21  31:9 36:7 37:4,7  41:11 43:19,22 48:5  48:8,12 56:8,14  57:19  sites 32:5 36:18,19,20  43:12  sits 44:13  situation 15:15 51:11  Sivak 1:16 4:1 14:22  14:24 35:16,24 38:1  38:5 48:6 51:2  52:20  six 39:2  skin 16:4,5  sleep 40:7  slick 44:11  slide 27:9,22 56:22  small 48:11 52:5  smaller 47:4  smart 40:6  smooth 49:22  soil 9:3,8 10:15,20,20  10:21,23,25 11:1,11  11:14,15 12:2,5,15  12:19,24 13:1,3,17</p>
--	---	---	--

13:20,21,25,25 14:5 16:2,3,4 17:21,25 18:14 19:11 20:24 21:7 24:16,22 25:13 25:24,24 26:3,16 27:6,22 28:12,16,21 29:16 31:3 32:1,2 35:6 37:13 46:21 48:25,25 49:1,2,6 <b>soils</b> 3:8 12:2,3 16:21 17:4,5,6 20:19 21:1 21:14,20 23:3 24:23 25:7 26:24 36:7,16 37:7 <b>sold</b> 46:24 <b>somebody</b> 52:8 55:21 <b>someplace</b> 41:12 <b>sorry</b> 4:14 35:22 <b>sort</b> 19:14 30:23 32:17,18 33:25 45:15 <b>sound</b> 54:24 <b>source</b> 7:13 8:15 9:7 28:22 29:3,6 43:20 <b>sources</b> 11:10 <b>special</b> 56:13 <b>species</b> 11:19 <b>specific</b> 38:11 <b>specifics</b> 52:1 <b>spill</b> 16:9 <b>spins</b> 41:22 <b>spot</b> 12:23 13:12 26:2 26:9 27:10 28:12 43:3,3 <b>spots</b> 11:13 <b>stabilizing</b> 23:1 <b>staff</b> 4:23 <b>stage</b> 41:15 <b>stand</b> 4:20 30:11 <b>standing</b> 3:22 <b>stands</b> 4:21 <b>start</b> 8:11 15:3,10 39:16 48:23 49:6,16 <b>started</b> 43:18 45:12 <b>state</b> 2:6 22:4 23:23 30:11 34:25 46:13 48:21 56:2 58:5 <b>stated</b> 49:8 <b>statement</b> 53:19	<b>State's</b> 23:23 <b>stations</b> 9:20 <b>stenographer</b> 6:9 30:12 <b>stenographically</b> 2:3 58:12 <b>step</b> 20:14 36:8 <b>steps</b> 50:3 <b>stick</b> 33:19 <b>Stickel</b> 7:15 45:19 <b>stood</b> 31:1 <b>stop</b> 33:4 39:9 40:17 <b>storm</b> 11:8 <b>street</b> 2:8 3:8,9 7:14 7:16,24 8:6,9,14,17 8:20 9:12,13 10:5,6 26:2,16 27:10 35:2 36:7 41:11 42:4 45:7 47:1 51:21,22 <b>streets</b> 38:4 <b>strict</b> 55:18 <b>stricter</b> 56:11 <b>structures</b> 18:14,16 <b>studies</b> 19:21 <b>study</b> 1:17 4:6,7 7:8 9:2,10 10:2 11:21 14:6 19:18 20:5,7 21:5 23:25 24:5,13 28:6 31:7 46:2,8 47:24 <b>stuff</b> 34:17 41:15 44:23 49:24 50:17 <b>subjected</b> 54:9 <b>subsoil</b> 13:5 <b>subsurface</b> 10:21,21 10:24,25 12:3,4,19 17:2,7 <b>suburban</b> 19:19 <b>suggest</b> 37:5 <b>suggesting</b> 23:7 <b>suggests</b> 49:21 <b>summary</b> 6:6 12:15 14:20 57:1 <b>Superfund</b> 1:1 3:5 5:6 25:1 31:8 32:5 43:12 48:5 52:11,21 53:9 <b>Superfunds</b> 32:4 46:12	<b>Superintendent</b> 5:1 <b>sure</b> 5:25 7:1 29:24 34:18 36:24 40:1 41:7,17 43:5,6 44:8 53:20 <b>surface</b> 10:20,22 11:2 12:3,18 13:4 14:9 14:13,19 16:21 17:5 17:7 <b>survey</b> 11:12,18,22 <b>SVE</b> 24:22 28:16 <b>sworn</b> 58:7 <b>system</b> 6:24 7:23 8:14 23:20 26:7 28:16 33:12,24 34:1,13,20 37:14 45:11 <b>systems</b> 8:7 29:4 50:23 <hr/> <b>T</b> <hr/> <b>T</b> 1:10 2:2,2 58:1,1 <b>table</b> 13:21 14:6,18 <b>take</b> 12:5 19:22 24:10 30:12 41:16 42:11 42:21,25 45:23 49:11 <b>taken</b> 2:3 3:10 6:9 15:19,21 42:20 58:12 <b>takes</b> 32:2,17 <b>talk</b> 14:22 19:3 20:4 20:13 27:25 38:12 <b>talked</b> 17:14 <b>talking</b> 10:4 19:19 33:19 41:14 43:18 48:11 50:15 <b>tanks</b> 11:8 <b>tax</b> 52:15,21,24 <b>TCE</b> 8:4 54:17 <b>team</b> 30:21 31:6 <b>Tech</b> 3:24 4:7 8:25 20:4 <b>technique</b> 11:12 <b>techniques</b> 11:7 <b>technologies</b> 20:11 21:6,11 <b>technology</b> 31:8 55:3 55:10 <b>tell</b> 32:21 34:3 39:16	44:16 <b>telling</b> 51:13 <b>temporarily</b> 40:16 <b>ten</b> 11:1 13:5,17 56:12 <b>tenants</b> 46:21 <b>ten-foot</b> 10:24 <b>terms</b> 14:1 <b>terrestrial</b> 19:18 <b>test</b> 53:25 54:16,16 54:19 <b>tested</b> 45:16 54:15 <b>testify</b> 58:8 <b>testimony</b> 58:11 <b>Tetra</b> 3:24 4:7 8:25 20:4 <b>Tetrachloroethene</b> 8:5 13:2 <b>thank</b> 3:2 5:4 34:6,7 34:25 47:20 51:16 54:11 55:11 56:16 57:10,20,23 <b>that's</b> 3:24 8:2,17 17:1 18:1 19:15 21:24 22:18 23:17 24:7,8 26:5 27:19 27:21 28:13,18 31:22 32:7 33:16 34:21 35:15 36:3,12 37:13 43:8,25 44:9 44:13,16,24 45:9 47:5 48:14 49:1,14 49:24 50:9,18 52:11 55:5 <b>there's</b> 4:22 18:2 19:17,20 25:8 26:18 37:19,19 38:13 43:19 49:23 53:2 55:20 <b>they'll</b> 41:2,16 47:10 <b>they're</b> 5:25 8:7 17:15 19:13 21:7 43:15,16 46:20,24 50:25 <b>they've</b> 46:23 <b>thing</b> 19:16 37:15 40:6,22 41:4 <b>things</b> 11:9 30:3,3 32:10 37:8 38:10
--	---	--	--

40:3,8,9,10 41:18 42:9 55:7 <b>think</b> 33:3,16,19 34:8 34:9 42:11 44:10 48:9 52:25 54:10 <b>third</b> 24:21 25:23 29:12 <b>thoroughfare</b> 42:2 <b>thought</b> 30:22 <b>thousand</b> 33:14 <b>thousands</b> 32:6 54:5 <b>threatened</b> 11:18 <b>three</b> 7:13 19:9 30:18 42:22 <b>threshold</b> 21:22 22:7 24:25 <b>time</b> 6:24 7:1 24:3 29:6 30:3,11 31:12 31:17 32:11,12 35:23 36:21 46:22 48:9 54:14,15 58:13 <b>timeline</b> 43:8 48:18 49:19 <b>times</b> 37:20 <b>timing</b> 39:15 49:22 <b>today</b> 6:4 49:11 <b>tomorrow</b> 50:3 <b>tonight</b> 5:12 6:8 7:9 8:19 14:25 18:23 28:3 36:2 43:18 <b>tonight's</b> 3:6 <b>top</b> 14:6,17 <b>topics</b> 38:11 <b>topographic</b> 11:16 <b>totally</b> 26:17 <b>town</b> 34:10 38:21 45:20 <b>toxic</b> 23:1 <b>toxicity</b> 22:24 <b>tracks</b> 7:18 <b>traffic</b> 40:17 <b>transcript</b> 6:10 57:2 58:11 <b>transection</b> 14:8 <b>travels</b> 44:12 <b>treat</b> 50:19 <b>treated</b> 23:8 26:16 27:19 34:12,12 49:6 <b>treating</b> 28:25 32:12	33:4 <b>treatment</b> 6:24 7:21 7:23 8:7,13 21:5 22:24 23:20 25:24 26:23 28:15 29:4,6 29:7 39:25 45:10 50:8 <b>Trichloroethene</b> 8:4 <b>tried</b> 45:23 <b>truck</b> 40:17,20 <b>true</b> 58:11 <b>truth</b> 58:8,8,9 <b>try</b> 9:7 10:15 11:12 30:2,5 31:2,4,13 36:10 40:7 48:6 <b>trying</b> 30:3 47:6 55:8 <b>turn</b> 8:22 20:2 27:24 40:20 <b>turned</b> 45:11 <b>Twenty</b> 43:2 <b>twice</b> 38:15 <b>two</b> 4:25 8:7,15 9:20 11:4 12:19 15:12 21:21 22:9 23:22 26:8 27:2 28:20 35:17 39:3 43:19,20 <b>type</b> 10:16 18:9 19:7 32:1 35:4,18 38:20 <b>types</b> 9:19 25:15 36:22,23 <b>typically</b> 37:6	<b>updated</b> 39:10 <b>updates</b> 38:24 39:1,8 <b>usable</b> 19:18 <b>use</b> 13:18 21:18 30:6 33:12 40:3,18 42:4 47:24 <b>USEPA</b> 1:16,18 <b>usually</b> 39:1 41:16 <b>utilities</b> 17:2 <b>utility</b> 17:1 <b>UV</b> 33:9,9,11,12,14	29:2 31:18 32:12 33:4,23 34:11,15,15 34:19 44:11,11,12 44:13 50:20 53:22 54:1,15,23 <b>way</b> 15:15,16 29:8,19 31:22 35:16 39:9 44:10 <b>ways</b> 28:7 <b>wear</b> 32:19 <b>Wednesday</b> 1:5 2:9 <b>Weekly</b> 39:8 <b>weeks</b> 39:3 <b>Wellfield</b> 1:1 3:4 <b>wells</b> 9:15 26:22 27:23 50:17 <b>went</b> 24:13 45:20 <b>weren't</b> 33:7 46:6,7 <b>wetting</b> 37:7 <b>we'll</b> 4:1,5,9,11 6:14 20:13 30:2,7 34:17 38:7 39:20,23 49:24 <b>we're</b> 7:8 8:19 10:3 15:2,10 16:7 18:10 19:1,19 24:3 29:25 30:9 31:4,14,23 32:16,21 33:19 34:21 36:9 40:7,9 46:3 48:11 49:9 51:10 55:3,5,7,8,15 57:17 <b>we've</b> 38:9 <b>what's</b> 7:6 32:8 35:14 38:22 39:11 44:20 <b>wherewithal</b> 52:3,6 53:7,8 <b>windows</b> 41:18 <b>wisdom</b> 31:25 <b>witness</b> 58:7 <b>won't</b> 25:6 51:11 <b>word</b> 44:6 47:24,25 <b>work</b> 9:3,7,10 11:3,6 11:25 17:1,3 18:18 23:9 26:12 35:13,15 35:19,24 37:1 39:5 39:10,21 41:5 42:17 42:17,21 48:2 52:10 55:10 <b>worked</b> 30:21	
	<b>U</b>	<b>V</b>		
	<b>ultimate</b> 28:22 <b>ultimately</b> 24:15 <b>unacceptable</b> 17:17 18:1 20:17 22:10 <b>underground</b> 11:8 <b>underlying</b> 14:13,16 <b>underneath</b> 18:14,16 26:24 <b>understand</b> 36:21 52:13,16,18 <b>underway</b> 24:2 <b>Unfortunately</b> 36:16 51:14 <b>Union</b> 2:8 9:21 35:2 <b>unknown</b> 51:23,24 <b>unpaid</b> 32:19 34:4	<b>vague</b> 48:23 <b>values</b> 22:5 48:1 <b>vapor</b> 18:12 19:2 24:22 25:24 26:16 27:6,22 28:12,16 29:16 31:3 35:7,10 44:23 45:16 <b>vaporized</b> 16:9 <b>vaporizing</b> 44:20 <b>vapors</b> 11:15 16:13 16:15,16 37:11,15 37:18 <b>various</b> 9:18 22:13 <b>vegetated</b> 14:11 <b>version</b> 7:9 <b>viable</b> 19:24 <b>Vicente(ph)</b> 4:25 <b>view</b> 10:5 <b>volatile</b> 12:6,25 16:6 16:8,14 19:23 31:10 33:25 <b>volatilizing</b> 18:13 <b>volume</b> 22:24 35:10		
		<b>W</b>		
		<b>Wall</b> 3:8 9:12 10:5,6 36:7 42:4 <b>want</b> 20:9 32:22 34:2 34:17 40:7 47:24 55:14 57:8,11 <b>wanted</b> 18:22 33:17 <b>wasn't</b> 7:18 18:19 <b>waste</b> 52:23 55:19,20 <b>watch</b> 12:9 <b>water</b> 5:3 6:23 7:1 13:21 14:6,18 28:25		

workers 16:23,25 17:12,13 23:9 working 29:22 39:23 Works 5:1 54:22,22 worried 31:16	2006 1:5 2:9 13:10 21 10:11 12:22 13:12 26:2,9 27:10 21-25 2:8 23 1:5 2:9 55:13 27 32:13,14 33:2,6		
<b>X</b>	<b>3</b>		
XI01637 58:25	30 32:15 46:5 300 5:17 33 55:5		
<b>Y</b>	<b>4</b>		
yards 43:1,2 year 26:13 45:12 years 30:17 31:1,3,15 32:11,13,14,15 33:1 33:2,5,6,11 34:14 44:1,2,3 50:6 51:8 54:23 55:5 56:5,12 York 32:5 36:19 you're 10:3 16:12,13 16:15 42:25 45:6 51:12 55:24	40 11:2 13:22 14:18 43:1 46 32:7 48 12:19		
<b>Z</b>	<b>5</b>		
zero 10:22 ZINCKGRAF 2:4 58:3,25	50 54:23		
<b>S</b>	<b>7</b>		
\$2,000 33:15 \$27,000 25:22	7:15 1:6 2:10 73 13:8		
<b>1</b>	<b>8</b>		
11th 6:3,3 49:10 57:22 120 46:12 13 30:17 14 13:7 15 31:1,15 32:11 33:1 50:6 56:12 17 45:21 19 12:18 13:6 32:6 1980 6:23 53:23 54:6 54:7 1981 6:25 53:12 1991 7:21 9:5	8:23 57:24 80 53:13 800 57:13		
<b>2</b>	<b>9</b>		
2 10:9 20 43:3 44:3 2003 12:18	90 31:12 90s 52:25 96 52:25		

APPENDIX IV

ADMINISTRATIVE RECORD INDEX

ROCKAWAY BOROUGH WELLFIELD  
OPERABLE UNIT 3  
ADMINISTRATIVE RECORD  
INDEX OF DOCUMENTS

3.0 REMEDIAL INVESTIGATION

3.4 Remedial Investigation Reports

- P. 300001 - Report: Final Remedial Investigation Report for Remedial Investigation/Feasibility Study, Rockaway Borough Wellfield Superfund Site, Wall Street/East Main Street Site, Rockaway Borough, Morris County, New Jersey, prepared by Tetra Tech FW, Inc., prepared for U.S. EPA, Region 2, February 2005.  
300735

4.0 FEASIBILITY STUDY

4.3 Feasibility Study Reports

- P. 400001 - Report: Final Feasibility Study Report for Soils at Rockaway Borough Wellfield Superfund Site, Wall Street/East Main Street Site, Morris County, New Jersey, prepared by Tetra Tech FW, Inc., prepared for U.S. EPA, Region 2, August 2006.  
400129

10.0 PUBLIC PARTICIPATION

10.9 Proposed Plan

- P. 10.00001- Superfund Program Proposed Plan, Rockaway Borough Wellfield Superfund Site, prepared by U.S. EPA, Region 2, August 2006.  
10.00011

APPENDIX V

NJDEP'S LETTER OF CONCURRENCE



**State of New Jersey**  
DEPARTMENT OF ENVIRONMENTAL PROTECTION

**JON S. CORZINE**  
*Governor*

**LISA P. JACKSON**  
*Commissioner*

Mr. George Pavlou, Director  
Emergency and Remedial Response Division  
U.S. Environmental Protection Agency  
Region II  
290 Broadway  
New York, NY 10007-1866

SEP 27 2006

Re: Rockaway Borough Wellfield Superfund Site  
Record of Decision

Dear Mr. Pavlou:

The New Jersey Department of Environmental Protection (NJDEP) has reviewed the "Record of Decision, Operable Unit Three, Rockaway Borough Wellfield Superfund Site, Rockaway, Morris County, New Jersey" prepared by the U.S. Environmental Protection Agency (USEPA) Region II in September 2006 and concurs with its selected remedy to address groundwater contaminated with volatile organic compounds at the site. The selected remedy addresses the contamination source for the Wall Street/East Main Street area of the site.


The major components of the selected remedy include:

- Excavation of an estimated 40 cubic yards of soil contaminated with volatile organic compounds;
- Off-site treatment and/or disposal; and,
- Soil Vapor Extraction, if necessary, to augment the soil excavation.

NJDEP appreciates the opportunity to participate in the decision making process to select an appropriate remedy and is looking forward to future cooperation with USEPA to implement the selected remedy.

If you have any questions, please call Edward Putnam, Assistant Director of the Remedial Response Element, at 609-984-3078.

Sincerely,



Irene Kropp, Assistant Commissioner  
Site Remediation and Waste Management Program

- C: Edward Putnam, Assistant Director, Remedial Response Element, NJDEP
- Carole Petersen, Chief, New Jersey Remediation Branch, USEPA